

STATE OF WASHINGTON DEPARTMENT OF ECOLOGY

1315 W. 4th Avenue . Kennewick, Washington 99336-6018 . (509) 735-7581

April 22, 2004

Mr. Roy Schepens, Manager Office of River Protection United States Department of Energy P.O. Box 450, MSIN: H6-60 Richland, Washington 99352-0550

Mr. Keith Klein, Manager Richland Operations Office United States Department of Energy P.O. Box 550, MSIN: A7-50 Richland, Washington 99352-0550

Mr. James Henschel, Project Director Bechtel National Inc. 2435 Stevens Center Place, MSIN: H4-02 Richland, Washington 99352-0550

Dear Messrs. Schepens, Klein, and Henschel:

Re: Completion of the April 2004 Modification of the Waste Treatment and Immobilization Plant Dangerous Waste Permit

This letter serves to notify you of the Washington State Department of Ecology's (Ecology) final permit decision to incorporate a number of design packages for the Waste Treatment and Immobilization Plant (WTP) into Part III, Chapter 10, of the Hanford Facility's Dangerous Waste Portion of the Resource Conversation and Recovery Act Permit for the Treatment, Storage, and Disposal of Dangerous Waste (WA7890008967). Because there were no comments received during the public comments period, this permit decision will become effective immediately upon receipt of this Notice of Decision.

The packages included in this modification are:

 Pretreatment Facility (PTF)-014 – Tank System for the High-Level Waste (HLW) Lag Storage and Feed Blending Process System (HLP) System



EDMC

- PTF-017 Tank System for the Treated Low Activity Waste (LAW) Evaporation Process (TCP) System
- PTF-025 Tank System Ancillary Equipment for the Ultra Filtration Process (UFP) System
- PTF-026 Tank System Ancillary Equipment for the HLP System
- PTF-032 Tank System for the TCP System
- PTF-040 Tank System for the UFP System
- Low-Activity Waste (LAW)-006 Tank System for the LAW Melter Offgas (LOP) System on the + 3 foot elevation
- LAW-009 Tank System for the Radioactive Liquid Waste Disposal (RLD) System on the +3 foot elevation
- LAW-010 Tank System for the LAW Concentrate Receipt Process (LCP) System on the +3 foot elevation
- LAW-011 Tank System for the LAW Melter Feed Process (LFP) System on the +3 foot elevation
- LAW-017 Miscellaneous Treatment Unit Subsystems for the LOP System on the +3 foot elevation
- HLW-009 Tank System Ancillary Equipment for the HLW Vit Primary Offgas Treatment (HOP) System SBS Condensate Receiver Vessels
- HLW-010 Miscellaneous Treatment Unit Subsystems for the HOP Silver Mordenite Units on the 21 foot elevation
- HLW-038 Double Wall Pipe for the RLD & HCP Systems on the 21 foot elevation
- Engineering Specifications for Field Applied Special Protective Coating for Secondary Containment Areas (WTP-3PS-AFPS-TP006)

Other changes to the Permit include:

- Incorporation of previously approved Class 1' and Class 2 Permit modifications including changes to Chapter 4.0 of Appendix 51
- Incorporation of new information into the Permit tables

The document Engineering Specifications for Field Applied Special Protective Coating for Secondary Containment Areas (WTP–3PS–AFPS–TP006) is approved and is being incorporated into the Permit. However, Ecology is **NOT GIVING APPROVAL** to install any coatings in regulated areas until Ecology has received and approved a demonstration showing the special protective coating and polymeric filler combination are "an equivalent device as approved by the department" pursuant to Washington Administrative Code 173-303-640(4)(d)(iv). Ecology will provide the details of the contents of the demonstration to the Permittees separately.

Messrs. Schepens, Klein, and Henschel April 22, 2004 Page 3

The final permit modification package consists of the Statement of Basis and the revised WTP unit-specific conditions and appendices on a CD-ROM. The location of the page changes and design information are noted in the Statement of Basis for the modification. Changes to the permit conditions are noted with single-line strike out for text deletions and double-underline for text additions.

Hard copies of the information in the final WTP permit modification will be available at the Ecology Administrative Record in Kennewick, Office of River Protection Administrative Record, and the Hanford Public Information Repository in Richland.

Ecology would like to remind the Permittees that the approvals granted in this modification are for the purpose of allowing construction to proceed on a specific part of the WTP (e.g., specific secondary containment areas, tanks, ancillary equipment). If other portions or equipment were mentioned in the documents approved, our approval does not extend to other portions of the WTP treatment systems. For example, the System Description for the HOP and Process Vessel Vent (PVV) Systems (24590-HLW-3YD-HOP-00001) has been incorporated into the administrative record. Although the document discusses the off-gas treatment system for completeness, our approval does not constitute an approval of the adequacy of the off-gas treatment system. The permit documents also indicate the instrumentation that the Permittees believe is regulated. Ecology does not currently have enough information to make a determination as to the regulatory status of the instrumentation.

If there are any questions regarding this letter, please call Ms. Suzanne Dahl at (509) 736-5705 or Mr. Steve Skurla at (509) 736-3011.

Sincerely,

Michael A. Wilson

Program Manager

Nuclear Waste Program

MW:SS:jc

Enclosures

See cc next page

Messrs. Schepens, Klein, and Henschel April 22, 2004 Page 4

Nick Ceto, EPA cc: Joel Hebdon, USDOE-RL Tony McKarns, USDOE-RL Wahed Abdul, USDOE-ORP John Eschenberg, USDOE-ORP Pete Furlong, USDOE-ORP Lori Huffman, USDOE-ORP Bruce Nicoll, USDOE-ORP Jim Rasmussen, USDOE-ORP Ro Vinson, PEC Todd Martin, HAB Ken Niles, ODOE Bill Clements, BNI Tim Horst, BNI Bob Lawrence, BNI Phil Schuetz, BNI Fred Beraneck, WGI Phil Peistrup, WGI Steve Piccolo, WGI Stuart Harris, CTUIR Pat Sobotta, NPT Russell Jim, YIN

cc/enc: Cathy Massimino, EPA

Environmental Portal

Ecology Administrative Record, Kennewick Hanford Public Information Repository, Washington State University

USDOE Administrative Record, Richland



Statement of Basis

For the Modification of
Waste Treatment and Immobilization Plant-Specific Conditions
in the Dangerous Waste Portion of the
Hanford Resource Conservation and Recovery Act Permit

April 2004 Publication No. 04-05-001 Revision 1

STATEMENT OF BASIS FOR MODIFICATION OF THE DANGEROUS WASTE PORTION OF THE RESOURCE CONSERVATION AND RECOVERY ACT PERMIT FOR THE TREATMENT, STORAGE, AND DISPOSAL OF DANGEROUS WASTE, PART III, CHAPTER 10 (WA7890008967), WASTE TREATMENT AND IMMOBILIZATION PLANT

Publication Number 04-05-001 Revision 1

Permittees

United States Department of Energy (Owner/Operator) Office of River Protection/Richland Operations Office P.O. Box 550 Richland, Washington 99352

Bechtel National, Inc. (Co-Operator) 2535 Stevens Center Place Richland, Washington 99352

This Statement of Basis has been developed by the Washington State Department of Ecology (Ecology) in accordance with the requirements of Washington Administrative Code (WAC) 173-303-840(2)(f)(iv). Its purpose is to present information on Ecology's tentative decision to modify Part III, Chapter 10, Waste Treatment and Immobilization Plant (WTP) of the Hanford Facility's Dangerous Waste Portion of the Resource Conservation and Recovery Act (RCRA) Permit for the Treatment, Storage, and Disposal (TSD) of Dangerous Waste, hereafter called "the Permit". This modification includes supporting technical information and engineering drawings for construction on the regulated portions of the WTP Pretreatment Building, Low Activity Waste Building, and High Level Waste Building. Additional changes incorporate previously approved Class 1' and Class 2 modifications into the Permit and changes to supporting information. Pursuant to WAC 173-303-830(3), only the conditions that are subject to this modification are reopened for comment.

Ecology has elected to prepare a Statement of Basis pursuant to WAC 173-303-840(2)(f)(iv) rather than a Fact Sheet. A Statement of Basis was prepared for previous major WTP Permit modifications. This process is being followed for permit modifications initiated by Ecology to incorporate similar design package information and other changes to the WTP Permit conditions. The September 25, 2002, Fact Sheet is available from Ecology upon request (Ecology Publication Number 01-05-006).

This Statement of Basis is divided into four sections, which include:

- 1.0 Hanford Facility Permit Background
- 2.0 The WTP Permitting Process
- 3.0 Procedures for Reaching a Final Decision on the Draft Permit
- 4.0 Proposed Modifications to the Hanford Facility Permit

1.0 Hanford Facility Permit Background

Ecology issued the Permit for the Hanford Facility in 1994. The Permit provides standard and general facility conditions, as well as, unit-specific conditions for the operation, closure, and post-closure of mixed and dangerous waste TSD units at Hanford.

The Permit is normally modified annually to incorporate newly permitted units, reflect Class 1/2/3 Modifications, and include minor changes in grammar, consistency, and presentation. The Washington State

Dangerous Waste Regulations in WAC 173-303-830 describe the types of changes or modifications that may be made to a dangerous waste permit issued by Ecology.

Approximately 50 TSD units at Hanford are operating or closing under RCRA interim or final status standards.

Conditions of the Permit are presented in six parts:

- Standard Conditions (Part I)
- General Facility Conditions (Part II)
- Unit-Specific Conditions for Final Status Operations (Part III)
- Corrective Action for Past Practices (Part IV)
- Unit-Specific Conditions for Units Undergoing Closure (Part V)
- Unit-Specific Conditions for Units in Post-Closure (Part VI)

As noted above, the WTP TSD Unit was added to the Unit-Specific Conditions for Final Status Operations (Part III) portion of the Permit on September 25, 2002. The permit modification was effective on October 25, 2002. The WTP Unit is currently being constructed under final status standards.

2.0 The WTP Permitting Process

The permitting of the WTP Unit is using a phased (or stepped) approach. The first phase was completed on September 25, 2002, with issuance of a final permit for beginning construction of the WTP Unit Low Activity Waste (LAW) and High Level Waste (HLW) buildings and a compliance schedule to provide additional detailed information to Ecology. The compliance schedule addresses submittal of information necessary for construction of the rest of the WTP Unit, and eventual operation. The second phase of permitting is implementation of the compliance schedule, which requires design and other information be submitted before regulated portions of the WTP Unit are constructed. The third phase of permitting is implementation of the last portion of the compliance schedule, which requires updating portions of the Dangerous Waste Permit Application that were incorporated into the final Permit. These portions of the Permit are more administrative in nature, and can not be completed before the design is nearly complete (e.g., Contingency Plan, Closure Plan, Training Plan). It is anticipated that at the completion of these three phases, the WTP Unit will be in compliance with all the relevant requirements of WAC 173-303, and after receiving written permission from Ecology, can begin storage or treatment of dangerous and/or mixed waste. For more details on the WTP permitting process, see the September 25, 2002, Fact Sheet (Ecology Publication Number 01-05-006).

The design submittals (second phase described above) have been structured to allow the Permittees to provide design information in roughly the same order as the buildings are constructed. Therefore, the packages start at the lowest level of the building (i.e., below grade levels) and are submitted for regulated areas of each level of the building before construction begins. This process has been modified for some design packages. If the process system in the design package is located on more than one level in a WTP Building, the design package can address components on more than one building level. This will prevent the confusion caused by one process system description being segmented into multiple design packages.

The Permit breaks out design packages into three general groups by the type of regulated equipment: (1) secondary containment; (2) primary containment (e.g., tanks, miscellaneous units [i.e., evaporators and melters], containment buildings); and (3) other associated, regulated equipment (e.g., ancillary equipment, equipment associated with miscellaneous units). Using tank systems as an example, secondary containment packages include details of the design of secondary containment that must be in place in regulated areas when the floors and walls are built for that level of the building (e.g., floor slope, sump location). Construction of the floors and walls is usually followed by the installation of tanks and other large equipment. Therefore, a tank package on that level will be included in the Permit before installation (e.g., structural details for those tanks or miscellaneous units showing nozzle locations, unit volumes, tank shell

thickness). The last equipment usually installed on a level for a tank system is the ancillary equipment (e.g., piping, pumps, process instrumentation, electrical equipment). Therefore, the ancillary equipment package that provides details for equipment on that level will be included in the Permit before installation (e.g., materials of construction, pipe support details, pump types and their operating limits).

With each WTP Building consisting of multiple levels, the total number of design packages is large. The Permittees estimate about 150 packages will have to be incorporated into the Permit. This could potentially trigger 150 public comment periods. In reality, Ecology intends to group packages, where possible, to reduce the potential number of public comment periods.

The secondary containment, primary containment, and other associated, regulated equipment packages for different levels require repetitive information submittals in each package. Again, using tank systems as an example, the method of installation of secondary containment liners on each level is expected to be the same and most tanks will use the same construction specifications. The Permit allows the Permittees to reference the previously submitted design information. Therefore, some design packages may consist mostly of references to information previously provided.

Ecology is authorized, pursuant to WAC 173-303-830(4)(e), to grant temporary authorizations for the Permittees to start construction on a design package after Ecology approval, but before the draft permit modification process is complete. A Permittee is allowed to request a temporary authorization to implement a modification prior to public notice and comment, pursuant to WAC 173-303-830(4)(e)(ii)(A). To issue a temporary authorization, Ecology must find it meets the criteria as described in WAC 173-303-830(4)(ii)(A) and -830(4)(iii). The term of a temporary authorization is limited to 180 days with the potential for Ecology approval of two terms, with a maximum combined duration of 360 days. The purpose of a temporary authorization is to allow the timely implementation of a permit modification. Construction that takes place under a temporary authorization is at the Permittees' risk because public comment may require the Permittees to modify something that is already built. The submittal schedule developed by the Permittees will allow most design packages to undergo public comment and be incorporated into the Permit prior to construction of those areas.

3.0 Procedures for Reaching a Final Decision on the Draft Permit

This Washington State Hazardous Waste Management Act, Chapter 70.105 Revised Code of Washington (RCW), and regulations promulgated in Chapter 173-303 of the WAC, regulate the management of dangerous waste in Washington. In accordance with WAC 173-303-800, facilities that treat, store, and/or dispose of dangerous waste must obtain a permit for these activities.

A 45-day public comment period for draft permit modifications to Part III, Chapter 10, WTP, of the Permit begins on February 23, 2004, and ends on April 9, 2004. All comments received during the public comment period will be considered and responded to before final decisions are made on the proposed modifications. Regulatory requirements for public notice and involvement (for this permit modification) are described in WAC 173-303-840(3). Comments must be post-marked or received by e-mail no later than April 9, 2003. Comments hand delivered by April 9, 2004, to the address below also will be accepted. Direct all written comments to:

Mr. Steve Skurla
Department of Ecology
1315 W. 4th Avenue
Kennewick, Washington 99336
E-mail address: ssku461@ecy.wa.gov

A public hearing will be held at the Department of Ecology, (address shown above), if requested.

Ecology will consider and respond to all written comments submitted by the deadline, and verbal comments submitted at the public meeting, if held. Ecology will then make a final permit decision, which will become effective 30 days after Ecology provides notice of the decision to the Permittees and all who commented. If

Ecology's decision includes substantial changes to the Permit because of public comment, Ecology will initiate a new public comment period.

All commenters and the Permittees shall receive a copy of the Responsiveness Summary and a notification of the final permit decision. Ecology's final permit decision may be appealed within 30 days after notice of the final permit decision has been provided.

Copies of the Permit for the Hanford Facility, including the proposed, draft permit modifications are available for review at the Hanford Public Information Repositories listed below. [For additional information, call the Hanford Cleanup Hotline toll-free at (800) 321-2008].

HANFORD PUBLIC INFORMATION REPOSITORIES

Portland

Portland State University Branford Price Miller Library 934 SW Harrison and Park Portland, Oregon 97207 (503) 725-3690

Attn: Michael Bowman/Jocelyn Kramer

E-mail: bowman@lib.pdx.edu

Spokane

Gonzaga University Foley Center East 502 Boone Spokane, Washington 99258-0001 (509) 323-3839

Attn: Connie Scarppelli

E-mail: carter@its.gonzaga.edu

Richland

Public Reading Room 2770 University Drive Consolidated Information Center, Rm. 101L Richland, Washington 99352 (509) 372-7443

Attn: Terri Traub

E-mail: reading_room@pnl.gov

Seattle

University of Washington Suzzallo Library Government Publication Division Seattle, Washington 98195 (206) 543-4664

Attn: Eleanor Chase

E-mail: echase@u.washington.edu Public Service: (206) 543-1937

This Statement of Basis for the proposed draft permit modification is also available on the World Wide Web at http://www.ecy.wa.gov/programs/nwp/.

If special accommodations are needed for public comment, please contact Tim Hill, Department of Ecology, Nuclear Waste Program, at (509) 736-3026 (voice), or (360) 407-6006 (TDD).

4.0 Proposed Permit Modification to Part III, Chapter 10, WTP of the Permit

The proposed Draft Permit Modification to Part III, Chapter 10, WTP of the Permit includes:

- Inclusion of design packages into the Permit (acronyms are defined in 'Notes' in Table 1):
 - o PTF-014 Tank System for the HLP System
 - o PTF-017 Tank System for the TCP System
 - o PTF-025 Tank System Ancillary Equipment for the UFP System
 - o PTF-026 Tank System Ancillary Equipment for the HLP System
 - o PTF-032 Tank System for the TCP System
 - o PTF-040 Tank System for the UFP System
 - o LAW-006 Tank System for the LOP System on the + 3 foot elevation
 - o LAW-009 Tank System for the RLD system on the +3 foot elevation
 - o LAW-010 Tank System for the LCP System on the +3 foot elevation
 - o LAW-011 Tank System for the LFP System on the +3 foot elevation
 - LAW-017 Miscellaneous Treatment Unit Subsystems for the LOP System on the +3 foot elevation

- HLW-009 Tank System Ancillary Equipment for the HOP System SBS Condensate Receiver Vessels
- o HLW-010 Miscellaneous Treatment Unit Subsystems for the HOP Silver Mordenite Units on the -21 foot elevation
- o HLW- 038 Double Wall Pipe for the RDL & HCP Systems on the -21 foot elevation
- o Engineering Specifications for Field Applied Special Protective Coating for Secondary Containment Areas (WTP-3PS-AFPS-TP006) (To be added to Appendix 7.7)
- o Hanford Tank WTP Post Construction Traffic Analysis Final Project Report (24590-100-SC-W000-00003-04-01, Revision 00B (To be added to the Administrative Record).

Other changes include:

- o Incorporation of previously approved Class 1' and Class 2 Permit modifications including changes to Chapter 4.0 of Appendix 51
- o Incorporation of new information into the Permit tables.

4.1 Supplemental Design Information

Table 1 lists the design information included in this draft permit modification and where in the Permit the information is proposed to be located. At final issuance of the permit modification, Ecology will specify where each drawing or report resides in the Permit. Paper copies of the page changes to the Permit as a result of this modification will be stored in the Administrative Record. Duplicate sets of drawings will not be issued to the Permittees at issuance of the permit modification in order to minimize the amount of duplicate paperwork, unless drawing changes are made as a result of public comment. The letter issuing the modification to the Permittees will include the current Permit with the modifications on a CD-ROM.

4.2 Other Changes Included in This Modification

As the Permit for the WTP Unit is implemented, Ecology will modify the permit conditions for many reasons including: to clarify text, add new conditions, delete existing conditions, or to correct errors. To communicate the changes in the draft review package, the draft permit modification will include page changes showing all significant draft changes to the Permit. The text to be deleted will be struck-out with a single line and the new text will be double-underlined. Only the text changing in the current modification will have changes highlighted by underlines and strikeouts. At issuance of the next permit modification, clean page changes will be issued to the Permittees and Administrative Record for the previous modification.

Two Class 1' Modifications (as defined in WAC-173-303-830) to interim compliance dates were granted by Ecology. The changes are in Attachment 51, Appendix 1.0 and were necessary to bring the compliance dates in line with the new Tri-Party Agreement Milestone date for operation of the WTP in 2011. Draft page changes are included in this modification package.

The Engineering Specifications for Field Applied Special Protective Coating for Secondary Containment Areas (WTP-3PS-AFPS-TP006) was submitted and will be included in Attachment 51, Appendix 7.7.

A traffic analysis report was also submitted in this modification package. The Dangerous Waste Permit Interim Compliance Schedule Item 2 requires submittal of a revised traffic report for incorporation into the Administrative Record. The *Hanford Tank WTP Post Construction Traffic Analysis Final Project Report* (24590-100-SC-W000-00003-04-01, Revision 00B) was submitted to fulfill this requirement. Bechtel National, Inc. and U.S. Department of Energy Certification Statements were submitted as well.

At the time the permit was originally issued, WTP tanks and miscellaneous units were identified using the British Nuclear Fuels Ltd. numbering system. Bechtel National Inc. (BNI) has changed all the identifiers to match the BNI corporate tank numbering system. This permit modification has continued to revise the identifiers to the BNI identification numbers in the tables in the Permit Conditions. This will align the identifiers in the Permit Conditions with the drawings and documents submitted and incorporated in

Appendix 51. The rest the identifiers included in other portions of the Permit will be updated in an upcoming permit modification that will tie into the renewal of the entire Hanford Site dangerous waste permit in 2004.

Additional data will be added to Tables in Sections III.10.E., III.10.F., III.10.H., III.10.I., III.10.J., and III.10.H., based on information provided in the design packages included in this modification.

One Class 2 Modification (as defined in WAC-173-303-830) will delete from the list of regulated areas the Drum Transfer Tunnel located on the -21 foot level of the High Level Waste Building. The Drum Transfer Tunnel is designed to move non-liquid mixed waste (mainly spent, containerized High Efficiency Particulate Air (HEPA) filters from the HEPA Filter Room on the west side of the High Level Waste Building to the east side of the building for transfer out of the building. The Permittees originally believed open canisters containing waste and/or contaminated failed equipment might be stored in the tunnel for more than 90 days and therefore requested that the tunnel be included in the permit as a containment building unit per WAC 173-303-695. Now, the Permittees have decided to not use the Drum Transfer Tunnel for storage of waste for more than 90 days. Because the tunnel is no longer to be used for storing waste, it would no longer be required to be regulated under WAC 173-303. Ecology has accepted this proposed change, but reminds the Permittees that storing waste in the Drum Transfer Tunnel for more than 90 days will be a violation of the WTP Permit. Draft changes to the table in Chapter III.10.F and Attachment 51, Chapter 4.0 are included in this modification package.

The second Class 2 Modification adds the Pour Tunnels No. 1 and 2 to the regulated units in the -21 foot elevation of the High Level Waste Building. These areas were added as a containment buildings units because they will hold unlidded canisters for cooling prior to transfer to the canister handling cave for lid welding. Ecology approved these modifications on January 24, 2004. As a convenience we are incorporating the changes to permit documents as a result of the Class 2 modification with this modification package. The marked-up page changes are included in this review package but, the Class 2 modifications were subject to a separate public review process and are not considered open for public comment at this time.

Table 1 - Design Packages Submitted by Permittees

DOCUMENT/ DRAWING NUMBER	PTF-014, Rev 0 - Tank System for th	REPLACES	PERMIT LOCATION
24590-CM-HC4-HXYG-0138-02-10, Rev 00A	IQRPE Independent Assessment Report	N/A	8.11
25490-PTF-M5-V17T-P0007, Rev 0	Process Flow Diagram	N/A	8.1
25490-PTF-M5-V17T-P0008, Rev 0	Process Flow Diagram	N/A	8.1
25490-PTF-PEN-ENV-04-001	Permit Equivalency Notice, "Changes to the PT HLP System Permit Process Flow Diagram 24590-PTF-M5-V17T-P0008 Rev 0"	N/A	8.1
24590-PTF-M6-HLP-P0001, Rev 1	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-HLP-P0002, Rev 1	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-HLP-P0003, Rev 1	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-HLP-P0005, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-HLP-P0006, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-HLP-P0007, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-HLP-P0009, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-HLP-P0010, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-PEN-ENV-04-002	Permit Equivalency Notice, "Changes to the PT HLP System Permit Piping & Instrument Diagram 24590-PTF-M6-HLP-P0001 Rev 1"	N/A	8.2
24590-PTF-PEN-ENV-04-003	Permit Equivalency Notice, "Changes to the PT HLP System Permit Piping & Instrument Diagram 24590-PTF-M6-HLP-P0003 Rev 1"	N/A	8.2
24590-PTF-PEN-ENV-04-004	Permit Equivalency Notice, "Changes to the PT HLP System Permit Piping & Instrument Diagram 24590-PTF-M6-HLP-P0010 Rev 1"	N/A	8.2
24590-PTF-MV-HLP-P0003, Rev 0	Mechanical Drawings	N/A	8.6
24590-PTF-MV-HLP-P0004, Rev 0	Mechanical Drawings	N/A	8.6
24590-PTF-MV-HLP-P0005, Rev 0	Mechanical Drawings	N/A	8.6
24590-PTF-MV-HLP-P0006, Rev 0	Mechanical Drawings	N/A	8.6
24590-PTF-MVD-HLP-P0006, Rev 1	Mechanical Data Sheets	N/A	8.6
24590-PTF-MVD-HLP-P0007, Rev 1	Mechanical Data Sheets	N/A	8.6
24590-PTF-MVD-HLP-P0008, Rev 1	Mechanical Data Sheets	N/A	8.6
24590-PTF-MVD-HLP-P0009, Rev 1	Mechanical Data Sheets	N/A	8.6
24590-PTF-N1D-HLP-P0003, Rev 0	Vessel/Tank Material Selection Data Sheet	N/A	8.9
24590-PTF-N1D-HLP-P0007, Rev 1	Vessel/Tank Material Selection Data Sheet	N/A	8.9
24590-PTF-N1D-HLP-P0010, Rev 1	Vessel/Tank Material Selection Data Sheet	N/A	8.9
24590-PTF-3YD-HLP-00001, Rev 0	HLP System Description for the HLW Lag	N/A	Administrative

	Storage & Feed Blending Process (HLP) System		Record
24590-PTF-3YN-HLP-00001, Rev 0	HLP System Description Notice	N/A	Administrative Record
PACKAGE	PTF-017, Rev 0 - Tank System fo	or the TCP System	
DOCUMENT/ DRAWING NUMBER	TITLE	REPLACES	PERMIT LOCATION
24590-CM-HC4-HXYG-00138-02-04 Rev 00A	IQRPE Independent Assessment Report	N/A	8.11
24590-PTF-M5-V17T-P0006 Rev 0	Process Flow Diagram	N/A	8.1
24590-PTF-M6-TCP-P0001 Rev 0	Piping & Instrumentation Diagram	N/A	8.2
24590-PTF-M6-TCP-P0002 Rev 0	Piping & Instrumentation Diagram	N/A	8.2
24590-PTF-MV-TCP-P0002 Rev 0	Mechanical Drawings	N/A	8.6
24590-PTF-MVD-TCP-P0002 Rev 1	Mechanical Drawings	N/A	8.6
24590-PTF-NID-TCP-P0001 Rev 0	Vessel/Tank Material Selection Data Sheet	N/A	8.9
24590-PTF-3YN-TCP-00001 Rev 0	System Description Change Notice	N/A	Administrative Record
24590-PTF-3YD-TCP-00001 Rev 0	System Description for the Treated LAW Concentrate Storage Process (TCP)	N/A	Administrative Record
PACKAGE PTF-025 Rev	0 - Tank System Ancillary Equip	ment for PT Facility UFP S	vetam
DOCUMENT/ DRAWING NUMBER	TITLE	REPLACES	PERMIT LOCATION
24590-CM-HC4-HXYG-00138-02-06, Rev 00A	IQRPE Independent Assessment Report	N/A	8.11
24590-PTF-NID-UFP-P0001, Rev 0	Material Selection Data Sheets	N/A	8.9
24590-PTF-NID-UFP-P0002, Rev 0	Material Selection Data Sheets	N/A	8.9
2.550111111115 011 10002,10010;		N/A	8.13
24590-PTF-PER-J-02-004, Rev 0	System Logic Description for the UFP System	IVA	0.13
	1	IVA	6.13
24590-PTF-PER-J-02-004, Rev 0	System		
24590-PTF-PER-J-02-004, Rev 0	1		ystem PERMIT
24590-PTF-PER-J-02-004, Rev 0 PACKAGE PTF-026, Rev	O, Tank System Ancillary Equiportitle	ment for PT Facility HLP S	ystem PERMIT LOCATION
PACKAGE PTF-026, Rev DOCUMENT/ DRAWING NUMBER	0, Tank System Ancillary Equip	ment for PT Facility HLP S REPLACES N/A	ystem PERMIT LOCATION 8.11
PACKAGE PTF-026, Rev DOCUMENT/ DRAWING NUMBER 24590-CM-HC4-HXYG-00138-02-09, Rev 00A	O, Tank System Ancillary Equiport TITLE IQRP Independent Assessment Report	ment for PT Facility HLP S REPLACES	ystem PERMIT LOCATION

PACKAGE PTF-032, I	Rev 0 - Tank System Ancillary Equ	uipment for the TCP Sys	
24590-CM-HC4-HXYG-00138-02-05, Rev 00A	IQRP Independent Assessment Report	N/A	8.11
24590-PTF-PER-J-012, Rev 0	System Logic Description for the TCP System	N/A	8.13
DACKACE DT	E 040 Day O Tank System for DT	Eggilder HED Cyctom	
	F-040, Rev 0, Tank System for PT IQRP Independent Assessment Report	N/A	8.11
24590-CM-HC4-HXYG-00138-01-18, Rev 00A	Process Flow Diagram	N/A	8.1
24590-PTF-M5-V17T-P0009, Rev 0 24590-PTF-M5-V17T-P0010, Rev 0	Process Flow Diagram Process Flow Diagram	N/A	8,1
	Process Flow Diagram Process Flow Diagram	N/A	8.1
24590-PTF-M5-V17T-P0011, Rev 0		N/A N/A	8.2
24590-PTF-M6-UFP-P0001, Rev 1	Piping & Instrumentation Diagrams	N/A N/A	
24590-PTF-M6-UFP-P0002, Rev 0	Piping & Instrumentation Diagrams		8.2
24590-PTF-M6-UFP-P0003, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-UFP-P0004, Rev 1	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-UFP-P0006, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
4590-PTF-M6-UFP-P0008, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
4590-PTF-M6-UFP-P0009, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
4590-PTF-M6-UFP-P0010, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
4590-PTF-M6-UFP-P0011, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-UFP-P0013, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-UFP-P0015, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-UFP-P0016, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-M6-UFP-P0017, Rev 0	Piping & Instrumentation Diagrams	N/A	8.2
24590-PTF-MV-UFP-P0001, Rev 0	Mechanical Drawings	N/A	8.6
24590-PTF-MV-UFP-P0002, Rev 0	Mechanical Drawings	N/A	8.6
24590-PTF-MV-UFP-P0003, Rev 0	Mechanical Drawings	N/A	8.6
24590-PTF-MV-UFP-P0004, Rev 0	Mechanical Drawings	N/A	8.6
24590-PTF-MV-UFP-P0005, Rev 0	Mechanical Drawings	N/A	8.6
24590-PTF-MV-UFP-P0006, Rev 0	Mechanical Drawings	N/A	8.6
24590-PTF-MV-UFP-P0007, Rev 0	Mechanical Drawings	N/A	8.6
24590-PTF-3PS-MLFP-TP001, Rev 1	Specifications	N/A	8.7
24590-PTF-MLD-UFP-P0007, Rev 1	Mechanical System Data Sheets	N/A	8.6
24590-PTF-MVD-UFP-P0001, Rev 0	Mechanical System Data Sheets	N/A	8.6
24590-PTF-MVD-UFP-P0002, Rev 0	Mechanical System Data Sheets	N/A	8.6
24590-PTF-MVD-UFP-P0005, Rev 0	Mechanical System Data Sheets	N/A	8.6
24590-PTF-MVD-UFP-P0006, Rev 0	Mechanical System Data Sheets	N/A	8.6
24590-PTF-MVD-UFP-P0007, Rev 0	Mechanical System Data Sheets	N/A	8.6
24590-PTF-MVD-UFP-P0014, Rev 0	Mechanical System Data Sheets	N/A	8.6
24590-PTF-MVD-UFP-P0015, Rev 0	Mechanical System Data Sheets	N/A	8.6

24590-PTF-N1D-UFP-P0003, Rev 0	Vessel/Tank Material Selection Data Sheet	N/A	8.9
24590-PTF-N1D-UFP-P0004, Rev 1	Vessel/Tank Material Selection Data Sheet	N/A	8.9
24590-PTF-N1D-UFP-P0005, Rev 0	Vessel/Tank Material Selection Data Sheet	N/A	8.9
24590-PTF-N1D-UFP-P0008, Rev 0	Vessel/Tank Material Selection Data Sheet	N/A	8.9
24590-PTF-3YN-UFP-00001, Rev 0	UFP System Description Change Notice	N/A	Administrative
			Record
24590-PTF-3YD-UFP-00001, Rev 0	UFP System Description for the UFP	N/A	Administrative
			Record

DOCUMENT/ DRAWING NUMBER	TITLE	REPLACES	PERMIT LOCATION
24590-CM-HC4-HXYG-00138-01-00019, Rev 00A	IQRPE Independent Assessment Report	N/A	9.11
24590-LAW-M5-V17T-P0007, Rev 0	Process Flow Diagram	N/A	9.1
24590-LAW-M5-V17T-P0008, Rev 0	Process Flow Diagram	N/A	9.1
24590-LAW-M6-LOP-P0001, Rev 0	Piping & Instrumentation Diagrams	N/A	9.2
24590-LAW-M6-LOP-P0002, Rev 0	Piping & Instrumentation Diagrams	N/A	9.2
24590-LAW-MV-LOP-P0001, Rev 0	Mechanical Drawing	N/A	9.6
24590-LAW-MV-LOP-P0002, Rev 0	Mechanical Drawing	N/A	9.6
24590-LAW-MVD-LOP-P0004, Rev 0	Mechanical Data Sheets	N/A	9.6
24590-LAW-MVD-LOP-P0005, Rev 0	Mechanical Data Sheets	N/A	9.6
24590-LAW-N1D-LOP-0002, Rev 0	Plant Item Material Selection Data Sheet	N/A	9.9
24590-LAW-3YD-LOP-00001, Rev 0	System Description for LOP & LVP: LAW Melter Offgas	N/A	Administrative Record

PACKAGE LAW-009, Rev 0 - Tank System for the RLD System at El. +3 Ft TITLE REPLACES PERMIT DOCUMENT/ DRAWING NUMBER **LOCATION IQRPE Independent Assessment Reports** N/A 24590-CM-HC4-HXYG-00138-02-07 Rev 00A 9.11 Piping & Instrument Diagram 24590-LAW-M6-RLD-P0001 Rev 0 9.2 24590-LAW-M6-RLD-P0001 Rev 1 Mechanical Drawings 24590-LAW-MV-RLD-P0002 Rev 1 9.6 N/A 24590-LAW-MV-RLD-P0003 Rev 1 24590-WTP-3PS-MV00-TP001 Rev 1 Specifications for Pressure Vessel Design & 7.7 N/A Fabrication 7.9 N/A 24590-WTP-3PS-G000-TP002 Rev 2 Specifications for Positive Material Identification N/A 9.6 24590-LAW-MVD-RLD-P0006 Rev 1 Mechanical Data Sheets 24590-LAW-MVD-RLD-P0007 Rev 2

B.1070 22211 4122 2322 3722 372	Material Selection Data Sheet	N/A	9,9
24590-LAW-NID-RLD-P0005 Rev 0 24590-LAW-3YD-20-00001	System Description Change Notice	N/A	Administrative
			Record
The second secon			

DOCUMENT/ DRAWING NUMBER	TITLE	REPLACES	PERMIT LOCATION
24590-101-SC-HXYG-0074-03-00001, Rev 00A	IQRPE Independent Assessment Report	N/A	9.11
24590-LAW-P1-P01T-P0002, Rev 3	General Arrangement Plan	24590-LAW-P1-P01T-P0002, Rev 2	9.4
24590-LAW-P1-P01T-P0007, Rev 4	General Arrangement Section	24590-LAW-P1-P01T-P0007, Rev 3	9.4
24590-LAW-P1-P01T-P0008, Rev 3	General Arrangement Section	24590-LAW-P1-P01T-P0008, Rev 2	9.4
24590-LAW-P1-P01T-P0009, Rev 4	General Arrangement Section	24590-LAW-P1-P01T-P0009, Rev 3	9.4
24590-LAW-P1-P01T-P0010, Rev 4	General Arrangement Section	24590-LAW-P1-P01T-P0010, Rev 3	9.4
24590-LAW-P1-P01T-P0011, Rev 0	General Arrangement Section	N/A	9.4
24590-LAW-M5-V17T-P0001, Rev 0	Process Flow Diagram	N/A	9.1
24590-LAW-M5-V17T-P0002, Rev 0	Process Flow Diagram	N/A	9.1
24590-LAW-M6-LCP-P0001, Rev 1	Piping & Instrumentation Diagram	24590-LAW-M6-LCP-P0001, Rev 0	9.2
24590-LAW-M6-LCP-P0002, Rev 0	Piping & Instrumentation Diagram	N/A	9.2
24590-WTP-PEN-ENV-03-003	Permit Equivalency Notice, "Change to the Permit P&IDs"	N/A	9.2
24590-LAW-MV-LCP-P0001, Rev 0	Mechanical Drawings	N/A	9.6
24590-LAW-MV-LCP-P0002, Rev 0	Mechanical Drawings	N/A	9.6
24590-WTP-PEN-ENV-03-001	Specifications: Permit Equivalency Notice, "Changes to the Permit Specifications 24590-WTP-3PS-MV00-TP002, Rev 1, Engineering Specification for Seismic Qualification Criteria for Pressure Vessels"	N/A	7.7
24590-WTP-PEN-ENV-03-002	Specifications: Permit Equivalency Notice, "Change to the Permit Specification 24590-WTP-3PS-MV00-TP003, Rev. 1, Engineering Specification for Pressure Vessel Fatigue Analysis"	N/A	7.7
24590-LAW-MVD-LCP-P0004, Rev 0	Mechanical Data Sheet	N/A	9.6
24590-LAW-MVD-LCP-P0005, Rev 0	Mechanical Data Sheet	N/A	9.6
24590-LAW-N1D-LCP-P0001, Rev 0	Material Selection Data Sheet	N/A	9.9
24590-LAW-3YD-LCP-00001, Rev 0	System Description for System LCP LAW Concentrate Receipt Process	N/A	Administrative Record

24590-WPT-PER-PR-03-002, Rev 0	Toxic Vapors & Emissions from WTP Tank System & Miscellaneous Treatment	N/A	Administrative Record
	Unit Systems		
PACKAGE LAW	-011, Rev 0 -Tank System for the I	LFP System at El. +3 ft	
DOCUMENT/ DRAWING NUMBER	TITLE	REPLACES	PERMIT LOCATION
24590-101-SC-HXYG-0074-03-00002, Rev 00A	IQRPE Independent Assessment Report	N/A	9.11
24590-LAW-M6-LFP-P0001, Rev 0	Piping & Instrument Diagram	N/A	9.2
24590-LAW-M6-LFP-P0003, Rev 0	Piping & Instrument Diagram	N/A	9.2
24590-LAW-MV-LFP-P0001, Rev 0	Mechanical Drawings	N/A	9.6
24590-LAW-MV-LFP-P0002, Rev 0	Mechanical Drawings	N/A	9.6
24590-LAW-MV-LFP-P0004, Rev 0	Mechanical Drawings	N/A	9.6
24590-LAW-MV-LFP-P0005, Rev 0	Mechanical Drawings	N/A	9.6
24590-LAW-MVD-LFP-P0007, Rev 0	Mechanical Data Sheet	N/A	9.6
24590-LAW-MVD-LFP-P0008, Rev 0	Mechanical Data Sheet	N/A	9.6
24590-LAW-MVD-LFP-P0010, Rev 0	Mechanical Data Sheet N/A		9.6
24590-LAW-MVD-LFP-P0011, Rev 0	Mechanical Data Sheet	N/A	9.6
24590-LAW-N1D-LFP-P0004, Rev 0	Plant Item Material Selection Data Sheet	N/A	9.9
24590-LAW-3YD-LFP-00001, Rev 0	System Description for the LFP System	N/A	Administrative Record
24590-LAW-3YD-LFP-00001	System Description Change Notice for LAW LFP	N/A	Administrative Record
			:
PACKAGE LAW-017, Rev 0 -	Miscellaneous Treatment Unit Sul	bsystem for the LOP System	em at +3 ft
	(WESP & SBS)		
DOCUMENT/ DRAWING NUMBER	TITLE	REPLACES	PERMIT LOCATION
24590-CM-HC4-HXYG-00138-02-00011, Rev 00A	IQRPE Independent Assessment Report	N/A	9.11
24590-LAW-MK-LOP-P0001001, Rev 0	Mechanical Drawings: SBS	N/A	9.6
24590-LAW-MK-LOP-P0001002, Rev 0	Mechanical Drawings: SBS	N/A	9.6
24590-LAW-MK-LOP-P0001003, Rev 0	Mechanical Drawings: SBS	N/A	9.6
24590-WTP-3PS-MKE0-TP001, Rev 0	Specification for WESP	N/A	7.7
	The state of the s	· · · · · · · · · · · · · · · · · · ·	

Mechanical Data Sheets for SBS

Material Selection Data Sheet for SBS

Material Selection Data Sheet for WESP

24590-LAW-MKD-LOP-P0008, Rev 0

24590-LAW-N1D-LOP-P0001, Rev 0 24590-LAW-N1D-LOP-P0003, Rev 0

N/A

N/A

N/A

9.6

9.9

9.9

24590-LAW-PER-PR-03-001, Rev 0	Mechanical Data Sheets: LAW Vit Offgas	N/A	9.18
	System Bypass Analysis		
24590-WTP-PER-CON-02-001, Rev 2	Installation of Tank System & Miscellaneous	N/A	7.12
	Treatment Systems		

PACKAGE HLW-009, Rev 0 - Tank System Ancillary Equipment for HOP (SBS Condensate Receiver Vessel)				
DOCUMENT/ DRAWING NUMBER	TITLE	REPLACES	PERMIT LOCATION	
24590-CM_HC4-HXYG-00138-02-08 Rev A	IQRPE Independent Assessment Report	N/A	10.11	
24590-HLW-PER-J-02-001 Rev 1	System Logic Description for HLW Facility- Melter Offgas Treatment Process (HOP) System	N/A	10.13	

PACKAGE HLW-010, Rev 0 - Miscellaneous Treatment Units for HLW Facility El. -21 ft (Silver Mordenite)

DOCUMENT/ DRAWING NUMBER	TITLE REPLACES				PERMIT LOCATION
24590-101-SC-HXYG-0074-03-00003, Rev A	IQRPE Independent Assessment Reports	N/A	10.11		
24590-HLW-M5-V17T-P0004, Rev 1	Process Flow Diagrams for Melter 1 HOP System	N/A	10.1		
24590-HLW-M5-V17T-P20004, Rev 0	Process Flow Diagrams for Melter 2 HOP System	N/A	10.1		
24590-HLW-M6-HOP-P0003, Rev 0	Piping & Instrumentation Diagram for Melter 1 HOP System, Sheet 1 of 2	N/A	10.2		
24590-HLW-M6-HOP-P0008, Rev 0	Piping & Instrumentation Diagram for Melter 1 HOP System, Sheet 2 of 2	N/A	10.2		
24590-HLW-M6-HOP-P20003, Rev 0	Piping & Instrumentation Diagram for Melter 2 HOP System, Sheet 1 of 2	N/A	10.2		
24590-HLW-M6-HOP-P20008, Rev 0	Piping & Instrumentation Diagram for Melter 2 HOP System, Sheet 2 of 2	N/A	10.2		
24590-HLW-3PS-MBT0-TP001, Rev 1	Specifications: Silver Mordenite Column Design & Fabrication	N/A	10.7		
24590-HLW-PEN-ENV-04-002	Maximum Operating Pressure Correction: Silver Modenite Column Specification for HLW-101	N/A	10.7		
24590-HLW-MKD-HOP-P0014, Rev 1	Mechanical Systems Data Sheets	N/A	10.6		
24590-HLW-MKD-HOP-P0017, Rev 0	Mechanical Systems Data Sheets	N/A	10.6		
24590-HLW-NID-HOP-P0006, Rev 1	Material Selection Data Sheet: Silver Mordenite Column	N/A	10.9		

24590-HLW-3YN-HOP-00003, Rev 0	System Description Change Notice	N/	A	Administrative
				Record
24590-HLW-PER-PR-03-001, Rev, 0	Description of HLW Vit System Bypass Events	N/	A	10.18

DOCUMENT/ DRAWING NUMBER	ev 0 - Double-Wall Pipe in the RLI TITLE	REPLACES	PERMIT LOCATION
24590-CM-HC4-HXYG-00138-01-15, Rev B	IQRPE Independent Assessment Report	N/A	10.11
24590-HLW-M6-RLD-P0001, Rev 0	Piping & Instrumentation Diagrams for the RLD System (Active Effluent Collection)	N/A	10.2
24590-HLW-M6-RLD-P0002, Rev 0	Piping & Instrumentation Diagrams for the RLD System (Plant Wash & Drains Vessel)	N/A	10.2
24590-HLW-M6-HCP-P0001, Rev 0	Piping & Instrumentation Diagrams for the HCP System (Concentrate Receipt Vessel 1)	N/A	10.2
24590-HLW-M6-HCP-P0002, Rev 0	Piping & Instrumentation Diagrams for the HCP System (Concentrate Receipt Vessel 2)	N/A	10.2
24590-WPT-PER-PL-02-001, Rev 3	Piping Material Class Description	24590-WTP-PER-PL-02-001, Rev 2	4.0
NOTES: FRP = Waste Feed Receipt Process System HCP = HLW Condensate Receipt Process System	LSM = Locally Shie LOP = LAW Melter LVP = LAW Second		n

FRP = Waste Feed Receipt Process System
HCP = HLW Condensate Receipt Process Syst
HLP = HLW Lag Storage and Feed Blending P

Process System

HLW = High Level Waste

HOP = HLW Vit Primary Offgas Treatment System

IQRPE = Independent, Qualified, Registered Professional Engineer

LAB = WTP Laboratory Building

LAW = Low Activity Waste

LCP = LAW Concentrate Receipt Process System

LFP = LAW Melter Feed Process System

MTU = Miscellaneous Treatment Units

PTF = Pretreatment Building

PVV = Process Vessel Vent System

PWD = Plant Wash and Disposal System

RLD = Radioactive Liquid Waste Disposal System

SBS = Submerged Bed Scrubber

TCP = Treated LAW Evaporation Process System
UFP = Ultrafiltration Process System

WESP = Wet Electrostatic Precipitator

Permit Number: WA7890008967 Class III Modification to Revision 7 Expiration Date: September 27, 2004

Waste Treatment and Immobilization Plant Unit Specific Permit Conditions

Page Changes to Conditions

(New text is double underlined Deleted text is struck out)

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 1 of 210

CHAPTER 10 Waste Treatment and Immobilization Plant 2 The Waste Treatment and Immobilization Plant (WTP) is the unit designed to treat the mixed (radioactive 3 and dangerous) waste stored in underground tanks at the Hanford Site. The waste will be separated into 4 High-level and Low-level waste streams in a Pretreatment Building. The waste streams are mixed with 5 glass forming additives, heated to 950-1250°C in melters, and poured into containers. The waste is 6 immobilized in the glass matrix. The immobilized waste is transported from the WTP Unit for disposal. 7 COMPLIANCE WITH APPROVED PERMIT AND ATTACHMENT 51 8 Ш.10.А. 9 The Permittees shall comply with all requirements set forth in Attachment 51, including the 10 conditions specified in Permit Conditions III.10.B through III.10.K. Enforceable portions of the application have been incorporated in Attachment 51 and are identified as follows. All 11 sections, figures, and tables included in these portions are also enforceable, unless stated 12 otherwise. 13 Where information regarding treatment, management, and disposal of the radioactive source, 14 15 byproduct material, and/or special nuclear components of mixed waste (as defined by the Atomic Energy Act of 1954, as amended) has been incorporated into this permit, it is not 16 incorporated for the purpose of regulating the radiation hazards of such components under 17 18 the authority of this permit and chapter 70.105 RCW. ATTACHMENT 51 19 Part A, Form 3 Permit Application, Revision 1 (December 6, 2001) 20 Chapter 1.0 21 Chapter 2.0 Facility Description (Topographic Map) Waste Analysis Plan 22 Chapter 3.0 **Process Information** 23 Chapter 4.0 24 Chapter 6.0 Procedures to Prevent Hazards 25 Chapter 7.0 Contingency Plan Chapter 8.0 Personnel Training Closure Chapter 11.0 27 Chapter 12.0 Reporting and Recordkeeping 28 Compliance Schedule Appendix 1.0 29 Appendix 2.0 Critical Systems 30 Appendix 3.0 Drawing Category Table 31 32 Appendix 4.0 Piping Material Index Table 33 Appendix 5.0 Legends for Process Flow Diagrams and Piping and Instrumentation Diagrams (RESERVED) 34 Appendix 6.0 Risk Assessment 35 Preliminary Risk Assessment Work Plan 36 6.1 Previously Submitted Preliminary Risk Assessment Work Plan 37 6.1.1 38 6.1.2 Documentation of Revisions to Preliminary Risk Assessment Work Plan Risk Assessment Work Plan (RESERVED) 39 6.2^{-} 6.3 Pre-Demonstration Test Risk Assessment Report (RESERVED) 40 Basis and Assumptions (RESERVED) 41 6.3.1

Final Risk Assessment Report (RESERVED)

6.4

42

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 2 of 210

	1			6.4.1	Basis and Assumptions (RESERVED)
	2		Appendix	7.0	WTP Documents Applicable to All Regulated Areas
	3		/ Ippoliting	7.1	Process Flow Diagrams (RESERVED)
	4			7.2	Piping and Instrumentation Diagrams (RESERVED)
	- - 5-		: - <u>-</u>	7.3	System Description Documentation (RESERVED)
	6			7.4	General Arrangement Drawings (RESERVED)
	. 7			7.5	Civil, Structural, and Architectural Criteria and Typical Design Details
	8			7.6	Mechanical Drawings (RESERVED)
	9	1		7.7	Specifications
	10			7.8	Engineering Calculations (RESERVED)
. 5	11	•		7.9	Material Selection Documentation
	12			7.10	Critical Systems Equipment/Instrument List (RESERVED)
	13			7.11	
	14		-	7.12	Installation Plans
	15			7.13	Instrument Control Logic and Narrative Description (RESERVED)
	16			7.14	Descriptions of Instrument Installation and Testing Procedures
	17				(RESERVED)
	18			7.15	Operating Documents
		٠			
	19		Appendix		Pretreatment Building
	20			8.1	Process Flow Diagrams
	21			8.2	Piping and Instrumentation Diagrams
	22			8.3	System Description Documentation (RESERVED)
	23			8.4	General Arrangement Drawings
	24			8.5	Civil, Structural, and Architectural Criteria and Typical Design Details
	25			8.6	Mechanical Drawings -
	26			8.7	Specifications
	27			8.8	Engineering Calculations
	28			8.9	Material Selection Documentation
	29	. :		8.10	Critical Systems Equipment/Instrument List (RESERVED)
	30			8.11	IQRPE Reports
	31	•		8.12	Installation Plans (RESERVED)
	32			8.13	Instrument Control Logic and Narrative Description
	33	•		8.14	Descriptions of Instrument Installation and Testing Procedures
	34		₹	0.15	(RESERVED)
	35			8.15	Operating Documents (RESERVED)
	36	April 1980	Appendix	9.0	LAW Building
7	37			9.1	Process Flow Diagrams
	38			9.2	Piping and Instrumentation Diagrams
	39			9.3	System Description Documentation (RESERVED)
	40			9.4	General Arrangement Drawings
	41			9.5	Civil, Structural, and Architectural Criteria and Typical Design Details
	42			9.6	Mechanical Drawings
	43			9.7	Specifications
	44			9.8	Engineering Calculations
	45			9.9	Material Selection Documentation
	46		100	9.10	Critical Systems Equipment /Instrument List (RESERVED)
	47		* * * * * * * * * * * * * * * * * * *	9.11	IQRPE Reports
	48			9.12	Installation Plans (RESERVED)
	49			9.13	Instrument Control Logic, and Narrative Description

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 3 of 210

1	9.14	Descriptions of Instrument Installation and Testing Procedures (RESERVED)
2	9.15	Demonstration Test Plan (RESERVED)
4	9.16	Demonstration Test Report (RESERVED)
5	9.17	Treatment Effectiveness Report (RESERVED)
6	9.18	Operating Documents
. 7	Appendix 10.0	HLW Building
8	10.1	Process Flow Diagrams
9	10.2	Piping and Instrumentation Diagrams
10	10.3	System Description Documentation (RESERVED)
11	10.4	General Arrangement Drawings
12	10.5	Civil, Structural, and Architectural Criteria and Typical Design Details
13	10.6	Mechanical Drawings
14	10.7	Specifications
15	10.8	Engineering Calculations
16	10.9	Material Selection Documentation
17	10.10	Critical Systems Equipment/Instrument List (RESERVED)
18	10.11	IQRPE Reports
19	10.11	Installation Plans (RESERVED)
20	10.13	Instrument Control Logic and Narrative Description
21	10.14	Descriptions of Instrument Installation and Testing Procedures
22	10.14	(RESERVED)
	10.15	Demonstration Test Plan (RESERVED)
23	10.15	Demonstration Test Plan (RESERVED)
24	10.17	Treatment Effectiveness Report (RESERVED)
25	10.17	Operating Documents
26	10.18	Operating Documents
27	Appendix 11.0	Laboratory Building
28	11.1	Process Flow Diagrams (RESERVED)
29	11.2	Piping and Instrumentation Diagrams (RESERVED)
30	11.3	System Description Documentation (RESERVED)
31	11.4	General Arrangement Drawings
32.	11.5	Civil, Structural, and Architectural Criteria and Typical Design Details
33	11.6	Mechanical Drawings (RESERVED)
34	11.7	Specifications (RESERVED)
35	11.8	Engineering Calculations
.36	11.9	Material Selection Documentation (RESERVED)
37	11.10	Critical Systems Equipment/Instrument List (RESERVED)
38	11.11	IQRPE Reports
39	11.12	Installation Plans (RESERVED)
40	11.13	Instrument Control Logic and Narrative Description (RESERVED)
41	11.14	Descriptions of Instrument Installation and Testing Procedures
42		(RESERVED)
43	11.15	Operating Documents (RESERVED)
44	Appendix 12.0	Balance of Facilities
45	12.1	Process Flow Diagrams (RESERVED)
46	12.2	Piping and Instrumentation Diagrams (RESERVED)
47	12.3	System Description Documentation (RESERVED)
48	12.4	General Arrangement Drawings (RESERVED)
49	12.5	Civil, Structural, and Architectural Criteria and Typical Design Details
50		(RESERVED)

Permit Number: WA7890008967

Modification to Revision 7 Expiration Date: September 27, 2004

Page 4 of 210

1 2		12.6 Mechanical Drawings (RESERVED) 12.7 Specifications (RESERVED)
3		12.8 Engineering Calculations (RESERVED)12.9 Material Selection Documentation (RESERVED)
4 5	· .	12.10 Critical Systems Equipment/Instrument List (RESERVED)
6		12.11 IQRPE Reports (RESERVED)
7	•	12.12 Installation Plans (RESERVED)
8		12.13 Instrument Control Logic and Narrative Description (RESERVED)
9	·	12.14 Descriptions of Instrument Installation and Testing Procedures
10		(RESERVED)
11	HI 10 D	12.15 Operating Documents (RESERVED)
12	III.10.B	STANDARD CONDITIONS AND GENERAL FACILITY CONDITIONS
13 14 15 16 17		In addition to the conditions in this chapter, the Permittees must comply with all the applicable portions of the Dangerous Waste Portion and EPA portion of the Resource Conservation and Recovery Act (RCRA) Permit for the Hanford Facility. In the event that a Unit-Specific Condition for the WTP Unit in Conditions III.10.C. through III.10.K. conflicts with a general condition in Conditions I and II of this permit, the Unit-Specific Condition shall apply to the WTP Unit.
19	Ш.10.С.	UNIT-SPECIFIC CONDITIONS FOR THE WTP UNIT
20	III.10.C.1	Facility-Specific Definitions and Acronyms
21		The following definitions are specific to the WTP Unit:
22 23 24		"ash" means a measure of the contribution of particulate matter from the melter feeds to the melter off-gas, as determined by representative sampling and analysis of the melter feed using ASTM Method D-482, or an equivalent method.
25 26		"batch" refers to waste staged in one DST designated as mixed waste for transfer to the WTP Unit for treatment.
27 28 29 30 31 32 33 34 35 36 37		"continuous monitoring system" means using a device which continuously samples the regulated parameter specified on Permit Tables III.10.H.F, III.10.I.F, III.10.J.F, and III.10.K.F, with the exception of pressure, without interruption, evaluates the detector response at least once every fifteen (15) seconds and computes and records the average value at least every sixty (60) seconds, except during allowable periods of calibration and except as defined otherwise by the CEMS Performance Specifications in 4B and 8A in Appendix B, 40 CFR Part 60. For the parameter pressure, the term "continuous monitoring system" means using a device that continuously samples the pressure without interruption and evaluates the detector response without averaging at least once each second and records the value at least every sixty (60) seconds. In addition, if the AWFCO is engaged due to a pressure exceedance, the pressure value must be recorded.
38 39 40 41		"cascade event" means when additional waste feed cut-off parameter set points deviate outside the limits specified in Permit Tables III.10.H.F, III.10.I.F, III.10.J.F, and III.10.K.F after waste feed is cut-off, but while waste or waste residues are being managed in HLW and LAW.
42 43 44 45		"dangerous and/or mixed waste management unit" means dangerous and/or mixed waste management units, areas, systems, and sub-systems as defined in Permit Tables III.10.D.A, III.10.E.A through D, III.10.F.A, III.10.G.A, III.10.H.A, III.10.I.A, III.10.J.A, and III.10.K.A.
46		"dioxin/furan" and "dioxins and furans" means tetra-, penta-, hexa-, hepta-, and octa-

chlorinated dibenzo dioxins and furans.

47

Permit Number: WA7890008967 Modification to Revision 7

Expiration Date: September 27, 2004

Page 5 of 210

1 2	"HLW Vitrification System" is defined as specified on Permit Tables III.10.J.A and B, and III.10.K.A and B.
3 4	"hourly rolling average" or "HRA" shall mean the arithmetic mean of the sixty (60) most recent one-minute readings recorded by the continuous monitoring system.
5 6	"LAW Vitrification System" is defined as specified on Permit Tables III.10.H.A and B, and III.10.I.A and B.
7 8 9	"mode of operation" means operation of the LAW Vitrification System or the HLW Vitrification System within set limits for each operating parameter specified in Permit Tables III.10.H.D and F (for LAW) and Permit Tables III.10.I.D and F (for HLW).
10 11	"one-minute average" means the average of detector responses calculated at least every sixty (60) seconds from responses obtained at least every fifteen (15) seconds.
12 13	"Permittees" means the United States Department of Energy (owner/operator) and Bechtel National, Inc. (co-operator).
14 15	"Pretreatment Plant Miscellaneous Unit Systems" is defined as specified on Permit Tables III.10.G.A and B.
16 17 18 19	"primary sump" means any pit or reservoir that meets the WAC 173-303-040 definition of "tank," and those troughs/trenches connected to it, that serve to collect dangerous/hazardous waste, deliberately introduced (e.g., from decontamination or treatment activities), for transport to TSD facilities.
20	"rolling average" means the average of all one-minute averages over the averaging period.
21 22 23 24	"secondary sump" means any pit or reservoir that meets the WAC 173-303-040 definition of "tank," and those troughs/trenches connected to it, that serve to collect dangerous/hazardous waste, not deliberately introduced (e.g., from spills, leaks, or overflows), for transport to TSD facilities.
25 26 27	"standard operating procedure" or "SOP" shall mean a written description of the procedures by which a process, equipment, etc. shall be operated. An SOP may be written by the manufacturer and/or the Permittees.
28 29 30 31 32 33 34	"successful completion of the demonstration test" shall mean operations including a minimum of three test runs without significant interruptions (i.e., each test run was completed on the same day initiated and the samples have been preserved and maintained intact, and one in which sampling of exhaust gas was representative of the LAW Vitrification System or HLW Vitrification System Operations, whichever is applicable, and adequate to achieve evaluation of PODCs destruction and removal efficiency (DRE) to 99.99%).
35 36	"TEQ" means toxicity equivalence, the international method of relating the toxicity of various dioxin/furan congeners to the toxicity of 2,3,7,8- tetrachlorodibenzo-p-dioxin.
37 38	"pre-process" means prior to introduction into a dangerous or mixed waste management unit at the WTP Unit.
39 40	"in-process" means duration of a waste in a dangerous or mixed waste management unit at the WTP Unit.
41	"post-process" means prior to the introduction into a subsequent dangerous or mixed waste

"vendor information" means documentation prepared by a vendor (e.g., catalog cut sheets) for plant items that are routinely manufactured and stocked by vendors (i.e., items that are

management unit at the WTP Unit or prior to shipment from the WTP Unit.

42

43

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 6 of 210


1 2 3 4		considered "off the shelf") and are not being procured in accordance with Permittee's engineering drawings and specifications. Documentation such as catalog cut sheets shall be annotated to specify selected items which meet Permittee's procurement requirements. Documentation associated with "one of a kind", custom items, and commercial grade items (e.g., bulk pipe, valves) that will be procured in accordance with the Permittees engineering
6 7		drawings and specifications is not considered vendor information. Changes to the drawings and specifications may require a permit modification.
8 9		The following acronyms are specific to the WTP Unit:
10		AWFCO Automatic Waste Feed Cut-off
11		CEMS Continuous Emissions Monitoring System
12		CMS Continuous Monitoring System
13		DFETP Dioxin and Furan Emission Test Plan
14		DRE Destruction and Removal Efficiency
15		Dscf Dry standard cubic feet
16	•	ERP Emergency Response Plan
17		IHLW Immobilized High-Level Waste (Glass)
18		ILAW Immobilized Low-Activity Waste (Glass)
19		IQRPE Independent, qualified, registered, professional engineer
20		HLW High-level Waste
21		LAW Low Activity Waste
22		NCR Nonconformance Report
23		PODC Principal Organic Dangerous Constituents
24	· 	RDTP Revised Demonstration Test Plan
25		RPP-WTP River Protection Project-Waste Treatment Plant
26		TOC Total Organic Carbon
27 28		WTP River Protection Project - Waste Treatment and Immobilization Project (also known as the Waste Treatment Plant and Vitrification Plant)
29		6Mo Six Percent Molybdenum Alloy
30		304L ASTM A240 Grade 304L Stainless Steel
31	· · · · · · · · · · · · · · · · · · ·	316L ASTM A240 Grade 316L Stainless Steel
32	III.10.C.2.	General Waste Management
33 34 35 36 37 38 39	III.10.C.2.a.	The Permittees may not commence treatment or storage of dangerous waste or mixed waste in any new or modified portion of the facility until the Permittees have received a Permit modification approval pursuant to Permit Conditions III.10.C.2.e. and III.10.C.2.f., or III.10.C.2.g., and submitted to Ecology, by certified mail, express mail, or hand delivery, a letter signed by the Permittees and a Registered Professional Engineer stating that the facility has been constructed or modified in compliance with the Permit in accordance with WAC 173-303-810(14)(a); and
40 41		 Ecology has inspected the modified or newly constructed facility and finds it is in compliance with the conditions of the Permit, or

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 7 of 210




Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 8 of 210



for these parameters for pre-process, in-process, and post-process operations addressing

on a unit specific basis treatment effectiveness, as specified in Tables III.10.E.E

compatibility, safe operation, and compatibility with unit materials of construction.

through H, III.10.G.C, III.10.H.C, III.10.I.C, III.10.J.C, and III.10.K.C, waste

45

46

47

48

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 9 of 210

2		Amend the sampling, analysis, and QA/QC procedures to include these parameters and the monitoring frequency.
3 4 5 6 7		iv. Requirements that the Permittees shall, for Type I sumps if liquids are detected, and for Type II sumps, as defined in Attachment 51, Chapter 4.0 of this Permit, if liquid levels are outside normal operating parameters, either collect the liquid and return to the treatment process, or designate the sump contents for proper management and disposal prior to removal.
8		v. For ILAW and IHLW containers, a description of procedures used to verify exterior container surfaces are visually free of mixed waste.
10 11		vi. Requirement that wastes generated at the WTP Unit meet the receiving authorized TSD facility waste acceptance criteria prior to a waste stream transfer.
12 13		vii. Requirements and criteria for reevaluation of sampling and analysis frequency for all waste streams.
14 15		viii. Documentation demonstrating methods for obtaining samples of wastes are representative as discussed in WAC 173-303-110(2).
16	III.10.C.4.	Recordkeeping
17 18 19 20 21 22	Ш.10.С.4.а.	The unit specific portion of the Hanford Facility Operating Record shall include the documentation specified in Attachment 51, Chapter 12.0, General Condition II.I, applicable to the WTP Unit and other documentation specified in Attachment 51. The facility and unit specific record keeping requirements are distinguished in Table 12-1 of the General Information portion, Attachment 33 to the Sitewide Permit, and tied to the associated Sitewide Permit Conditions.
23	III.10.C.5	Procedure to Prevent Hazards
24 25	III.10.C.5.a.	The Permittees shall design, construct, and operate the WTP Unit in compliance with Attachment 51, Chapter 6.0, Section 6.1.
26 27 28 29 30 31 32 33		Prior to the initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees shall update and resubmit for approval Attachment 51, Chapter 6.0, Sections 6.3, 6.4, and 6.5 as a permit modification pursuant to Permit Conditions III.10.C.2.e and III.10.C.2.f, to be consistent with design details and schedule described in Attachment 51, Appendix 1.0. The WTP Unit fire protection systems shall be constructed to the applicable codes listed in Attachment 51, Chapter 6.0, Section 6.3.1.4. Updated Section 6.4.4. shall include descriptions of the essential loads and critical systems supplied with back-up, uninterruptible, and standby power.
34 35 36 37 38 39 40 41 42 43	III.10.C.5.c.	The Permittees shall inspect the WTP Unit to prevent malfunctions and deterioration, operator errors, and discharges that may cause or lead to the release of dangerous waste constituents to the environment, or a threat to human health. Inspections must be conducted in accordance with the WTP Unit Inspection Schedule, Attachment 51, Chapter 6.0, Section 6.2. Prior to the receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees shall update and resubmit to Ecology for review and approval the Inspection Schedule in Attachment 51, Chapter 6.0 of this Permit as a permit modification pursuant to Permit Conditions III.10.C.2.e and III.10.C.2.f, and Compliance Schedule in Attachment 51, Appendix 1.0. The revised schedule shall include, but not be limited to, i. through v. below. In addition, the Permittees shall submit to Ecology for incorporation into the Administrative Record, the basis for developing Inspection Schedule frequencies:
45 46		 Detailed dangerous and/or mixed waste management unit specific and general inspection schedules and description of procedures (not examples) pursuant to WAC 173-303-

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 10 of 210

	1 2 3 4 5		395(1)(d), 173-303-630(6), 173-303-640(4)(a)(i) and (6), 173-303-670(7)(b) in accordance with 173-303-680(3), 40 CFR, 264.1101(c)(4). The inspection schedule shall be presented in the form of a table that includes a description of the inspection requirement, inspection frequency, and types of problems to look for during the inspections.
	6 7		ii. The proposed locations (scaled drawing with layout) and capabilities of camera(s) (i.e., zoom angles, field of view, etc.) to be used for remote inspections.
	8 9 10		iii. Schedule and program description for performing integrity assessments as specified in Permit Conditions III.10.E.9.e.i., III.10.G.10.e.i., III.10.H.5.e.i., III.10.I.1.a.v., III.10.J.5.e.i., and III.10.K.1.a.v.
	11 12 13 14		iv. Inspection schedules for leak detection system and control instrumentation to include, but not limited to, valves pressure devices, flow devices, measuring devices, as specified in Permit Conditions III.10.E.9.e.xi, III.10.F.3.c, and III.10.G.10.e.xii, and Permit Conditions III.10.H.5.f.xvi, and III.10.J.5.f.xvi.
	15 16		v. Inspection schedule shall include inspections for all dangerous and/or mixed waste management units specified in Permit Sections III.10.D, E, F, G, H, I, J, and K.
	17 18	III.10.C.5.d.	The Permittees shall equip the WTP Unit with the equipment specified in Attachment 51, Chapter 6.0, as required by WAC 173-303-340(1) and Condition II.B.1 of this Permit.
:	19 20 21	III.10.C.5.e.	The Permittees shall test and maintain the equipment specified in Attachment 51, Chapter 6.0, as necessary, to assure proper operation in the event of emergency as required by Condition II.B.2 of this Permit.
:	22 23 24 25	III.10.C.5.f.	The Permittees shall maintain access to communications or alarms pursuant to WAC 173-303-340(2), as provided in the <i>RPP-WTP Emergency Response Plan</i> , Attachment 51, Chapter 7.0 as required by Condition II.B.3 of this Permit.
. :	26	III.10.C.6.	Contingency Plan
	27 28 29 30 31	III.10.C.6.a.	The Permittees shall immediately carry out applicable provisions of the <i>RPP-WTP Emergency Response Plan</i> , Attachment 51, Chapter 7.0 of this Permit, pursuant to WAC 173-303-360(2), whenever there is a release of dangerous and/or mixed waste or dangerous waste constituents, or other emergency circumstance, any of which threatens human health or the environment.
	32 33 34 35 36	III.10.C.6.b.	Prior to the initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees shall update and resubmit the Contingency Plan in compliance with Attachment 51, Chapter 7.0, and pursuant to WAC 173-303-350(5), as a permit modification pursuant to Permit Conditions III.10.C.2.e and III.10.C.2.f, to be consistent with design details and schedule described in Attachment 51, Appendix 1.0.
3	37 38 39 40	Ш.10.С.6.с.	After initial receipt of dangerous and/or mixed waste, the Permittees shall review and amend, if necessary, the applicable portions of the Contingency Plan, Attachment 51, Chapter 7.0 of this Permit, and in accordance with the provisions of WAC 173-303-350(5) and WAC 173-303-830(4). The Contingency Plan shall be amended as a permit modification pursuant to Permit Conditions III.10.C.2.e and III.10.C.2.f.
4	12	III.10.C.6.d.	RESERVED.
4	13 14 15	III.10.C.6.e.	Prior to the initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees shall comply with the requirements of WAC 173-303-350(3) and -360(1) concerning the emergency coordinator specific to the WTP Unit in compliance with Permit Condition II.A.4.

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 11 of 210

1.	III.10.C.7.	Training Plan
2 3 4 5 6	III.10.C.7.a.	Prior to the initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees shall update and resubmit, to Ecology for review and approval, the Training Program description in Attachment 51, Chapter 8.0 of this Permit as a permit modification pursuant to Permit Conditions III.10.C.2.e and III.10.C.2.f, and Compliance Schedule in Attachment 51, Appendix 1.0. The revised Training Program description shall include but not be limited to:
7 8		i. Detailed unit specific and general Training Program descriptions (not typical) consistent with WAC 173-303-806(4)(a)(xii).
9 10 11 12 13 14		ii. Sufficient detail to document that the training and qualification program for all categories of personnel whose activities may reasonably be expected to directly affect emissions from the LAW and HLW Systems, except control room operators, is appropriately consistent with 40 CFR 63.1206(c)(6)(ii), and for control room operators, is appropriately consistent with 40 CFR 63.1206(c)(6)(i) and 63.1206(c)(6)(iii) through 63.1206(c)(6)(vi) [WAC 173-303-680(2)].
15 16 17 18	III.10.C.7.b.	The Permittees shall ensure that the LAW and HLW Systems are operated and maintained, at all times, by persons who are trained and qualified to perform these and any other duties that may reasonably be expected to directly affect emissions from the LAW and HLW Systems [WAC 173-303-680(2)].
19 20 21 22	III.10.C.7.c.	The Permittees shall conduct personnel training in accordance with the approved description of the WTP Unit Training Plan, Attachment 51, Chapter 8.0 of this Permit, pursuant to WAC 173-303-330. The Permittees shall maintain documents in accordance with Condition II.C.1. of this Permit and WAC 173-303-330(2) and (3).
23	ПІ.10.С.7.d.	RESERVED.
24 25 26 27 28 29	III.10.C.7.e.	The Permittees shall submit, under separate cover, the actual detailed WTP Unit Dangerous Waste Training Plan in accordance with the Compliance Schedule in Attachment 51, Appendix 1.0. The WTP Unit Dangerous Waste Training Plan will be reviewed for compliance with the outline of the training program in Attachment 51, Chapter 8.0 and requirements of WAC 173-303-330. The Training Plan will be incorporated into the Administrative Record.
31 32 33 34	III.10.C.8.a.	The Permittees must conduct closure of the WTP Unit according to the Closure Plan in Attachment 51, Chapter 11.0, and Conditions II.J. (Facility Closure), II.K. (Soil/Ground Water Closure Performance Standards), and III.10.C.8. of this Permit. The closure plan shall be modified according to provisions of WAC 173-303-610(3)(b)(ii).
35 36 37 38 39 40 41	III.10.C.8.b.	Prior to initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees shall update and resubmit the Closure Plan, Attachment 51, Chapter 11.0 of this Permit, for approval as a permit modification pursuant to Permit Condition III.10.C.2.g., to be consistent with design details and schedule described in Attachment 51, Appendix 1.0. The updated Closure Plan must be consistent with the closure performance standards specified in Permit Condition II.K, WAC 173-340 and, in addition for Containment Buildings, consistent with 40 CFR 264.1102(b) as referenced by WAC 173-303-695.
42 43 44		The Permittees shall submit, for Ecology review and approval, an update to the Closure Plan, Attachment 51, Chapter 11.0 within one hundred eighty (180) days prior to commencing partial closure, as a permit modification pursuant to Permit Conditions

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 12 of 210


1 2 3	III,10.C.8.d.	Ecology, for review and approval, a Sampling and Analysis Plan and a revised Closure Plan as a permit modification pursuant to Permit Conditions III.10.C.2.e and III.10.C.2.f.
4	III.10.C.8.e.	At least forty-five (45) days before initiating closure, the Permittees must provide Notification of Closure pursuant to WAC 173-303-610(3)(c).
6 7 8 9		Ecology may require additional sampling and/or investigation after the Permittees implement the approved Sampling and Analysis Plan if Ecology determines that the sampling and analyses have not adequately demonstrated whether clean closure has been achieved. Such a requirement will be implemented pursuant to WAC 173-303-830(3). Additional sampling and analysis may be required for the following reasons:
11 12		i. Specialized sample collection or analytical techniques are required to ensure adequate quantitation limits for chemical constituents; or
13		ii. Results indicate the need to analyze for additional constituents at certain locations; or
14 15		iii. Results indicate additional soil or groundwater sampling is required in certain locations; or
16 17		iv. Other reasons indicate the Sampling and Analysis Plan has not adequately demonstrated whether clean closure has been achieved.
18	III.10.C.8.g.	RESERVED.
19 20 21 22 23 24 25	III.10.C.8.h.	Documentation supporting the independent registered professional engineer's certification of closure must be submitted to Ecology with the closure certification required by WAC 173-303-610(6). In addition to the items in Attachment 51, Chapter 11.0, the documentation must include the following and other information Ecology may request. The Permittees are required to furnish documentation supporting the independent registered professional engineer's certification to Ecology upon request, until Ecology has notified the Permittees in writing that Ecology agrees with and has accepted the Permittees' closure certification:
26		i. Sampling procedures that were followed;
27		ii. soil and concrete locations that were sampled;
28 29	4	iii. Sample labeling and handling procedures that were followed, including chain of custody procedures;
30 31 32 33 34 35 36		iv. Description of procedures that were followed to decontaminate concrete or metal to meet the clean closure standards as set by Ecology, on a case by case basis, in accordance with the closure performance standards of WAC 173-303-610(2)(a)(ii) and in a manner that minimizes or eliminates post-closure escape of dangerous waste constituents, or to achieve a "clean debris surface" as specified in 40 CFR 268.45, Table 1, concrete surfaces, as incorporated by reference in WAC 173-303-140. [WAC 173-303-610(2)(b)(ii)].
37		v. Laboratory and field data, including supporting QA/QC summary;
38		vi. Report that summarizes closure activities;
39		vii. Copy of all field notes taken by the independent registered professional engineer; and
40		viii. Copy of all contamination survey results.
41	III.10.C.9.	Critical Systems
42 43	II.10.C.9.a.	The WTP Unit critical systems, as defined in the Hanford Site-wide Permit definition section, are identified in Attachment 51, Appendix 2.0.

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 13 of 210



4

6

7

8

31

32 33

34

35

36

37

38

39

40

41

42

43 44

45

46

47

48 49

- III.10.C.9.c. The Permittees shall conduct all construction subject to this Permit in accordance with the approved designs, plans, and specifications that are required by this Permit, except as specified in Conditions III.10.C.9.d. or III.10.C.9.e. For purposes of Conditions III.10.C.9.d. and III.10.C.9.e., the Ecology representative will be an Ecology construction inspector, project manager, or other designated representative of Ecology.
- III.10.C.9.d. The Permittees shall submit a nonconformance report (NCR) to the Ecology representative, 9 as applicable, within five (5) calendar days of the Permittees becoming aware of 10 incorporation of minor nonconformance from the approved designs, plans, and 11 specifications into the construction of critical systems, as defined in the Hanford Site-wide 12 Permit definition section. Such minor nonconformance shall be defined, for the purposes of 13 this Permit Condition, as nonconformance that is necessary to accommodate proper 14 construction and the substitution of the use of equivalent or superior materials or equipment 15 that do not substantially alter the Permit conditions or reduce the capacity of the facility to 16 protect human health or the environment. Such minor nonconformance shall not be 17 considered a modification of this Permit. If Ecology determines that the nonconformance is 18 not minor, it will notify the Permittees in writing that a permit modification is required for 19 the deviation and notify the Permittees in writing whether prior approval is required from 20 Ecology before work proceeds which affect the nonconforming item. 21
- 22 III.10.C.9.e. The Permittees shall formally document, with a nonconformance report (NCR), incorporation of minor nonconformance from the approved designs, plans, and 23 specifications into the construction of non-critical systems subject to this Permit. Such 24 25 minor nonconformance shall not be considered a modification of this Permit. All nonconformance reports shall be maintained in the WTP Unit Operating Record and shall be 26 made available to Ecology upon request or during the course of an inspection. If Ecology 27 28 determines that the nonconformance is not minor, it will notify the Permittees in writing that a permit modification is required for the deviation and whether prior approval is required 29 from Ecology before work proceeds which affects the nonconforming item. 30
 - III.10.C.9.f. For each Critical System identified in Attachment 51, Appendix 2.0 or meets the definition of Critical System as defined in this Permit, the Permittees shall submit to Ecology for review and approval, following the schedule in Attachment 51, Appendix 1.0 of this Permit, the information identified in Permit Conditions III.10.D.10., III.10.E.9., III.10.F.7., III.10.G.10., III.10.H.5., and III.10.J.5. Information Ecology determines to incorporate into the Permit will follow the Permit Condition III.10.C.2.g. process, unless stated otherwise within the specific permit condition. Information Ecology determines necessary to support design basis will be incorporated into the Administrative Record.
 - III.10.C.9.g. Upon completion of the WTP Unit construction subject to this Permit, the Permittees shall produce as-built drawings of the project which incorporate the design and construction modifications resulting from all change documentation as well as modifications made pursuant to Permit Conditions III.10.C.2.e., III.10.C.2.f., and III.10.C.2.g. The Permittees shall place the as-built drawings into the operating record within twelve (12) months of completing construction.
 - III.10.C.9.h. The Permittees shall formally document changes to approved designs, plans, and specifications with design change documentation [e.g., Design Change Authorization (DCA), Design Change Notice (DCN), Field Change Request (FCR), Field Change Notice (FCN)]. All design change documentation shall be maintained in the WTP Unit unit-specific Operating Record and shall be made available to Ecology upon request or during the

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 14 of 210

1 2 3 4 5		course of an inspection. For any design change documentation affecting any critical systems, the Permittees shall provide copies to Ecology within five (5) working days. Identification of critical systems shall be included by the Permittees in each WTP Unit unit-specific dangerous waste permit application, closure plan, or permit modification, as appropriate.
6 7 8		Ventilation system duct work is not required to be doubly contained within the WTP Unit. However, upon discovery of accumulation of liquids, a compliance plan will be submitted within sixty (60) days of discovery to correct the problem.
9	III.10.C.10	Equivalent Materials
10 11 12 13 14 15 16 17 18 19 20	III.10.C.10.a	If certain equipment, materials, and administrative information (such as names, phone numbers, addresses) are specified in this Permit, the Permittees may use equivalent or superior substitutes. Use of such equivalent or superior items within the limits (e.g., ranges, tolerances, and alternatives) already clearly specified in sufficient detail in Attachment 51 of this Permit, are not considered a modification of this Permit. However, the Permittees must place documentation of the substitution, accompanied by a narrative explanation and the date the substitution became effective in the operating record within seven (7) days of putting the substitution into effect, and submit documentation of the substitution to Ecology. Upon review of the documentation of the substitution, if deemed necessary, Ecology may require the Permittees to submit a permit modification in accordance with Permit Conditions III.10.C.2.e. and III.10.C.2.f.
21 22		Note: The format of tables and forms contained in Attachment 51 of this Permit are not subject to the requirements of this Permit, and may be revised at the Permittees' discretion.
23 24 25 26 27 28	Ш.10.С.10.Ь	If Ecology determines that a substitution was not equivalent to the original, they will notify the Permittees that the Permittees' claim of equivalency has been denied, of the reasons for the denial, and that the original material or equipment must be used. If the product substitution is denied, the Permittees shall comply with the original approved product specification, find an acceptable substitution, or apply for a permit modification in accordance with Permit Conditions III.10.C.2.e. and III.10.C.2.f.
29	III.10.C.11.	Risk Assessment
30 31 32 33 34 35 36	ПІ.10.С.11.а.	The Permittees shall submit, in accordance with Attachment 51, Appendix 1.0 of this Permit to Ecology for approval, the "Previously Submitted Risk Assessment Workplan," Attachment 51, Appendix 6.1.1. of this Permit, revised in consultation with Ecology to address the revisions (NOD/responses) documented in Attachment 51, Appendix 6.1.2 and updated to address the following, as a permit modification pursuant to Permit Conditions III.10.C.2.e. and III.10.C.2.f. The updated previously submitted Risk Assessment Work Plan shall be added to Attachment 51 as Appendix 6.2 (Risk Assessment Work Plan).
37 38		 i. EPA guidance for performance of Human Health and Ecological Risk Assessments for Hazardous Waste Combustion Facilities current at the time of the submittal;
39		ii. Toxicity data current at the time of the submittal;
40 41		iii. Compounds newly identified or updated emissions data from current waste characterization and emission testing;
42 43		iv. Air modeling updated to include stack gas parameters based on most current emissions testing and WTP Unit design;
44		v. Physical/transport properties of constituents current at the time of the submittal;
45		vi. Process Description based on most current WTP Unit design;

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 15 of 210

1		vii. Emissions data and an supporting calculations based on most current with Omi; and
2		viii. Update of receptor locations based on land use or land use zoning changes, if any.
3 4	III.10.C.11.b.	The Permittees shall submit for Ecology approval, prior to initial receipt of dangerous and/or mixed waste in the WTP Unit, a Pre-Demonstration Test Risk Assessment Report as
5 6 7 8 9 10 11 12 13 14		Attachment 51, Appendix 6.3 addressing direct and indirect human health and ecological risks performed pursuant to Ecology approved work plan under Permit Condition III.10.C.11.a. This report shall also include submittal of projected stack emissions data in Tables III.10.G.D., III.10.H.E., and III.10.J.E. of this Permit and Attachment 51, Appendix 6.3.1 (Basis and Assumptions), completed and updated which details the basis and assumptions for these emissions, including but not limited to, projected operating conditions, feed-rates, and treatment effectiveness, consistent with information provided and approved pursuant to Permit Conditions III.10.G.6., III.10.G.10., III.10.H.5., and III.10.J.5. as a permit modification pursuant to Permit Conditions III.10.C.2.e. and III.10.C.2.f.
15 16 17 18 19 20 21 22 23 24	III.10.C.11.c.	Within ninety (90) days of Ecology approval of the Demonstration Report(s) submitted pursuant to Permit Condition III.10.H.3.d.i, the Permittees shall submit a Final Risk Assessment Report as Attachment 51, Appendix 6.4, incorporating the emission test results from the Demonstration Report(s). The Final Risk Assessment Report shall be prepared in accordance with the Risk Assessment Work Plan, as approved by Ecology pursuant to Permit Condition III.10.C.11.a, except the following updates are hereby incorporated. The Permittees shall also submit with this Final Risk Assessment Report, Tables III.10.G.D. and III.10.I.E. of this Permit and Attachment 51, Appendix 6.4.1 (Basis and Assumptions) updated to incorporate the emissions data from this Final Risk Assessment Report(s), as a permit modification pursuant to Permit Conditions III.10.C.2.e. and III.10.C.2.f.
25		i. Toxicity data current at the time of the submittal;
26 27		ii. Compounds newly identified or updated emissions data from current waste characterization and emission testing;
28 29		iii. Air modeling updated to include stack gas parameters based on most current emissions testing;
30		iv. Physical/transport properties of constituents current at the time of the submittal;
31		v. Update of receptor locations based on land use or land use zoning changes, if any;
32		vi. Process description based on current WTP Unit design;
33		vii. Emissions data and all supporting calculations based on current WTP Unit; and
34 35		viii. Data from final risk assessment report pursuant to Permit Condition III.10.C.11.d, if available first, or simultaneously.
36 37 38 39 40 41 42 43 44 45		Within ninety (90) days of Ecology approval of the Demonstration Report(s) submitted pursuant to Permit Condition III.10.J.3.d.i, the Permittees shall submit a Final Risk Assessment Report as Attachment 51, Appendix 6.4, incorporating the emission test results from the Demonstration Report(s). The Final Risk Assessment Report shall be prepared in accordance with the Risk Assessment Work Plan, as approved by Ecology pursuant to Permit Condition III.10.C.11.a, except the following updates are hereby incorporated. The Permittees shall also submit with this Final Risk Assessment Report, Tables III.10.G.D. and III.10.K.E. of this Permit and Attachment 51, Appendix 6.4.1 (Basis and Assumptions) updated to incorporate the emissions data from this Final Risk Assessment Report, as a permit modification pursuant to Permit Conditions III.10.C.2.e. and III.10.C.2.f.
46		i Toxicity data current at the time of the submittal:


Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 16 of 210

1 2		ii. Compounds newly identified or updated emissions data from current waste characterization and emission testing;
3		iii. Air modeling updated to include stack gas parameters based on most current emission testing;
5		iv. Physical/transport properties of constituents current at the time of the submittal;
6		v. Update of receptor locations based on land use or land use zoning changes, if any;
7	• •	vi. Process description based on current WTP Unit design;
8		vii. Emissions data and all supporting calculations based on current WTP Unit; and
9 10	1.3	viii. Data from final risk assessment report pursuant to Permit Condition III.10.C.11.c, if available first, or simultaneously.
11 12	III.10.C.11.e.	The Final Risk Assessment Report(s) required by Permit Conditions III.10.C.11.c. and III.10.C.11.d. may be combined, or provided separately, as appropriate.
13	III.10.C.12	Air Emissions
14 15 16 17 18	•	Prior to installing or using any equipment subject to the requirements of WAC 173-303-690, the Permittees shall obtain a Permit Modification following the Permit Condition III.10.C.2.g. process to incorporate WAC 173-303-690 standards into the permit application and this Permit prior to generation/receipt of dangerous and/or mixed waste in the WTP Unit.
19 20 21 22 23		Prior to installing or using any equipment subject to the requirements of WAC 173-303-691, the Permittees shall obtain a Permit Modification following the Permit Condition III.10.C.2.g. process to incorporate WAC 173-303-691 standards into the permit application and this Permit prior to generation/receipt of dangerous and/or mixed waste in the WTP Unit.
24 25 26 27		The Permittees shall comply with the organic air emission standards as set forth in WAC 173-303-692. The Permittees shall obtain a permit modification following the Permit Condition III.10.C.2.g. process to incorporate WAC 173-303-692 standards into the permit application and this Permit prior to generation/receipt of dangerous waste in the WTP Unit
28	III.10.C.13	Remote Data Access
29 30 31 32 33 34 35		Onsite, unrestricted, twenty-four (24) hour access to key WTP Unit operating data and emissions monitoring data shall be provided to Ecology. This onsite, unrestricted access shall include providing and maintaining for Ecology only use a computer terminal and printer linked to key WTP Unit operating data and emissions monitoring data. This terminal shall be equipped with all necessary software and hardware to monitor, retrieve, and trend this data. Additional remote access will be provided on Ecology request if security concerns can be addressed.
36		
37	III.10.D.	CONTAINERS
38		Container Storage Areas and Storage Limits
39 40 41 42 43 44	, , , , , , , , , , , , , , , , , , ,	The Permittees may store, in containers, all dangerous and/or mixed waste listed in the Part A, Forms Attachment 51, Chapter 1.0 of this Permit, in accordance with the WAP, Attachment 51, Chapter 3.0 of this Permit, as approved pursuant to Permit Conditions III.10.C.3. and III.10.C.2. Total containerized dangerous and/or mixed waste storage at the Facility shall not exceed 2,780,000 gallons (372,520 cubic feet) pursuant to requirements in Permit Condition III.10.D.1.b.

Modification to Revision 7

Expiration Date: September 27, 2004

Page 17 of 210




III.10.D.3.a, RESERVED.

47

Expiration Date: September 27, 2004


Page 18 of 210



Modification to Revision 7


Expiration Date: September 27, 2004

Page 19 of 210



Expiration Date: September 27, 2004


Page 20 of 210



Modification to Revision 7

Expiration Date: September 27, 2004

Page 21 of 210



Expiration Date: September 27, 2004 Page 22 of 210

1 2 3 4 5 6 7 8		stored; for permanent containment systems, how the base underlying the containers is sloped (i.e., floor slopes to sumps) or the containment system is otherwise designed and operated to drain and remove liquids resulting from leaks, spills, or other liquids, or how containers are kept from contact with standing liquids in the permanent containment system (i.e., elevated or are otherwise protected); for container storage areas without permanent containment systems, a description of how the storage area is designed or operated to drain and remove liquids or how containers are kept from contact with standing liquids;
9 10	ii.	Permanent containment systems materials selection documentation (including, but not limited to, materials of construction, coatings and liner materials for concrete portions of containment systems);
12 13 14	iii.	Sketches, drawings, or data demonstrating compliance with WAC 173-303-630(8) (location of buffer zone and containers holding ignitable or reactive waste) and WAC 173-303-630(9)(c) (location of incompatible waste), where applicable;
5 16 17	iv. *	Submit Permit Table III.10.D.B. completed to provide for all permanent containment systems, the information as specified in each column heading, consistent with information to be provided in i. through iii. above.
18 19 20 21 22 23 24 25 26 27 28	shall 51, A inco this Atta infor Concord III.1 at a residue.	r to initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees I update and submit to Ecology, consistent with the schedule described in Attachment Appendix 1.0, for review and approval, the following, as specified below, for reporation into Attachment 51, Chapter 4.0, and Appendices 9.18, 10.18, and 12.15 of Permit, except Permit Condition III.10.D.10.c.vii., which will be incorporated into chment 51, Chapter 6.0 of this Permit. In order to incorporate the following rmation (specified below) into Attachment 51, Appendix 9.18, 10.18, and 12.15, Permidition III.10.C.2.g. will be followed. All information provided under this permit lition must be consistent with information provided pursuant to Permit Conditions 0.D.10.b., III.10.D.10.c., and III.10.D.10.d. as approved by Ecology, and will include minimum, the following information as required pursuant to WAC 173-303-630 and C 173-303-340:
10	i.	Attachment 51, Chapter 4.0, Narrative Descriptions, updated; Descriptions of procedures for addition and removal of waste from containers;
1 2 3	i i.	Descriptions of procedures for opening and closing of containers, including any inspections performed prior to opening;
5 5	iv.	Descriptions of procedures for handling and transport of containers within the WTP Unit;
6 7 8	v .	Description of the tracking system used to track containers throughout the WTP Unit pursuant to WAC 173-303-380. The tracking system, at a minimum, will do the following:
9		A. Track the location of containers within the WTP Unit;
·0 ·1		B. Track which containers have been shipped off-facility and/or off-site, and to where they have been shipped;
2		C. For containers intended for transport off-site, include information in accordance with the requirements specified in WAC 173-303-190(3)(b);
4		D. Record the date container is placed in the container storage area;

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 23 of 210

٠.	1 2 3 4			E. Record the nature of the waste in any given container, including dangerous waste designation codes, any associated land disposal restriction treatment requirements, and the major risk(s) associated with the waste (as described in Permit Conditions III.10.D.5.a. and III.10.D.5.c.).
	5 6 7		vi.	Descriptions of procedures for container spacing, stacking, and labeling pursuant to WAC 173-303-630(3), WAC 173-303-630(5)(c), WAC 173-303-340(3), WAC 173-303-630(6);
	8		vii.	Descriptions of procedures for investigating container storage areas and investigating and repairing containment systems [WAC 173-303-320, WAC 173-303-630(6)];
	10 11		viii.	Descriptions of procedures for responding to damaged (e.g., severe rusting, apparent structural defects) or leaking containers [WAC 173-303-630(2)];
	12 13 14		ix.	Descriptions of operational procedures demonstrating how accumulated liquids can be analyzed and removed from permanent and portable containment systems to prevent overflow [WAC 173-303-806(4)(b)(i)(E)];
	15 16 17 18 19 20 21 22 23 24 25		х.	For portable containment systems, vendor information, design drawings, or sketches showing the following information. These items shall include as a minimum basic design parameters, dimensions, and materials of construction; how the design promotes positive drainage control (such as a locked drainage valve) to prevent release of contaminated liquids and so that uncontaminated liquids can be drained promptly for convenience of operation; how the base underlying the containers is sloped (i.e., floor slopes to sumps) or the containment system is otherwise designed and operated to drain and remove liquids resulting from leaks, spills, or other liquids, or how containers are kept from contact with standing liquids in the containment system (i.e., elevated or are otherwise protected); and capacity of the containment system relative to the volume of the largest container to be stored;
	26 27 28		xi.	Where ignitable and reactive waste are stored or otherwise managed in containers, a description of the procedures used to ensure compliance with WAC 173-303-630(8)(a) and (b);
	29 30 31		xii.	Where incompatible waste are stored or otherwise managed in containers, a description of the procedures used to ensure compliance with WAC 173-303-630(9)(a) and (b), and 173-303-395(1)(b) and (c);
	32 33 34		xiii.	Submit Permit Table III.10.D.C completed to provide for all portable containment systems, the information as specified in each column heading, consistent with information to be provided in i. through xii. above;
	35 36		xiv.	Test procedures and results or other documentation or information to show that the waste do not contain free liquids, as applicable.
	37 38 39 40 41 42 43	III.10.D.10.d.	App and 10.13 51, 0	r to initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees submit to Ecology, consistent with the schedule described in Attachment 51, endix 1.0, for review and approval, completed Permit Tables III.10.D.A, III.10.D.B, III.10.D.C, for incorporation into Attachment 51, Chapter 4.0, and Appendices 9.18, 8, and 12.15 of this Permit. In order to incorporate the information into Attachment Chapter 4.0, and Appendices 9.18, 10.18, and 12.15 of this Permit, Permit Condition 0.C.2.g. process will be followed.

Modification to Revision 7

Expiration Date: September 27, 2004

Page 24 of 210

Table III.10.D.A - Container Storage Areas Description

Dangerous and Mixed Waste Container Storage Areas	Maximum Capacity Gallons (Solids) (ft ³) ^d	Maximum Capacity (Liquid ^c)
LAW Vitrification Plant	(11)	
ILAW Buffer Container Storage Area ^a	89,099 gal. (11,939 ft ³)	RESERVED
ILAW Container Storage Area	889,448 gal. (119,186 ft ³)	RESERVED
LAW Container Storage Area	80,549 gal. (10,794 ft ³)	RESERVED
HLW Vitrification Plant		
IHLW Canister Storage Area ^a	245,504 gal. (32,898 ft³)	RESERVED
HLW Container Storage Area No. 1	266,654 gal. (35,732 ft ³)	RESERVED
HLW Container Storage Area No. 2	71,999 gal. (9,648 ft³)	RESERVED
HLW Container Storage Area No. 3	43,392 gal. (5,815 ft ³)	RESERVED
Other Areas		
Central Waste Storage Facility	617,137 gal. (82,696 ft ³)	RESERVED
Non-Radioactive Dangerous Waste Container Storage Area ^b	48,214 gal. (6,461 ft ³)	RESERVED
HLW Melter Out-Of-Service Storage Area	202,498 gal. (27,135 ft³)	RESERVED
LAW Melter Out-Of-Service Storage Area	216,962 gal. (29,073 ft ³)	RESERVED
Containment Building Container Storage	RESERVED	RESERVED

^{*}Capacity is for immobilized glass waste storage.

Capacity is for dangerous and/or mixed waste storage.

8

12

13

14

^c All material within the containment systems will be considered waste for the purposes of calculating free volume, 5

where free volume is the amount of space available in containment systems (i.e., free volume = total capacity of containment systems [which includes total capacity of portable containment systems] minus volume occupied by

equipment and containers within containment systems). d Gallons converted to cubic feet using a conversion factor of 1 gallon (liquid) x $0.134 = 1 ft^{3}$ (rounded to the nearest 9 10 whole number).

^eLocation and capacities of containers stored within portable containment systems specified on Table III.10.D.C are 11 limited to the dangerous and mixed waste container storage areas and capacities specified above.

Modification to Revision 7

Expiration Date: September 27, 2004

Page 25 of 210

Table III.10.D.B - Container Storage Area Permanent Containment Systems

Container Storage Areas	Permanent Containment System	Permanent Containment System	Permanent Containment System Dimensions (ft) &	Permanent Containment System Capacity (gal) (relative to 10% of the volume of all containers		
	Description – Drawing #s	Sump/Floor Drain ID#	Materials of Construction	within the container storage area, or 100% of the volume of the largest container, whichever is greater).		
Central Waste Storage Facility	RESERVED	RESERVED	RESERVED	RESERVED		

Table III.10.D.C - Container Storage Area Portable Containment Systems

)	and the second of the second o		
Portable Containment System Description – Specifications and	Portable Containment System Container Storage Area(s) Location(s)	Portable Containment System Dimensions (ft) & Materials of	Portable Containment System Capacity (gal) (relative to 10% of the volume of all containers
Vendor Information		Construction	managed within the portable containment system, or 100%
			of the volume of the largest container, whichever is
<u> </u>			greater).
RESERVED	RESERVED	RESERVED	RESERVED

^a Location and capacities of containers stored within portable containment systems specified on this Permit Table are limited to the dangerous and mixed waste container storage areas and capacities specified in Permit Table

8 III.10.D.A.

9

10

26

27

28

29 30

2

III.10.E TANK SYSTEMS

- 11 III.10.E.1 Approved Waste and Storage Limits
- III.10.E.1.a. The Permittees may store in tank systems all dangerous and/or mixed waste listed in the Part
 A Forms, Attachment 51, Chapter 1.0 of this Permit and in accordance with the Waste
 Analysis Plan, Attachment 51, Chapter 3.0 as approved pursuant to Permit Condition
 III.10.C.3. of this Permit. Total tank system dangerous and/or mixed waste storage at the
 Facility shall not exceed 4,735,000 gallons pursuant to requirements in Permit Condition
 III.10.E.1.
- III.10.E.1.b. The Permittees may store and manage dangerous and/or mixed waste only in approved tank 18 systems listed in Permit Tables III.10.E.A through D, I, K, M, and O, as approved/modified 19 20 pursuant to Permit Condition III.10.E.9., in accordance with Permit Section III.10.E of this Permit, and in accordance with Attachment 51, Chapters 1.0 and 4.0, and Attachment 51, 21 Appendices 8.1 through 8.15, 9.1 through 9.14, 9.18, 10.1 through 10.14, 10.18, and 11.1 22 23 through 11.15 of this Permit, as approved pursuant to Permit Conditions III.10.E.9.b through 24 e. The Permittees shall limit the total volume of waste to quantities specified for the individual units listed in Permit Tables III. 10.E.A through D, I, K, M, and O. 25
 - III.10.E.1.c. The Permittees shall manage ignitable and reactive, and incompatible waste in accordance with WAC 173-303-395(1). Any tank system specified in Permit Tables III.10.E.A through D and III.10.E, I, K, M, and O as approved/modified pursuant to Permit Condition III.10.E.9., in which ignitable, reactive, or incompatible waste are managed shall meet the requirements specified in WAC 173-303-640(9) and (10).

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 26 of 210

1 2 3 4	III.10.E.1.d.	The Permittees shall ensure all certifications required by specialists (e.g., independent, qualified, registered professional engineer; independent corrosion expert; independent, qualified installation inspector; etc.) use the following statement or equivalent pursuant to Permit Condition III.10.C.10 of this Permit:
5 6 7 8 9		"I, (Insert Name) have (choose one or more of the following: overseen, supervised, reviewed, and/or certified) a portion of the design or installation of a new tank system or component located at (address), and owned/operated by (name(s)). My duties were: (e.g., installation inspector, testing for tightness, etc.), for the following tank system components (e.g., the tank, venting piping, etc.), as required by the Dangerous Waste Regulations, namely, WAC 173-303-640(3) (applicable paragraphs (i.e., (a) through (g)).
11 12 13 14 15		"I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment."
16 17 18	III.10.E.1.e.	In all future permit submittals, the Permittees shall include tank names with the tank designation (e.g., Process Condensate Vessels located in the RLD System are designated V45028A and V45028B, respectively).
19	III.10.E.2	Tank System Design and Construction
20 21 22 23 24	III.10.E.2.a.	The Permittees shall construct the tank systems identified in Permit Tables III.10.E.A through D, I, K, M, and O, as approved/modified pursuant to Permit Condition III.10.E.9., as specified in Attachment 51, Appendices 8.1 through 8.14, 9.1 through 9.14, 10.1 through 10.14, and 11.1 through 11.14 of this Permit, as approved pursuant to Permit Conditions III.10.E.9.b., III.10.E.9.c., and III.10.E.9.d.
25 26 27 28 29 30	III.10.E.2.b.	The Permittees shall construct all secondary containment systems identified in Permit Tables III.10.E.A through D, and I through P, as approved/modified pursuant to Permit Condition III.10.E.9., as specified in Attachment 51, Appendices 8.2, 8.4 through 8.15, 9.2, 9.4 through 9.14, 9.18, 10.2, 10.4 through 10.14, 10.18 and 11.2, 11.4 through 11.15, 11.15 of this Permit, as approved pursuant to Permit Conditions III.10.E.9.b., III.10.E.9.c., and III.10.E.9.d.
31 32 33	III.10.E.2.c.	Modifications to approved design, plans, and specifications in Attachment 51 of this Permit for the WTP Unit Tank Systems shall be allowed only in accordance with Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g., III.10.C.9.d, e., and h.
34	III.10.E.3	Tank System Installation and Certification
35 36 37 38 39 40	III.10.E.3.a.	The Permittees must ensure that proper handling procedures are adhered to in order to prevent damage to the system during installation. Prior to covering, enclosing, or placing a new tank system or component in use, an independent, qualified, installation inspector or an independent, qualified, registered professional engineer, either of whom is trained and experienced in the proper installation of tank systems or components, must inspect the system for the presence of any of the following items:
41		i. Weld breaks;
42		ii. Punctures;
43		iii. Scrapes of protective coatings;
44		iv. Cracks;

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 27 of 210


	1.	·	v. Corrosion;
	2		vi. Other structural damage or inadequate construction/installation.
	3 4		All discrepancies must be remedied before the tank system is covered, enclosed, or placed in use [WAC 173-303-640(3)(c)].
	5 6 7 8 9	III.10.E.3.b.	For tank systems or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the tank and compacted to ensure that the tank and piping are fully and uniformly supported [WAC 173-303-640(3)(d)].
	10 11 12 13	Ш.10.Е.3.с.	The Permittees must test for tightness all new tanks and ancillary equipment prior to these components being covered, enclosed, or placed into use. If a tank system is found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the tank system being covered, enclosed, or placed in use [WAC 173-303-640(3)(e)].
÷ .	14 15 16	III.10.E.3.d.	The Permittees must ensure ancillary equipment is supported and protected against physical damage and excessive stress due to settlement, vibration, expansion, or contraction [WAC 173-303-640(3)(f)].
	17 18 19 20 21 22 23 24 25	III.10.E.3.e.	The Permittees must provide the type and degree of corrosion protection recommended by an independent corrosion expert, based on the information provided in Attachment 51, Appendices 8.9, 8.11, 9.9, 9.11, 10.9, 10.11, 11.9, and 11.11 of this Permit, as approved pursuant to Permit Conditions III.10.E.9.b.i., III.10.E.9.b.iv., III.10.E.9.b.v., III.10.E.9.c.i., III.10.E.9.c.iv., III.10.E.9.c.iv., III.10.E.9.d.iv., and III.10.E.9.d.v. or other corrosion protection if the Ecology believes other corrosion protection is necessary to ensure the integrity of the tank system during use of the tank system. The installation of a corrosion protection system that is field fabricated must be supervised by an independent corrosion expert to ensure proper installation [WAC 173-303-640(3)(g)].
	26 27 28 29 30 31 32 33 34	III.10.E.3.f.	Prior to initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees shall obtain, and keep on file in the WTP Unit operating record, written statements by those persons required to certify the design of the tank system and supervise the installation of the tank system in accordance with the requirements of WAC 173-303-640(3)(b), (c), (d), (e), (f), and (g), attesting that each tank system and corresponding containment system listed in Permit Tables III.10.E.A through D and III.10.E.I through P, as approved/modified pursuant to Permit Condition III.10.E.9., were properly designed and installed, and that repairs, pursuant to WAC 173-303-640(3)(c) and (e) were performed [WAC 173-303-640(3)(a) WAC 173-303-640(3)(h)].
	35 36 37 38		The independent tank system installation inspection and subsequent written statements shall be certified pursuant to Permit Condition III.10.E.1.d., comply with all requirements of WAC 173-303-640(3)(h) and shall consider, but not be limited to, the following tank system installation documentation:
	39		i. Field installation report with date of installation;
	40		ii. Approved welding procedures;
	41		iii. Welder qualifications and certification;
	42 43 44		iv. Hydro-test reports, as applicable, in accordance with the American Society of Mechanical Engineers Boiler and Pressure Vessel Code, Section VIII, Division 1, American Petroleum Institute (API) Standard 620, or Standard 650 as applicable;
	45		v. Tester credentials;

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 28 of 210

1		vi. Field inspector credentials;
2		vii. Field inspector reports;
3		viii. Field waiver reports; and
5		ix. Non-compliance reports and corrective action (including field waiver reports) and repair reports.
6	III.10.E.4	Integrity Assessments
7 8 9 10 11 12 13 14	III.10.E.4.a.	The Permittees shall ensure periodic integrity assessments are conducted on the WTP Unit Tank Systems listed in Permit Tables III.10.E.A through D, I, K, M, and O, as approved/modified pursuant to Permit Condition III.10.E.9., over the term of this Permit as specified in WAC 173-303-640(3)(b), following the description of the integrity assessment program and schedule in Attachment 51, Chapter 6.0 of this Permit, as approved pursuant to Permit Conditions III.10.E.9.e.i. and III.10.C.5.c. Results of the integrity assessments shall be included in the WTP Unit operating record until ten (10) years after post-closure, or corrective action is complete and certified, whichever is later.
15 16 17 18	HI.10.E.4.b.	The Permittees shall address problems detected during the tank integrity assessments specified in Permit Condition III.10.E.4.a. following the integrity assessment program in Attachment 51, Chapter 6.0 of this Permit, as approved pursuant to Permit Conditions III.10.E.9.e.i. and III.10.C.5.c.
19 20 21 22 23 24	III.10.E.4.c.	The Permittees must immediately and safely remove from service any Tank System or secondary containment system which through an integrity assessment is found to be "unfit for use" as defined in WAC 173-303-040, following Permit Conditions III.10.E.5.i.i through iv., vi., and vii. The affected tank system or secondary containment system must be either repaired or closed in accordance with Permit Condition III.10.E.5.i.v. [WAC 173-303-640(7)(e) and (f), WAC 173-303-640(8)].
25	III.10.E.5	Tank Management Practices
26 27	III.10.E.5.a.	No dangerous and/or mixed waste shall be managed in the WTP Unit Tank System unless the operating conditions, specified under Permit Condition III.10.E.5 are complied with.
28 29 30 31 32	HI.10.E.5.b.	The Permittees shall install and test all process and leak detection system monitoring/instrumentation, as specified in Permit Tables III.10.E.E through H, as approved/modified pursuant to Permit Condition III.10.E.9., in accordance with Attachment 51, Appendices 8.1, 8.2, 8.14, 9.1, 9.2, 9.14, 10.1, 10.2, 10.14, 11.1, 11.2, and 11.14 of this Permit, as approved pursuant to Permit Conditions III.10.E.9.e.ix. and III.10.E.9.d.x.
33 34 35	Ш.10.Е.5.с.	The Permittees shall not place dangerous and/or mixed waste, treatment reagents, or other materials in the WTP Unit Tank System if these substances could cause the tank system to rupture, leak, corrode, or otherwise fail [WAC 173-303-640(5)(a)].
36 37 38 39 40	III.10.E.5.d.	The Permittees shall operate the WTP Unit Tank System to prevent spills and overflows using the description of controls and practices as required under WAC 173-303-640(5)(b) described in Permit Condition III.10.C.5, and Attachment 51, Appendices 8.15, 9.18, 10.18, and 11.15 of this Permit, as approved pursuant to Permit Condition III.10.E.9.e.iv. [WAC 173-303-640(5)(b), WAC 173-303-806(4)(c)(ix)].
41 42 43 44 45	III.10.E.5.e.	For routinely non-accessible WTP Unit Tank Systems, as specified in Attachment 51, Chapter 4.0 of this Permit, as updated pursuant to Permit Condition III.10.E.9.e.vi., the Permittees shall mark all routinely non-accessible tank system access points with labels or signs to identify the waste contained in the tanks. The label, or sign, must be legible at a distance of at least fifty (50) feet and must bear a legend that identifies the waste in a manne

Modification to Revision 7
Expiration Date: September 27, 2004


Page 29 of 210



Modification to Revision 7

Expiration Date: September 27, 2004


Page 30 of 210



Modification to Revision 7

Expiration Date: September 27, 2004

Page 31 of 210



Expiration Date: September 27, 2004

Page 32 of 210


specified below will include dimensioned engineering drawings and information on sumps and floor drains):

- i. IQRPE Reports (specific to foundation, secondary containment, and leak detection system) shall include review of design drawings, calculations, and other information on which the certification report is based and shall include as applicable, but not limited to, review of such information described below. Information (drawings, specifications, etc.) already included in Attachment 51, Appendices 8.0 through 11.0 of this Permit, may be included in the report by reference and should include drawing and document numbers. IQRPE Reports shall be consistent with the information separately provided in ii. through ix. below. The IQRPE Report(s) (specific to foundation, secondary containment and leak detection system) for the LAW and HLW buildings (-21 foot elevation only) shall be submitted with the first IQRPE Report for tanks, identified in Permit Condition III.10.E.9.c.i. [WAC 173-303-640(3)(a), WAC 173-303-806(4)(c)(i)];
- ii. Design drawings (General Arrangement Drawings in plan and cross sections) and specifications for the foundation, secondary containment, including, liner installation details, and leak detection methodology [Note: leak detection systems for areas where daily, direct, or remote visual inspection is not feasible, shall be continuous in accordance with WAC 173-303-640(4)(e)(iii)(C)]. These items should show the dimensions, volume calculations, and location of the secondary containment system, and should include items such as floor/pipe slopes to sumps, tanks, floor drains [WAC 173-303-640(4)(b) through (f), WAC 173-303-640(3)(a), WAC 173-303-806(4)(c)(i)];
- iii. The Permittees shall provide the design criteria (references to codes and standards, load definitions, and load combinations, materials of construction, and analysis/design methodology) and typical design details for the support of the secondary containment system. This information shall demonstrate the foundation will be capable of providing support to the secondary containment system, resistance to pressure gradients above and below the system, and capable of preventing failure due to settlement, compression, or uplift [WAC 173-303-640(4)(c)(ii), WAC 173-303-806(4)(c)(vii)];
- iv. A description of materials and equipment used to provide corrosion protection for external metal components in contact with soil, including factors affecting the potential for corrosion as required under WAC 173-303-640(3)(a)(iii)(B) [WAC 173-303-806(4)(c)(v)];
- v. Secondary containment/foundation and leak detection system materials selection documentation (including, but not limited to, concrete coatings and water stops, and liner materials as applicable) [WAC 173-303-806(4)(c)(i)];
- vi. Detailed description of how the secondary containment for each tank system will be installed in compliance with WAC 173-303-640(3)(c) [WAC 173-303-806(4)(c)(vi)];
- vii. Submit Permit Tables III. 10.E.J, L, N, and P, completed to provide for all secondary containment sumps and floor drains, the information as specified in each column heading, consistent with information to be provided in i. through vi. above;
- viii. Documentation that secondary containment and leak detection systems will not accumulate hydrogen gas levels above the lower explosive limit for incorporation into the Administrative Record [WAC 173-303-340].
- ix. A detailed description of how tank system design provides access for conducting future tank integrity assessments [WAC 173-303-640(3)(b), WAC 173-303-806(4)(c)(vi)];

Modification to Revision 7


Expiration Date: September 27, 2004

Page 33 of 210



Expiration Date: September 27, 2004

Page 34 of 210



Expiration Date: September 27, 2004

Page 35 of 210

			erregies de la com unicación de la comunicación de
1 2 3		vii.	Tank, ancillary equipment, and leak detection system instrument control logic narrative description (e.g., software functional specifications, descriptions of fail-safe conditions, etc.);
4 5 6		viii.	System Descriptions (process) related to ancillary equipment and system descriptions related to leak detection systems, (including instrument control logic and narrative descriptions), for incorporation into the Administrative Record;
7 8 9		ix.	A detailed description of how the ancillary equipment will be installed and tested [WAC 173-303-640(3)(c) through (e), WAC 173-303-640(4)(b) and (c), and WAC 173-303-806(4)(c)(vi)];
10 11 12 13 14		X.	For process monitoring, control, and leak detection system instrumentation for the WTP Unit Tank System as identified in Permit Tables III.10.E.E through H, a detailed description of how the process monitoring, control, and leak detection system instrumentation will be installed and tested [WAC 173-303-640(3)(c) through (e), WAC 173-303-640(4)(b) and (c), WAC 173-303-806(4)(c)(vi)];
15 16 17 18		xi.	Mass balance for projected normal operating condition used in developing the process and instrumentation diagrams, including assumptions and formulas used to complete the mass balance, so that they can be independently verified, for incorporation into the Administrative Record;
19 20 21		xii.	Documentation that ancillary equipment is designed to prevent the accumulation of hydrogen gas levels above the lower explosive limit for incorporation into the Administrative Record [WAC 173-303-340].
22 23 24 25 26		xiii.	Leak detection system documentation (e.g. vendor information, etc.) consistent with information submitted under Permit Condition III.10.E.9.c.ii. and Permit Conditions III.10.E.9.d.ii., vii., viii. and x. above, shall be submitted for incorporation into the Administrative Record.
27 28 29 30 31 32 33	III.10.E.9.e.	shall spec of th Atta cond	r to initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees I submit to Ecology, pursuant to Permit Condition III.10.C.9.f., the following as diffed below for incorporation into Attachment 51, Appendices 8.15, 9.18, 10.18, 11.15 his Permit, except Permit Condition III.10.E.9.e.v., which will be incorporated into chment 51, Chapter 6.0 of this Permit. All information provided under this permit dition must be consistent with information provided pursuant to Permit Conditions 0.E.9.b., c., d., and e., III.10.C.3.e., and III.10.C.11.b., as approved by Ecology.
34 35 36 37 38 39 40		i.	Integrity assessment program and schedule for all WTP Unit tanks shall address the conducting of periodic integrity assessments on all WTP Unit tanks over the life of the tank, in accordance with III.10.E.9.b.ix. and WAC 173-303-640(3)(b), and descriptions of procedures for addressing problems detected during integrity assessments. The schedule must be based on past integrity assessments, age of the tank system, materials of construction, characteristics of the waste, and any other relevant factors [WAC 173-303-640(3)(b), WAC 173-303-806(4)(c)(vi)];
41 42 43 44		ii.	Detailed plans and descriptions, demonstrating the leak detection system is operated so that it will detect the failure of either the primary or secondary containment structure or the presence of any release of dangerous and/or mixed waste, or accumulated liquid in the secondary containment system within twenty-four (24) hours. Detection of a leak of at least 0.1 callons per hour within twenty four (24) hours is defined as being able to

of at least 0.1 gallons per hour within twenty-four (24) hours is defined as being able to

45

Expiration Date: September 27, 2004

Page 36 of 210

1 2		detect a leak within twenty-four (24) hours. Any exceptions to this criteria must be approved by Ecology [WAC 173-303-640(4)(c)(iii), WAC 173-303-806(4)(c)(vii)];
3 4 5	iii.	Detailed operational plans and descriptions, demonstrating that spilled or leaked waste and accumulated liquids can be removed from the secondary containment system within twenty-four (24) hours [WAC 173-303-806(4)(c)(vii)];
6 7 8 9	iv.	Descriptions of operational procedures demonstrating appropriate controls and practices are in place to prevent spills and overflows from tanks or containment systems in compliance with WAC 173-303-640(5)(b)(i) through (iii) [WAC 173-303-640(5)(b), WAC 173-303-806(4)(c)(ix)];
10 11 12	v.	Description of procedures for investigation and repair of tank systems [WAC 173-303-320, WAC 173-303-640(6), WAC 173-303-640(7)(e) and (f), WAC 173-303-806(4)(a)(v), WAC 173-303-806(4)(c)(vii)];
13 14 15	vi.	Updated Chapter 4.0, Narrative Descriptions, Tables and Figures as identified in Permit Tables III.10.E.A through D (as modified pursuant to Permit Condition III.10.E.9.e.xii.) and updated to identify routinely non-accessible tank systems;
16 17 18	vii	Description of procedures for management of ignitable and reactive, and incompatible dangerous and/or mixed waste in accordance with WAC 173-303-640(9) and (10) [WAC 173-303-806(4)(c)(x)].
19 20	vii	i. A description of the tracking system used to track dangerous and/or mixed waste throughout the WTP Unit Tank System, pursuant to WAC 173-303-380.
21 22 23 24 25 26 27 28 29 30	ix.	Permit Tables III.10.E.E through H shall be completed for WTP Unit Tank System process and leak detection system monitors and instruments (to include but not limited to: instruments and monitors measuring and/or controlling flow, pressure, temperature, density, pH, level, humidity, and emission) to provide the information as specified in each column heading. Process and leak detection system monitors and instruments for critical systems as specified in Attachment 51, Appendix 2.0 and as updated pursuant to Permit Condition III.10.C.9.b. and for operating parameters as required to comply with Permit Condition III.10.C.3.e.iii. shall be addressed. Process monitors and instruments for non-waste management operations (e.g., utilities, raw chemical storage, non-contact cooling waters, etc.) are excluded from this permit condition.
31 32 33	х.	Supporting documentation for operating trips and expected operating range as specified in Permit Tables III.10.E.E through H as approved pursuant to Permit Condition III.10.E.9.e.ix.
34 35 36	xi.	Documentation of process and leak detection instruments and monitors (as listed in Permit Tables III.10.E.E through H) for the WTP Unit Tank Systems to include but not be limited to the following:
37		A. Procurement specifications;
38		B. Location used;
39		C. Range, precision, and accuracy;
40 41 42		 D. Detailed descriptions of Calibration/functionality test procedures (e.g., method number [ASTM]) or provide a copy of manufacturer's recommended calibration procedures;
43 44		E. Calibration/functionality test, inspection, and routine maintenance schedules and checklists, including justification for calibration, inspection and maintenance

Modification to Revision 7

Expiration Date: September 27, 2004

Page 37 of 210

frequencies, criteria for identifying instruments found to be significantly out of calibration, and corrective action to be taken for instruments found to be 2 significantly out of calibration (e.g., increasing frequency of calibration, 3 4 instrument replacement, etc.); Equipment instrument control logic parrative description (e.g., software functional 5 specifications, descriptions of fail safe conditions, etc.), as identified in Permit 6 Tables III.10.E.E through H not addressed in Permit Condition III.10.E.9.d. 7 xii. Permit Tables III.10.E.A through D amended as follows: 9 Under column 1, update and complete list of dangerous and/or mixed waste tank systems, including plant items that comprise each system (listed by item number); 10 Under column 2, update and complete system designations; 11 Under column 3, replace the 'reserved' with the Attachment 51, Appendices 8.0, 12 9.0, 10.0, and 11.0, subsections specific to tank systems as listed in column 1; 13 14 Under column 4, update and complete list of narrative description tables and figures; 15 E. Under column 5, update and complete maximum capacity, for each tank. 16 xiii. Permit Tables III.10.E.I, K, M, and O amended as follows: 17 Under column 1, replace the 'reserved' with the updated and complete list of 18 19 sump numbers and room location; Under column 2, replace the 'reserved' with the updated and complete maximum 20 sump capacities in gallons; 21 Under column 3, replace the 'reserved' with the updated and complete sump 22 dimensions and materials of construction: 23 Under column 4, replace the 'reserved' with the updated and complete list of 24 engineering descriptions (drawing numbers, specifications, etc.); 25 26 27

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 38 of 210

Table III.10.E.A – Pretreatment Plant Tank Systems Description

Dangerous and/or mixed waste Tank Systems Name	System Designation	Engineering Description (Drawing Nos., Specifications Nos., etc.)	Narrative Description, Tables & Figures		Maximum Capacity (gallons)
Waste Feed Receipt Vessels FRP-VSL-	FRP	24590-PTF	Section 4.1.2.1; Table 4-3 and 4-11; and	i i	SL-00002-A = 474,000
00002-A through D (Waste Feed Receipt Process System)		-M2-FRP-P0001	Figures 4A-1, 4A-2, 4A-5, 4A-61, 4A-62, 4A-78, 4A-79 of Attachment 51,		SL-00002-B = 474,000
Trocess Bystem)		-M2-FRP-P0002	Chapter 4.0 of this Permit.		SL-00002-C = 474,000
		-M2-FRP-P0003		FRP-VS	SL-00002-D = 474,000
		-M2-FRP-P0004			
		-M5-V17T-P0003			
		-M6-FRP-P0001			
		-M6-FRP-P0002			· · · · · · · · · · · · · · · · · · ·
	Ť	-MVD-FRP-00001			
		-MVD-FRP-00002			
		-MVD-FRP-00003			
		-MVD-FRP-00004			
		-MVD-FRP-P0005			
	•	-MVD-FRP-P0006			
		-MVD-FRP-P0007			
		-MVD-FRP-P0008			
		-P1-P01T-P0001			
		<u>-P1-P01T-P0002</u>			
		-P1-P01T-P0008			
	•	-P1-P01T-P0009		.·	
		-P1-P01T-P0010		771100	50.050
Evaporator Feed Vessels V11001A-B, Evaporator Process Condensate Pot	FEP	RESERVED	Section 4.1.2.2; Table 4-3 and 4-11; and Figures 4A-1, 4A-2, 4A-6, 4A-61, 4A-	1 1	A = 59,070 B = 90,070
V11005, (Waste Feed Evaporation Process System)		- -	62, 4A-63, 4A-78, 4A-79, 4A-80 of Attachment 51, Chapter 4.0 of this	V1100	· · · · · · · · · · · · · · · · · · ·

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 39 of 210

	Dangerous and/or mixed waste Tank Systems Name	System Designation	Engineering Description (Drawing Nos., Specifications Nos.,	Narrative Description, Tables & Figures	Maximum Capacity (gallons)
f	-		etc.)	Permit.	
ľ	Ultrafilter Permeate Vessel UFP-VSL-	UFP	RESERVED	Section 4.1.2.3; Table 4-3 and 4-11; and	V12015A - 28,390
	00062A, Ultrafilter Permeate Vessel		24590-PTF	Figures 4A-1, 4A-2, 4A-7, 4A-61, 4A-	V12015B - 28,390
	UFP-VSL-00062B, Ultrafilter Permeate		-M6-UFP-P0001	62, 4A-78, 4A-79 of Attachment 51,	V12015C - 28,390
	Vessel UFP-VSL-00062C LAW Permeate Hold Vessels V12015A-C,		-M6-UFP-P0002	Chapter 4.0 of this Permit.	V12010A = 62,340
	Ultrafilteration Feed Preparation Vessel		-M6-UFP-P0003		V12010B - 62,340
	UFP-VSL-00001A, Ultrafiltration Feed		-M6-UFP-P0004		$\frac{V12010B}{V12011A} = \frac{02,340}{26,840}$
	Vessel UFP-VSL-00002A		-M6-UFP-P0005		V12011B - 26.840
İ	<u>Ultrafilteration Feed Preparation Vessel</u> <u>UFP-VSL-00001B</u> , <u>Ultrafilteration Feed</u>		-M6-UFP-P0006	·	UFP-VSL-00062A = 34,700
	Vessel UFP-VSL-00002B, Evaporator		-M6-UFP-P0007		
	Concentrate Buffer Vessels V12010A-B,	•	-M6-UFP-P0008		$\frac{\text{O17-VSL-00002B} - \text{J-7,700}}{\text{UFP-VSL-00062C} = 34,700}$
	Ultrafiltration Feed-Vessels V12011A-B,		-M6-UFP-P0009		UFP-VSL-00001A = 75,593
	Ultrafilters <u>UPF-FILT-00001A, UPF-</u> FILT-00001B, UPF-FILT-00002A, UPF-	, , , , ,	-M6-UFP-P0010		$\frac{\text{OTT-VSL-00001A} - 73,373}{\text{UFP-VSL-00002A} = 40,783}$
	FILT-00002B, UPF-FILT-00003A, and		-M6-UFP-P0011	·	$\frac{\text{UFP-VSL-00002R} - 40.783}{\text{UFP-VSL-00001B} = 75.593}$
	<u>UPF-FILT-00003B G12002A-B,</u>		-M6-UFP-P0015	·	$\frac{\text{UFP-VSL-00002B} - 73,323}{\text{UFP-VSL-00002B} = 40,783}$
	G12003A-B, and G12004A-B		-MV-UFP-P0001		UPF-FILT-00001A= RESERVED
	(Ultrafiltration Process System)		-MV-UFP-P0002		UPF-FILT-00001B= RESERVED
			-MV-UFP-P0003		UPF-FILT-00002A= RESERVED
İ			-MV-UFP-P0004		UPF-FILT-00002B= RESERVED
			-MV-UFP-P0005		UPF-FILT-00003A= RESERVED
			-MV-UFP-P0006		UPF-FILT-00003B= RESERVED
			-MV-UFP-P0007		$\frac{\text{G12002}\Lambda - 140}{\text{G12002}\Lambda}$
			-MVC-UFP-00001		G12002B = 140
1			-MVC-UFP-00002		$\frac{G12002D}{G12003A} = \frac{140}{140}$
			-MVC-UFP-00003		G12003B - 140
			-MVC-UFP-P0001		$\frac{G12003B}{G12004A} = \frac{140}{140}$
L			-141 y C-O11-1 0001		U1200721 170

Permit Number: WA7890008967
Modification to Revision 7
Expiration Date: September 27, 2004
Page 40 of 210

Dangerous and/or mixed waste Tank Systems Name	System Designation	Engineering Description	Narrative Description, Tables & Figures	Maximum Capacity
		(Drawing Nos., Specifications Nos.,		(gallons)
100		etc.)	23.3	5420017
		-MVC-UFP-P0002		G12004B140
		<u>-MVC-UFP-P0005</u>		
		<u>-MVC-UFP-P0006</u>		
		<u>-MVC-UFP-P0007</u>		
		<u>-MVC-UFP-P0014</u>		
		<u>-MVC-UFP-P0015</u>		
	(A)	ii ii	** *	
	. 1920 14 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		· · · · · ·	
			무기복 : 뭐	
	Francisco de la constante de l	0.4500 DOT	0	HLP-VSI-00022 = 270,600
HLW Feed Receipt Vessel HLP-VSI-	HLP	24590-PTF-	Section 4.1.2.4; Table 4-3 and 4-11; and Figures 4A-1, 4A-2, 4A-8, 4A-61, 4A-	$\frac{\text{HLP-VS}-00022-270,000}{\text{V}12007-18,070}$
00022, HLW Feed Blending Vessel HLP-VSL-00028 V12007, Sr/TRU Lag		<u>-M6-HLP-P0001</u>	62, 4A-78, 4A-79 of Attachment 51,	
Storage Vessels HPL-VSL-00027A&B.	1 (1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	<u>-M6-HLP-P0002</u>	Chapter 4.0 of this Permit.	HLP-VSL-00028 = 142,200
V12001A & C, Lag Storage Vessels		<u>-M6-HLP-P0003</u>	*	V12001A = 96,900
V12001D & E (HLW Lag Storage and		<u>-MV-HLP-P0003</u>		V12001C = 96,900
Feed Blending Process system)		<u>-MV-HLP-P0004</u>		$\underline{\text{HPL-VSL-}00027A} = 127,260$
	Take 1	<u>-MV-HLP-P0005</u>		HPL-VSL-00027B = 127,260
		<u>-MV-HLP-P0006</u>		V12001D = 96,900
		MVD-HLP-P0006		V12001E = 96,900
		MVD-HLP-P0007		
		MVD-HLP-P0008		
		MVD-HLP-P0009		

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 41 of 210

	<u> </u>				
Dangerous and/or mixed waste Tank Systems Name	System Designation	Engineering Description (Drawing Nos.,	Narrative Description, Tables & Figures		Maximum Capacity (gallons)
		Specifications Nos., etc.)			(g-mound)
Cesium Ion Exchange Columns C13001-	CXP	RESERVED	G-4-4105 T11-42 1411	CIOOI	
4, LAW Feed Vessel V13001, Caustic	UAI	RESERVED	Section 4.1.2.5; Table 4-3 and 4-11; and Figures 4A-1, 4A-2, 4A-9, 4A-61, 4A-	C13001	
Rinse Collection Vessel V13008, Cs IX			62, 4A-78, 4A-79 of Attachment 51,	C13002	= 680
Gas Separation Vessels (ID	1		Chapter 4.0 of this Permit.	C13003	= 680
RESERVED), Cesium Reagent Tank (ID	:		Onapter 1.5 of this Formit.	C13004	= 680
RESERVED)				V13001	= 61,200
(Cesium Ion Exchange Process System)				V13008	= 2,400
				Cs IX Ga	s Separation Vessels =
				RESERV	
				Cesium I	Reagent Tank =
		e green and a		RESERV	
Eluate Contingency Storage Vessel	CNP	RESERVED	Section 4.1.2.6; Table 4-3 and 4-11; and	V13073	= 11,060
V13073, Recovered Nitric Acid Vessel	t + 1		Figures 4A-1, 4A-2, 4A-10, 4A-61, 4A-	V13028	= 5,410
V13028, Cesium Concentrate Lute Pot			62, 4A-78, 4A-79 of Attachment 51,	V13030	* •
V13030, (Cesium Nitric Acid Recovery Process System)	194		Chapter 4.0 of this Permit.	12000	
					· · · · · · · · · · · · · · · · · · ·
Technetium Ion Exchange Buffer Vessel V43001, Cs Treated LAW Collection	TXP	RESERVED	Section 4.1.2.8; Table 4-3 and 4-11; and	, ,	= 18,100
Vessel (ID RESERVED), Technetium			Figures 4A-1, 4A-2, 4A-12, 4A-61, 4A-62, 4A-78, 4A-79 of Attachment 51,		ed LAW Collection
Ion Exchange Columns C43006-9,			Chapter 4.0 of this Permit.	· · · · · · · · · · · · · · · · · · ·	D RESERVED)
Caustic Rinse Collection Vessel V43056,		•	Chapter 4.0 of this formit.	C43006	= 680
Treated LAW Buffer Vessels V43110A-				C43007	= 680
C, Tc Reagent Vessels (ID's				C43008	= 680
RESERVED) (Technetium Ion Exchange				C43009	= 680
Process System)		4		V43056	= 3,300
				V43110A	$\Lambda = 33,050$
	and the state of t	Aller Commence		V43110E	3 = 33,050
			The second second	1 1	C = 33,170
	\mathbf{y}^{t} and \mathbf{y}^{t}			i i	ent Vessels (ID's
	1.			RESERV	

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 42 of 210

Dangerous and/or mixed waste Tank Systems Name	System Designation	Engineering Description (Drawing Nos., Specifications Nos., etc.)	Narrative Description, Tables & Figures	Maximum Capacity (gallons)
Recovered Technetium Eluant Vessel V43071, Technetium Concentrate Lute Pot V43072 (Technetium Eluant Recovery Process System)	TEP	RESERVED	Section 4.1.2.9; Table 4-3 and 4-11; and Figures 4A-1, 4A-2, 4A-13, 4A-61, 4A-78 of Attachment 51, Chapter 4.0 of this Permit.	V43071 = 7,900 V43072 = 70
Process Condensate Hold Vessel V41013, Plant Wash Vessels V45009A- B, LAW SBS Purge Receipt Vessels (ID RESERVED) (Treated LAW Evaporation Process System (TLP)), LAW Buffer Storage Vessel V41001 Treated LAW Concentrate Storage Process System TCP-VSL-00001	TLP TCP	RESERVED 24590-PTF -M6-TCP-P0001 -MV-TCP-P0002 -MVD-TCP-00001 -MVD-TCP-P0002	Section 4.1.2.11 & 4.2.2.12; Table 4-3 and 4-11; and Figures 4A-1, 4A-2, 4A-16, 4A-61, 4A-62, 4A-78, 4A-79 of Attachment 51, Chapter 4.0 of this Permit.	V41013 = 450 V45009A = 88,920 V45009B = 88,920 LAW \$B\$ Purge Receipt Vessels (ID RESERVED) V41001 = 117,000 TCP-VSL-00001 = 146,740
Spent Resin Collection Vessels V43135A-B, Resin Flush Collection Vessel V43136, Spent Resin Dewatering Moisture Separation Vessel (ID RESERVED) (Spent Resin and Dewatering Process System)	RDP	RESERVED	Section 4.1.2.13; Table 4-3 and 4-11; and Figures 4A-1, 4A-2, 4A-15, 4A-61, 4A-78 of Attachment 51, Chapter 4.0 of this Permit.	V43135A = 8,720 V43135B = 8,720 V43136 = 11,220 Spent Resin Dewatering Moisture Separation Vessel= RESERVED
Process Condensate Vessels V45028A-B (Pretreatment Plant Radioactive Liquid Waste Disposal System)	RLD	RESERVED	Section 4.1.2.16; Table 4-3; and Figures 4A-1, 4A-2, 4A-18, 4A-61, 4A-62, 4A-78, 4A-79 of Attachment 51, Chapter 4.0 of this Permit.	V45028A = 321,720 V45028B = 321,720
Ultimate Overflow Vessel PWD-VSL-00033, HLW Effluent Transfer Vessel PWD-VSL-00043, Primary Acidic/Alkaline Effluent Vessel V45013, Secondary Acidic/Alkaline Effluent Vessel V45018, Alkaline Effluent Vessels V15013 & V15018, Plant Wash Vessel V15009A, C3 Floor Drain	PWD	24590-PTF -M5-V17T-P0022002 -M6-PWD-P0002 -M6-PWD-P0043, -MV-PWD-P0001001 -MV-PWD-P0003001	Section 4.1.2.15; Table 4-3 and 4-11; and Figures 4A-1, 4A-2, 4A-17, 4A-60, 4A-61, 4A-62, 4A-78, 4A-79 of Attachment 51, Chapter 4.0 of this Permit.	PWD-VSL-00033 = 41,650 PWD-VSL-00043 = 41,650 V45013 = 49,850 V45018 = 49,850 V15013 = 93,180 V15009A = 73,860

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 43 of 210

				1	
Dangerous and/or mixed waste Tank	System Designation	Engineering	Narrative Description, Tables &		Maximum
Systems Name		Description	Figures		Capacity
		(Drawing Nos.,			(gallons)
		Specifications Nos.,			(8)
		etc.)			
Collection Vessel PWD-VSL-00046		-MV-PWD-P0005		PWD-	/SL-00046 = 4982
(Pretreatment Plant Wash and Disposal		-MVC-PWD-00029		. 1	8 = 93,180
System)		-MVC-PWD-00030			
				*	
		-MVD-PWD-P0001			
	,	-MVD-PWD-P0003			$A_{ij} = A_{ij} + A$
		-MVD-PWD-P0010		. 1	
		-P1-P01T-P0006			
		-P1-P01T-P0009			
		-P1-P01T-P0012			
	* -	-P1-P01T-P0014		* **	
		-P1-P01T-P0015			
Vessel Vent Header Collection Vessel	PVP	RESERVED	Section 4.1.2.17; Table 4-3; and Figures	V1505	2 = 900
V15052, Condensate Collection Vessel			4A-1, 4A-2, 4A-19, 4A-61, and 4A-78	V1503	8 = 1,230
V15038, HEME Drain Collection Vessels			of Attachment 51, Chapter 4.0 of this		7 = 2,760
V15326-7			Permit.		·
(Pretreatment Vessel Vent Process				V1532	6 = 820
System)	·		No. 1		

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 44 of 210

Table III.10.E.B - Law Vitrification Plant Tank Systems Description

Mixed Waste Tank Systems Name	Unit Designation	Unit Description	Narrative Description, Tables & Figures	Maximum Capacity (gallons)
		RESERVED	Section 4.1.3.1; Table 4-4 and 4-11; and Figures	V21001 = 14,392
Melter 1 Concentrate Receipt Vessel LAW-	LCP		4A-1, 4A-3, 4A-20, of Attachment 51, Chapter	
MV-LCP-VSL-00001 V21001, Melter 2		24590-LAW	4.0 of this Permit.	V21002 - 14,392
Concentrate Receipt Vessel MV-LCP-VSL-		<u>-M6-LCP-P0001</u>	7.0 01 tills i cimit.	V 21003 = 14,392
00002 V21002, Melter 3 Concentrate		<u>-M6-LCP-P0002</u>		LCP-VSL-00001 = 18,130
Receipt Vessel V21003		-MV-LCP-P0001		LCP-VSL-00002 = 18.130
(LAW Concentrate Receipt Process	·	-MV-LCP-P0002		
System)		-MVD-LCP-00001		
		-MVD-LCP-00002		. :
		-MVD-LCP-P0004		
		-MVD-LCP-P0005		
		PECEDI MID		V01101 6 001
Melter 1 Feed Preparation Vessel <u>LAW</u>	LFP	RESERVED	Section 4.1.3.1; Table 4-4 and 4-11; and Figures	V21101 = 6,221 V21102 = 6,221
<u>LFP-VSL-00001V21101</u> , Melter 1 Feed		24590-LAW	4A-1, 4A-3, 4A-20, 4A-67, and 4A-83 of	$\frac{\sqrt{21102} - 6,221}{\sqrt{21201} - 6,221}$
Vessel <u>LAW-LFP-VSL-00002 V21102</u> ,	,	M6-LFP-P0001	Attachment 51, Chapter 4.0 of this Permit.	$\frac{\sqrt{21201} - 6,221}{\sqrt{21202} - 6,221}$
Melter 2 Feed Preparation Vessel <u>LAW-</u>		M6-LFP-P0002 M6-LFP-P0003		$V_{21301} = 6,221$
LFP-VSL-00003 V21201, Melter 2 Feed		M6-LFP-P0003 M6-LFP-P0004		$V_{21302} = 6,221$ $V_{21302} = 6,221$
Vessel <u>LAW-LPF-VSL-00004 V21202</u> , Melter 3 Feed Preparation Vessel V21301,		MV-LFP-P0001		LFP-VSL-00001 = 9.123
Melter 3 Feed Vessel V21301, Melter 3 Feed Vessel V21302		MV-LFP-P0002		LFP-VSL-00002 = 9.123
(LAW Melter Feed Process System)		MV-LFP-P0004		LFP-VSL-00003 = 9,123
(LAW Meller reed riocess bystem)	1,0	MV-LFP-P0005		LFP-VSL-00004 = 9,123
		MVD-LFP-00001		
		MVD-LFP-00002		
		MVD-LFP-00003		
		MVD-LFP-00004		
		MVD-LFP-P0007		
	N	MVD-LFP-P0008		
		MVD-LFP-P0010		
		MVD-LFP-P0011		

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 45 of 210

Mixed Waste Tank Systems Name	Unit Designation	Unit Description	Narrative Description, Tables & Figures	Maximum Capacity (gallons)
LAW Caustic Scrubber Blowdown Vessel V22001 (LAW Secondary Off-gas/Vessel Vent Process System)	LVP	RESERVED	Section 4.1.3.3; Table 4-4 and 4-11; and Figures 4A-1, 4A-3, 4A-23 of Attachment 51, Chapter 4.0 of this Permit.	V22001 = 12,191
LAW Melter 1 SBS Condensate Vessel	LOP	24590-LAW	Section 4.1.3.3; Table 4-4 and 4-11; and Figures	V22101 - 6,833
V22101 LAW-MV-LOP-VSL-00001, LAW	LOP	-M6-LOP-P0001	4A-1, 4A-3, 4A-22, 4A-67, and 4A-83 of	LOP-VSL-00001 = 9.056
Melter 2 SBS Condensate Vessel V22201 LAW-MV-LOP-VSL-00002, Melter 3 SBS	 .	<u>-M6-LOP-P0002</u> <u>-MV-LOP-P0001</u>	Attachment 51, Chapter 4.0 of this Permit.	$\frac{\text{V}_{22201} - 6,833}{\text{LOP-VSL-}00002 - 9,056}$
Condensate Vessel V22301,		<u>-MV-LOP-P0002</u> MVD-LOP-P0004		V22301 = 6,833 LOP-SCB-00001 = 4,948
(LAW Primary Off-gas Process System)		MVD-LOP-P0005		LOP-SCB-00002 = 4,948
Plant Wash Vessel <u>LAW-MV-RLD-VSL-00003 V25001</u> , C3/C5 Drains/Sump	RLD	24590-LAW	Section 4.1.3.4; Table 4-4 and 4-11; and Figures	V25001 - 25,130
Collection Vessel RLD-VSL-00004, SBS		<u>-M6-RLD-P0001</u> -M6-RLD-P0002	4A-1, 4A-2, 4A-25, 4A-66, 4A-67, 4A-82, and 4A-83 of Attachment 51, Chapter 4.0 of this	$\begin{array}{c c} RLD-VSL-00003 = 25,780 \\ RLD-VSL-00004 = 7696 \end{array}$
Condensate Collection Vessel <u>LAW-MV-RLD-VSL-00005 V25003</u> (LAW		-MV-RLD-P0001 -MV-RLD-P0002	Permit.	$\begin{array}{c} RLD-VSL-00005 = 25,780 \\ \hline V25003 - 24,704 \end{array}$
Vitrification Plant Radioactive Liquid Waste Disposal System)		-MV-RLD-P0003 -MVD-RLD-P0001		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
waste Disposal System)		-MVD-RLD-P0006		
		<u>-MVD-RLD-P0007</u> -MVD-RLD-00002		
		-MVD-RLD-00003 -MVD-RLD-00004		

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 46 of 210

Table III.10.E.C - HLW Vitrification Plant Tank Systems Description

Mixed Waste Tank Systems	Unit Designation	Unit Description	Narrative Description, Tables & Figures	Maximum		
Name				Capacity		
				(gallons)		
Concentrate Receipt Vessel V31001,	НСР	RESERVED	Section 4.1.4.1; Table 4-5 and 4-11; and Figures	V31001 = 17,900		
Concentrate Receipt Vessel2 V31002		•	4A-1, 4A-4, 4A-26, 4A-71, 4A-72, 4A-73, 4A-	V31002 = 17,900		
(HLW Cave Receipt Process System)			86, and 4A-87 of Attachment 51, Chapter 4.0 of	1,700		
			this Permit.			
	1 A					
	1					
	10 10 10 10 10 10 10 10 10 10 10 10 10 1					
				·		
T 1D 4 1 17 1 17 101 17 W		RESERVED	Section 4.1.4.1; Table 4-5 and 4-11; and Figures	V31101 = 8,800		
Feed Preparation Vessel V31101, HLW Melter Feed Vessel V31102	HFP	KESEKVED	4A-1, 4A-4, 4A-26, 4A-72, 4A-73, 4A-86, and			
(HLW Melter Feed Process System)			4A-87, of Attachment 51, Chapter 4.0 of this	V31102 = 8,800		
(TIEW Wester reed Frocess System)			Permit.			
SBS Condensate Receiver Vessel HOP-		24590-HLW	Section 4.1.4.3; Table 4-5 and 4-11; and Figures	HOP-VSL-00903 = 9891		
VSL-00903 (Melter Off-gas Treatment	НОР		4A-1, 4A-4, 4A-28, 4A-71, and 4A-86 of	1101-1312-00303 - 3831		
Process System-Primary System),		-M6-HOP-P0004	Attachment 51, Chapter 4.0 of this Permit.			
110ccss bystem 11mary bystem),		-M6-HOP-P0006				
		-MV-HOP-P0001	사용 기계 기계 기계 기계 기계 기계 기계 기계 기계 기계 기계 기계 기계			
		-MVD-HOP-P0001				
		-MVD-231-00001				
		DECEDATED	Carting 4.1.45, Table 4.5 and 4.11, and Element	V33004 = 2,500		
Canister Bogie Decontamination Vessel	HDH	RESERVED	Section 4.1.4.5; Table 4-5 and 4-11; and Figures 4A-1, 4A-4, 4A-30, 4A-71, 4A-72, 4A-86, 4A-87			
V33004, Waste Neutralization Vessel V33002, Canister Decontamination Vessel		. ,	of Attachment 51, Chapter 4.0 of this Permit.	V33002 = 5,300		
V33002 , Camster Decontamination Vesser V33001	West 1		of retainment 51, Chapter 10 of this i chine.	V33001 = 580		
(HLW Canister Decontamination Handling						
System)		ı				
Acidic Waste Vessel V35002, Plant Wash	RLD	RESERVED	Section 4.1.4.4; Table 4-5 and 4-11; and Figures	V35002 = 16,700		
and Drains Vessel V35003,			4A-1, 4A-4, 4A-31, 4A-71, 4A-72, 4A-73,4A-86,	V35003 = 13,200		
Decontamination Effluent Collection Vessel			4A-87 of Attachment 51, Chapter 4.0 of this	V35009 = 7,300		
V35009, Off-gas Drains Collection Vessel		1	Permit.	V35038 = 7,280		
V35038				V 33036 - 1,260		
(HLW Vitrification Plant Radioactive		<u> </u>				

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 47 of 210

Liquid Waste D	isposal System)			many timber to the telephone of the second s		
	<u></u>				* .	
1 2						
3		Table III.10.E.D – Anal	ytical Laboratory I	Tank Systems Descriptio	n ·	

Mixed Waste Tank Systems Name	Unit Designation	Unit Description	Narrative Description, Tables & Figures	Maximum Capacity (gallons)
Lab Liquid Effluent Collection Vessel V60001a, Lab Liquid Effluent Collection Vessel V60001b (Analytical Laboratory Tank System)	LAB	RESERVED	Section 4.1.5; Table 4-6 and 4-11; and Figures 4A-1, 4A-2, and 4A-113 of Attachment 51, Chapter 4.0 of this Permit.	V60001a = 12,063 V60001b = 12,063

Table III.10.E.E - Pretreatment Plant Tank System Process and Leak Detection System Instruments and Parameters

Tank System Locator and	Control Parameter	Type of Measuring	Location of Measuring	Instrument Range	Expected Range	Fail States	Instrument Accuracy	Operating Trips (Description &	Instrument Calibration
Name (including P&ID)		or Leak Detection Instrument	Instrument (Tag No.)			. ,1,	e e e e e e e e e e e e e e e e e e e	Numerical Limits)	Method No. and Range
PWD-SUMP- 00071 P-B005 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
PWD-SUMP- 00040 P-B002 ^a	Not Applicable	Bubbler Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
PWD-SUMP- 00001 P-0108B ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
PWD-SUMP- 00001A P-0108C ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
PWD-SUMP- 00002 P-0108A ⁸	Not Applicable	Radar Leak Detector	REŠERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 48 of 210

PWD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00002A	Applicable	Detector		-					
P-0108 ^a PWD-SUMP-	Not	Dadill that	RESERVED	RESERVED	RESERVED	RESERVED	BECERVED	NY-4 A1:1-	BECEBIES
00003	Not Applicable	Radar Leak Detector	KESEKVED	RESERVED	KESEKVED	RESERVED	RESERVED	Not Applicable	RESERVED
P-0106 ^a	Applicable	Detector	4 1.1 1						1
PWD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00004	Applicable	Detector	RESERVED	RESERVED	RESERVED	REBERVED	RESERVED	Not Applicable	RESERVED
P-0104 ^a									
PWD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00005	Applicable	Detector				4.5			:
P-0102A ^a			,		1.		14 to 1 to 1		
PWD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00006	Applicable	Detector	e. Sec.					Two controls	
P-0102 ^a	100	* 1 W		500			4.1.1		
PWD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00007	Applicable	Detector							1
P-0109 ^a									
PWD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00008	Applicable	Detector							
P-0111 ^a			,				***************************************	37 1 1 11	DEGEDIUS
PWD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00009	Applicable	Detector							
P-0112 ^a	N.T. (72 1 7 1	DECEDIAL	DECEDATED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
PWD-SUMP- 00010	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	KESEKVED	Not Applicable	KESEKVED
P-0113 ^a	Applicable	Detector			:				
PWD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00011	Applicable	Detector	RESERVED	RESERVED	KESEKVED	RESERVED	KOSEK (LB	T.Ott Ippliedole	11101111111
P-0114 ^a	пррисави	Bottolion							
PWD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00012	Applicable	Detector							
P-0117 ^a	**								
PWD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00013	Applicable	Detector					14 mg		
P-117A ^a									
PWD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED

Modification to Revision 7

Expiration Date: September 27, 2004 Page 49 of 210

00031 P-0119 ^a	Applicable	Detector							
PWD-SUMP- 00034 P-0121A ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
PWD-SUMP- 00035 P-0122A ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
PWD-SUMP- 00036 P-0118 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

^aSump locator and name (including P&ID designator) is located on Permit Table III.10.E J - Pretreatment Plant Tank Systems Secondary Containment Systems

Including Sumps and Floor Drains.

Table III.10.E.F - LAW Vitrification Plant Tank System Process and Leak Detection System Instruments and Parameters

O			•			-		i	
Tank System Locator and	Control Parameter	Type of Measuring	Location of Measuring	Instrument Range	Expected Range	Fail States	Instrument Accuracy	Operating Trips (Description &	Instrument Calibration
Name (including P&ID)		or Leak Detection Instrument	Instrument (Tag No.)					Numerical Limits)	Method No. and Range
RLD-SUMP- 00028 L-B001B ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
RLD-SUMP- 00029 L-0123 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
RLD-SUMP- 00030 L-0123 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
RLD-SUMP- 00031 L-0124 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
RLD-SUMP- 00032 L-0124 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED

Modification to Revision 7

Expiration Date: September 27, 2004

Page 50 of 210

RLD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00033	Applicable	Detector					a, kw		
L-0125 ^a				*				-	
RLD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00034	Applicable	Detector	<u> </u>		1				
L-0125 ^a						744 ·			
RLD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00035	Applicable	Detector		1 4 4					
L-0126 ^a									
RLD-SUMP-	Not	Radar Leak	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
00036	Applicable	Detector							
L-0126 ^a									
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

a Sump locator and name (including P&ID designator) is located on Permit Table III.10.E L - LAW Vitrification Plant Tank Systems Secondary Containment Systems Including Sumps and Floor Drains.

Table III.10.E.G - HLW Vitrification Plant Tank System Process and Leak Detection System Instruments and Parameters

Tank System Locator and Name (including P&ID)	Control Parameter	Type of Measuring or Leak Detection Instrument	Location of Measuring Instrument (Tag No.)	Instrument Range	Expected Range	Fail States	Instrument Accuracy	Operating Trips (Description & Numerical Limits)	Instrument Calibration Method No. and Range
HCP-SUMP- 00001 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
RLD-SUMP- 00001 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
HOP-SUMP- 00003 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
HOP-SUMP- 00008 ^a	<u>Not</u> <u>Applicable</u>	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
HDH-SUMP- 00001 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
HDH-SUMP- 00002 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESÉRVED

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 51 of 210

V	1			·			· · · · · · · · · · · · · · · · · · ·		
HDH-SUMP- 00003 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
RWH-SUMP- 00001 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
RWH-SUMP- 00005 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
RWH-SUMP- 00006 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
HPH-SUMP- 00001 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
HPH-SUMP- 00005 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
HMH-SUMP- 00002 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
<u>HMH-SUMP-</u> 00003- ^a	<u>Not</u> <u>Applicable</u>	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
<u>HFP-SUMP-</u> 00001 ^{<u>a</u>}	<u>Not</u> <u>Applicable</u>	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
HFP-SUMP- 00002 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
<u>HSH-SUMP-</u> 00007 ²	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
<u>HSH-SUMP-</u> <u>00008^a</u>	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
<u>HSH-SUMP-</u> <u>00009²</u>	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
HSH-SUMP- 00003 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

^aSump locator and name (including P&ID designator) is located on Permit Table III.10.E N - HLW Vitrification Plant Tank Systems Secondary Containment

Table III.10.E.H - Laboratory Tank System Process and Leak Detection System Instruments and Parameters

Systems Including Sumps and Floor Drains.

Modification to Revision 7

Expiration Date: September 27, 2004

Page 52 of 210

Tank System Locator and Name (including P&ID)	Control Parameter	Type of Measuring or Leak Detection Instrument	Location of Measuring Instrument (Tag No.)	Instrument Range	Expected Range	Fail States	Instrument Accuracy	Operating Trips (Description & Numerical Limits)	Instrument Calibration Method No. and Range
RLD-SUMP- 00041 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
RLD-SUMP- 00042 ^a	Not Applicable	Radar Leak Detector	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	Not Applicable	RESERVED
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

^aSump locator and name (including P&ID designator) is located on Permit Table III.10.E P - Laboratory Tank Systems Secondary Containment Systems Including Sumps and Floor Drains.

Table III.10.E.I - Pretreatment Plant Tank Systems Primary^a Containment Sump Systems

	<u></u>		
Γ	Sump I.D.# & Room	Maximum Sump Capacity	Sump Dimensions (feet) & Engineering Description
	Location	(gallons)	Materials of Construction (Drawing Nos., Specifications
			Nos., etc.)
Γ	RESERVED	RESERVED	RESERVED RESERVED

Primary sumps are defined in Permit Section III.10.C, and must comply with dangerous waste tank system requirements for tanks as described in WAC-173-303-640.

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 53 of 210

Table III.10.E J – Pretreatment Plant Tank Systems Secondary Containment Systems Including Sumps and Floor Drains

And the second second second second second	三百多 以新发生的发生的		그 그 그 그 그 그 그 그 그 그 그 그 그 그 그 그 그 그 그	
Sump or Drain Line I.D.# & Room Location	Maximum Sump (gallons) or Drain Line (gallons per minute) Capacity	Sump Type/Nominal Operating Volume (gallons)	Sump or Drain Line Dimensions (inches) & Materials of Construction	Engineering Description (Drawing Nos., Specifications No.'s, etc.)
PWD-SUMP-00071	112.2	Dry Sump ^a	24"x30"x36"	24590-PTF
P-B005 (Pit-19, El19')		,	Coating Type (RESERVED)	-M6-PWD-P00041
				-P1-P01T-P0006
				-P1-P01T-P0012
PWD-SUMP-00040	233.7	Wet Sump/	60"x30"x30"	24590-PTF
P-B002 (Pit-45, El45')	1 m	140.3	6Мо	-M6-PWD-P00012
			·	-P1-P01T-P0006
	The state of the s			<u>-P1-P01T-P0009</u>
PWD-SUMP-00001	73.5	Dry Sump ^e	30" Dia. By ~28" deep	24590-PTF
P-0108B (El. 0')			304L	-M6-PWD-P00008
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			-P1-P01T-P0001
				<u>-P1-P01T-P0009</u>
PWD-SUMP-00001A	73.5	Dry Sump ^a	30" Dia. By ~28" deep	24590-PTF
P-0108C (El. 0')			304L	-M6-PWD-P00010
				-P1-P01T-P0001
				-P1-P01T-P0010
PWD-SUMP-00002	73.5	Dry Sump [#]	30" Dia. By ~28" deep	24590-PTF
P-0108A (El. 0')	· var	,	304L	-M6-PWD-P00008
				-P1-P01T-P0001
				-P1-P01T-P0008
PWD-SUMP-00002A	73.5	Dry Sump ^a	30" Dia. By ~28" deep	24590-PTF
P-0108 (El. 0')	Tw.		304L	-M6-PWD-P00010
				-P1-P01T-P0001
4	200 A T			-P1-P01T-P0008
PWD-SUMP-00003	73.5	Dry Sump ^a	30" Dia. By ~28" deep	24590-PTF
P-0106 (El. 0')			304L	-M6-PWD-P00008
	,			-P1-P01T-P0001
				-P1-P01T-P0008
PWD-SUMP-00004	73.5	Dry Sump [#]	30" Dia. By ~28" deep	24590-PTF
P-0104 (El. 0')			304L	-M6-PWD-P00008

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 54 of 210

<u> </u>	<u>· </u>			The state of the s
				-P1-P01T-P0001
	•			-P1-P01T-P0008
PWD-SUMP-00005	73.5	Dry Sump ^a	30" Dia. By ~28" deep	24590-PTF
P-0102A (E1. 0')			304L	-M6-PWD-P00008
				-P1-P01T-P0001
				-P1-P01T-P0008
PWD-SUMP-00006	73.5	Dry Sump*	30" Dia. By ~28" deep	24590-PTF
P-0102 (El. 0')			304L	-M6-PWD-P00008
				-P1-P01T-P0001
				-P1-P01T-P0008
PWD-SUMP-00007	73.5	Dry Sump*	30" Dia. By ~28" deep	24590-PTF
P-0109 (El. 0')			304L	-M6-PWD-P00009
				-P1-P01T-P0001
		The second second		-P1-P01T-P0010
PWD-SUMP-00008	73.5	Dry Sump ^a	30" Dia. By ~28" deep	24590-PTF
P-0111 (El. 0')		, ,	304L	-M6-PWD-P00009
		· ·		-P1-P01T-P0001
				-P1-P01T-P0010
PWD-SUMP-00009	73.5	Dry Sump ^a	30" Dia. By ~28" deep	24590-PTF
P-0112 (El. 0')			304L	-M6-PWD-P00009
	,	-	· ·	-P1-P01T-P0001
PWD-SUMP-00010	73.5	Dry Sump ^a	30" Dia. By ~28" deep	24590-PTF
P-0113 (El. 0')		· · · · · · · · · · · · · · · · · · ·	304L	-M6-PWD-P00009
				-P1-P01T-P0001
				-P1-P01T-P0010
PWD-SUMP-00011	73.5	Dry Sump [⊕]	30" Dia. By ~28" deep	24590-PTF
P-0114 (El. 0')		*****	304L	-M6-PWD-P00009
	l e de la companya de la companya de la companya de la companya de la companya de la companya de la companya de			-P1-P01T-P0001
				-P1-P01T-P0010
PWD-SUMP-00012	73.5	Dry Sump [®]	30" Dia. By ~28" deep	24590-PTF
P-0117 (El. 0')			304L	-M6-PWD-P00009
		;		-P1-P01T-P0001
				-P1-P01T-P0010
PWD-SUMP-00013	73.5	Dry Sump ^a	30" Dia. By ~28" deep	24590-PTF
P-0117A (El. 0')			304L	-M6-PWD-P00014
		•		-P1-P01T-P0001

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 55 of 210

				-P1-P01T-P0010
PWD-SUMP-00031	73.5	Dry Sump [®]	30" Dia. By ~28" deep	24590-PTF
P-0119 (El. 0')			304L	-M6-PWD-P00010
			en en en en en en en en en en en en en e	-P1-P01T-P0001
			4	-P1-P01T-P0010
PWD-SUMP-00034	73.5	Dry Sump [®]	30" Dia. By ~28" deep	24590-PTF
P-0121A (El. 0')			304L	-M6-PWD-P00012
	e de la companya del companya de la companya del companya de la co		z_{∞} .	-P1-P01T-P0001
				-P1-P01T-P0010
PWD-SUMP-00035	73.5	Dry Sump [#]	30" Dia. By ~28" deep	24590-PTF
P-0122A (El. 0')	1 n i		304L	-M6-PWD-P00012
				-P1-P01T-P0001
PWD-SUMP-00036	73.5	Dry Sump ^a	30" Dia. By ~28" deep	24590-PTF
P-0118 (El. 0')	4		304L	-M6-PWD-P00012
				-P1-P01T-P0001
				-P1-P01T-P0010
PJV-ZF-00027-S11B-02	60	N/A	2" Dia.	24590-PTF-M6-PJV-P0002
P-0101 (PJV-BULGE-			316L	
00001 Drain, El. 0')				
PWD-ZF-00004-S11B-02	60	N/A	2" Dia.	24590-PTF-M6-PVP-P0003
P-0105 (PVP-BULGE-	• ,		316L	
00001 Drain, El. 0')				
PWD-ZF-00005-S11B-02	60	N/A	2" Dia.	24590-PTF-M6-PVP-P0003
P-0101A (PVP-BULGE-			316L	
00002 Drain, El. 0')				
RDP-ZF-00016-S11B-02	60	N/A	2" Dia.	24590-PTF-M6-RDP-P0001
P-0110A (RDP-BULGE-			316L	
00010 Drain, El. 0')				
TCP-PH-00032-S11B-02	60	N/A	2" Dia.	24590-PTF-M6-TCP-P0001
P-0116 (TCP-BULGE-			316L	
00004 Drain, El. 0')				
TEP-ZF-02066-S11B-	40	N/A	1-1/2" Dia.	24590-PTF-M6-TEP-P0001
011/2			316L	
P-0110A (TEP-BULGE-	*			
00006 Drain, El. 0')				

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 56 of 210

			T	
TXP-ZF-00022-S11M-	40	N/A	1-1/2" Dia.	24590-PTF-M6-TXP-P0001
011/2			316L	
P-0110B (TXP-BULGE-				
00001 Drain, El. 0')		•		
TXP-ZF-00021-S11M-	40	N/A	1-1/2" Dia.	24590-PTF-M6-TXP-P0001
011/2			316L	
P-0110C (TXP-BULGE-				
00002 Drain, El. 0')			ļ.,	
TXP-ZF-00042-S11M-	40	N/A	1-1/2" Dia.	24590-PTF-M6-TXP-P0001
011/2			316L	
P-0110C (TXP-BULGE-				
00004 Drain, El. 0')				
TXP-ZF-00019-S11M-	40	N/A	1-1/2" Dia.	24590-PTF-M6-TXP-P0004
011/2			316L	
P-0110C (TXP-BULGE-	to see			
00005 Drain, El. 0')				
CNP-ZF-00043-S11B-03	160	N/A	3" Dia.	24590-PTF-M6-CNP-P0002
P-0207 (CNP-BULGE-	,		316L	
00008 Drain, El. 28')				
PWD-FD-00432	155	N/A	6" Dia.	24590-PTF-M6-PWD-P0044
P-0201 Drain, El. 28'			316L	
PWD-FD-00452	706	N/A	8" Dia.	24590-PTF-M6-PWD-P0044
P-0201 Drain, El. 28'			316L	
PWD-FD-00456	155	. N/A	6" Dia.	24590-PTF-M6-PWD-P0044
P-0201A Drain, El. 28'			316L	
PWD-FD-00341	155	N/A	6" Dia.	24590-PTF-M6-PWD-P0044
P-0201A Drain, El. 28'			316L	
PWD-FD-00351A	52	N/A	3" Dia.	24590-PTF-M6-PWD-P0044
P-0201A Drain, El. 28'			316L	
PWD-FD-00451	706	N/A	8" Dia.	24590-PTF-M6-PWD-P0044
P-0203 Drain, El. 28'			316L	
PWD-FD-00339	155	N/A	6" Dia.	24590-PTF-M6-PWD-P0044
P-0203 Drain, El. 28'			316L	
PWD-FD-00450	706	N/A	8" Dia.	24590-PTF-M6-PWD-P0044
P-0203 Drain, El. 28'		14/21	316L	
1 -0203 Diam, Li. 20	<u> </u>	<u></u>	1 2102	<u> </u>

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 57 of 210

PWD-FD-00450A	155	N/A	6" Dia.	24590-PTF-M6-PWD-P0044
P-0203 Drain, El. 28'	To the control of the		316L	
PWD-FD-00449A	52	N/A	3" Dia.	24590-PTF-M6-PWD-P0044
P-0203 Drain, El. 28'			316L	
PWD-FD-00449	706	N/A	8" Dia.	24590-PTF-M6-PWD-P0044
P-0203A Drain, El. 28'			316L	
PWD-FD-00338	155	N/A	6" Dia.	24590-PTF-M6-PWD-P0044
P-0203A Drain, El. 28'			316L	2.050 1 12 1129 1 113 1 100 11
PWD-FD-00337	155	N/A	6" Dia.	24590-PTF-M6-PWD-P0044
P-0203B Drain, El. 28'			316L	
PWD-FD-00448	706	N/A	8" Dia,	24590-PTF-M6-PWD-P0044
P-0203B Drain, El. 28'			316L	
PWD-FD-00447A	52	N/A	3" Dia.	24590-PTF-M6-PWD-P0044
P-0203B Drain, El. 28'			316L	
PWD-FD-00447	706	N/A	8" Dia.	24590-PTF-M6-PWD-P0044
P-0204 Drain, El. 28'	(A)		316L	
PWD-FD-00336	155	N/A	6" Dia,	24590-PTF-M6-PWD-P0044
P-0204 Drain, El. 28'			316L	
PWD-FD-00397	155	N/A	6" Dia.	24590-PTF-M6-PWD-P0043
P-0206 Drain, El. 28'			316L	
PWD-FD-00443	706	N/A	8" Dia.	24590-PTF-M6-PWD-P0043
P-0206 Drain, El. 28'	2 V 1 S.S.		316L	
PWD-FD-00398A	52	N/A	3" Dia.	24590-PTF-M6-PWD-P0043
P-0207 Drain, El. 28'			316L	
PWD-FD-00398	155	N/A	6" Dia.	24590-PTF-M6-PWD-P0043
P-0207 Drain, El. 28'	k a la		316L	
PWD-FD-00399	155	N/A	6" Dia.	24590-PTF-M6-PWD-P0043
P-0208 Drain, El. 28'			316L	
PWD-FD-00400	52	N/A	3" Dia.	24590-PTF-M6-PWD-P0043
P-0209 Drain, El. 28'			316L	
PWD-FD-00444	706	N/A	8" Dia.	24590-PTF-M6-PWD-P0043
P-0209 Drain, El. 28'			316L	
PWD-FD-00401	155	N/A	6" Dia.	24590-PTF-M6-PWD-P0043
P-0209 Drain, El. 28'			316L	
PWD-FD-00402	155	N/A	6" Dia.	24590-PTF-M6-PWD-P0043
P-0210 Drain, El. 28'			316L	

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 58 of 210

PWD-FD-00445	706	N/A	8" Dia.	24590-PTF-M6	-PWD-P0043
P-0210 Drain, El. 28'			316L		
PWD-FD-00445A	706	N/A	8" Dia.	24590-PTF-M6	-PWD-P0043
P-0212 Drain, El. 28'			316L		
PWD-FD-00442	52	N/A	3" Dia.	24590-PTF-M6	-PWD-P0043
P-0212 Drain, El. 28'			316L		
PWD-FD-00404	155	N/A	6" Dia.	24590-PTF-M6	-PWD-P0043
P-0212 Drain, El. 28'			316L		
PWD-FD-00404A	155	N/A	6" Dia.	24590-PTF-M6	-PWD-P0043
P-0212 Drain, El. 28'			316L	1	
PWD-FD-00446	706	N/A	8" Dia.	24590-PTF-M6	-PWD-P0043
P-0212 Drain, El. 28'		·	316L		
RESERVED	RESERVED	RESERVED	RESERVED	RESER	VED

^aThis sump is routinely accessible for inspections and maintenance.

Modification to Revision 7

Expiration Date: \$eptember 27, 2004

Page 59 of 210

Table III.10.E K - LAW Vitrification Plant Tank Systems Primarya Containment Sump Systems

Sump I.D.# & Room Location	Maximum Sump Capacity (gallóns)	Sump Dimensions (feet) & Materials of Construction	Engineering Description (Drawing Nos., Specification Nos., etc.)	
RESERVED	RESERVED	RESERVED	RESERVED	

^a Primary sumps are defined in Permit Section III.10.C, and must comply with dangerous waste tank system requirements for tanks as described in WAC-173-303-640.

Table III.10.E.L - LAW Vitrification Plant Tank Systems Secondary Containment Systems Including Sumps and Floor Drains

Sump or Drain Line I.D.# & Room Location	Maximum Sump (gallons) or Drain Line (gallons per minute) Capacity	Sump Type/Nominal Operating Volume (gallons)	Sump or Drain Line Dimensions (inches) & Materials of Construction	Engineering (Drawing Nos., Nos.,	Specifications	
RLD-SUMP-00028	59	Dry Sump ^e	24" Dia. By 30" deep	24590-LAW-M	6-RLD-P0002	
L-B001B (C3/C5			304L or higher grade			
Drains/Sump Collection Vessel Cell, El. –21')		•				
RLD-SUMP-00029	46	Dry Sump*	30" Dia. By 15" deep	24590-LAW-M	6-R1 D-P0003	
L-0123 (Process Cell, El. +3'		, ~ , p	304L or higher grade			
RLD-SUMP-00030	46	Dry Sump ^a	30" Dia. By 15" deep	24590-LAW-M	6-RLD-P0003	
L-0123 (Process Cell, El.		•	304L or higher grade		,	
+3')	1. July 186					
RLD-SUMP-00031	46	Dry Sump [€]	30" Dia. By 15" deep	24590-LAW-M	6-RLD-P0003	
L-0124 Process Cell			304L or higher grade			
Sump, El. +3')					Maria de Maria de Carlos de Carlos de Carlos de Carlos de Carlos de Carlos de Carlos de Carlos de Carlos de Car La compansión de Carlos de Carlos de Carlos de Carlos de Carlos de Carlos de Carlos de Carlos de Carlos de Car	
RLD-SUMP-00032	46	Dry Sump ^a	30" Dia. By 15" deep	24590-LAW-M	6-RLD-P0003	
L-0124 (Process Cell, El.		•	304L or higher grade			
+3')						
RLD-SUMP-00033	46	Dry Sump ^e	30" Dia. By 15" deep	24590-LAW-M	6-RLD-P0003	
L-0125 (Process Cell, El.			304L or higher grade			
+3')						

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 60 of 210

RLD-SUMP-00034	46	Dry Sump ^a	30" Dia. By 15" deep	24590-LAW-M6-RLD-P0003
L-0125 (Process Cell, El.			304L or higher grade	
+3')				
RLD-SUMP-00035	46	Dry Sump ^e	30" Dia. By 15" deep	24590-LAW-M6-RLD-P0003
L-0126 (Effluent Cell, El.	in the second se		304L or higher grade	
+3')				
RLD-SUMP-00036	46	Dry Sump ^e	30" Dia. By 15" deep	24590-LAW-M6-RLD-P0003
L-0126 (Effluent Cell, El.			304L or higher grade	
+3')				
Drain Line ID# =	60	N/A	2" Dia.	24590-LAW-M6-RLD-P0002
RESERVED			316L	
L-B001B (RLD-BULGE-				
00001 Drain, El21')				
Drain Line ID# =	30	N/A	1" Dia.	24590-LAW-M6-RLD-P0002
RESERVED			316L	
L-B001B (Double-Walled			· · · · · · · · · · · · · · · · · · ·	
Piping Outer Containment				
Drain, El21')				
Drain Line ID# =	60	N/A	2" Dia.	24590-LAW-M6-LOP-P0001
RESERVED			6 Mo	
L-0123 [Primary Offgas				<u> </u>
(LOP) Melter 1 Valve		and the second second		
Bulge Drain, El. +3']				
Drain Line ID# =	60	N/A	2" Dia.	24590-LAW-M6-LCP-P0001
RESERVED			316L	
L-0123 (Concentrate Feed				
Receipt LCP-VSL-00001				
Valve Bulge Drains, El.				
+3')		,		
Drain Line ID# =	60	N/A	2" Dia.	24590-LAW-M6-LFP-P0001
RESERVED			316L	
L-0123 (Melter 1 Feed				
Prep/Feed Vessel Valve				
Bulge Drain, El. +3')				
Drain Line ID# =	60	N/A	2" Dia.	24590-LAW-M6-LOP-P0002
RESERVED			6 Mo	
KLDLK I DD				

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 61 of 210

- · · · · · · · · · · · · · · · · · · ·	and the second second			•	•
L-0124 [Primary Offgas					
(LOP) Melter 2 Valve					
Bulge Drain, El. +3']					
Drain Line ID# =	60	N/A	2" Dia.	24590-LAW-N	6-LCP-P0002
RESERVED			316L		.0 2.0002
L-0124 (Concentrate	•				2
Receipt Vessel LCP-VSL-					
00002 Valve Bulge Drain,				,	1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 -
E1. +3')					
Drain Line ID# =	60	N/A	2" Dia,	24590-LAW-N	16-LFP-P0003
RESERVED			316L		
L-0124 (Melter 2 Feed					. · · · · · · · · · · · · · · · · · · ·
Prep/Feed Vessel Valve					
Bulge Drain, El. +3')					
Drain Line ID# =	60	N/A	2" Dia.	24590-LAW-N	6-LOP-P0003
RESERVED		* **	6 Mo		• •
L-0125 [Primary Offgas					
(LOP) Melter 3 Valve					
Bulge Drain, El. +3']	, .				
Drain Line ID# =	60	N/A	2" Dia.	24590-LAW-N	16-LFP-P0005
RESERVED			316L		
L-0125 (Melter 3 Feed					
Prep/Feed Vessel Valve					Ť. [1
Bulge Drain, El. +3')			w th		4. L
Drain Line ID# =	60	N/A	2" Dia.	24590-LAW-N	16-LCP-P0002
RESERVED			316L		
L-0125 (Concentrate					
Receipt Vessel LCP-VSL-					
00003 Valve Bulge Drain,					
El. +3')					
Drain Line ID# =	60	N/A	2" Dia.	24590-LAW-M	6-RLD-P0001
RESERVED			6 Mo		
L-0126 (Plant Wash					
Vessel/SBS Condensate					
Collection Vessel Valve		**			
Bulge Drain, El. +3')					

Modification to Revision 7

Expiration Date: September 27, 2004

Page 62 of 210

RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

Table III.10.E M - HLW Vitrification Plant Tank Systems Primary^a Containment Sump Systems

Sump I.D.# & Room Location	Maximum Sump Capacity (gallons)	Sump Dimensions (feet) & Materials of Construction	Engineering Description (Drawing Nos., Specifications Nos., etc.)
RESERVED	RESERVED	RESERVED	RESERVED

^aPrimary sumps are defined in Permit Section III.10.C, and must comply with dangerous waste tank system requirements for tanks as described in WAC-173-303-640.

Table III.10.E N - HLW Vitrification Plant Tank Systems Secondary Containment Systems Including Sumps and Floor Drains

		· · · · · · · · · · · · · · · · · · ·		,		
Sump or Drain Line I.D.# & Room Location	Maximum Sump Sump (gallons) or Drain Type/Nominal Line (gallons per Operating Volume		Sump or Drain Line Dimensions (inches) & Materials of Construction	Engineering Description (Drawing Nos., Specifications Nos., etc.)		
	minute) Capacity	(gallons)				
HCP-SUMP-00001 H-B014 (Wet Process Cell, El. –21')	70	Wet Sump / 60	30" Dia. x 18" Deep 6Mo	24590-HLW-M6-RLD-P0015		
RLD-SUMP-00001 H-B014 (Wet Process Cell, El21')	70	Wet Sump / 60	30" Dia. x 18" Deep 6Mo	24590-HLW-M6-RLD-P0015		
HOP-SUMP-00003 H-B021 (SBS Drain Collection Cell No. 1, El. –21')	70	Dry Sump	30" Dia. x 18" Deep 6Mo	24590-HLW-M6-RLD-P0015		
HOP-SUMP-00008 H-B005 (SBS Drain Collection Cell No. 2, El21	<u>70</u>	<u>Dry Sump</u>	30" Dia. X 18" Deep 6Mo	24590-HLW-M6-RLD-P20004		

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 63 of 210

	· · · · · · · · · · · · · · · · · · ·			
HDH-SUMP-00001	70	Dry Sump	30" Dia. x 18" Deep	24590-HLW-M6-RLD-P0016
H-B039B (Canister Rinse			6Mo	
Tunnel, El. –16.5')			and the second second	
HDH-SUMP-00002	70	Dry Sump	30" Dia. x 18" Deep	24590-HLW-M6-RLD-P0004
H-B039A (Bogie			6Мо	
Decon/Maint, Tunnel-				
Canister Rinse, El. –16')				the same larger to
HDH-SUMP-00003	70	Dry Sump	30" Dia. x 18" Deep	24590-HLW-M6-RLD-P0015
H-B035 (Canister Decon			6Мо	
Cave, El. –16')	1.77			
RWH-SUMP-00001	70	Dry Sump	30" Dia. x 18" Deep	24590-HLW-M6-RLD-P0017
H-B015 (Drum Transfer	W. Carlotte and Ca		6Mo	2.050 112.0 100 1001.
Tunnel, El9.5')		·		
RWH-SUMP-00005	70	Dry Sump	30" Dia. x 18" Deep	24590-HLW-M6-RLD-P0017
H-B015 (Drum Transfer		J	6Мо	
Tunnel, El. –9.5')				
RWH-SUMP-00006	70	Dry Sump	30" Dia. x 18" Deep	24590-HLW-M6-RLD-P0017
H-B015 (Drum Transfer		,	6Мо	
Tunnel, El9.5')	N		*	
HPH-SUMP-00001	70	Dry Sump	30" Dia. x 18" Deep	24590-HLW-M6-RLD-P0016
H-0136 (Canister Handling			6Мо	
Cave, El3')				
HPH-SUMP-00005	70	Dry Sump	30" Dia. x 18" Deep	24590-HLW-M6-RLD-P0004
H-0136 (Canister Handling			6Мо	
Cave, El3')		,		
HMH-SUMP-00002	70	Dry Sump	30" Dia. x 18" Deep	24590-HLW-M6-RLD-P0003
H-0116B (Melter Cave No.			6Мо	
1-C3/C5Airlock, El. 0')	3.			
HMH-SUMP-00003	<u>10.8</u>	Dry Sump	18" in. x 11.5" x 12" Deep	24590-HLW-M6-RLD-P0003
H-0105B (Melter Cave No.	·		<u>6Mo</u>	
2-C3/C5Airlock, El. 0')	13			
HFP-SUMP-00001	<u>70</u>	Gravity Drain	30" Dia. x 18" Deep	24590-HLW-M6-RLD-P0015
H-0308 (Active Services			<u>6Mo</u>	
Duct Melter No.1 El, 37')				
HFP-SUMP-00002	70	Wet Sump / 60	30" Dia. x 18" Deep	24590-HLW-M6-RLD-P0008
H-0117 (Melter Cave No. 1,			6Mo	
El. 5')				
HFP-SUMP-00004	70	Gravity Drain	30" Dia. x 18" Deep	24590-HLW-M6-RLD-P0004
H-0302 (Active Services			<u>6Mo</u>	
Duct Melter No.2 El. 37')	4.			

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 64 of 210

HFP-SUMP-00005 70 Dry Sump 30" Dia, x 18" Deep 6Mo	24590-HLW-M6-RLD-P0005 24590-HLW-M6-RLD-P0017
El. 5')	24590-HLW-M6-RLD-P0017
	24590-HLW-M6-RLD-P0017
HOP-SUMP-00004 70 Dry Sump 30" Dia, x 18" Deep	24590-HLW-M6-RLD-P0017
	[24330-11E W -MD-KED-1 0017
H-0117 (Melter Cave No. 1,	
H-0117 (Wetter Cave No. 1, El. 3')	
	24590-HLW-M6-RLD-P0008
	24390-FLW-M0-KLD-F0006
1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	
El. 3')	24500 HI W MC DI D D0005
HSH-SUMP-00007 37.4 Dry Sump 24" x 18" x 20" Deep	24590-HLW-M6-RLD-P0005
H-0106 (Melter Cave No.	
2El. 3')	OACOO TITAY NEED DOORS
<u>HSH-SUMP-00008</u> <u>70</u> <u>Dry Sump</u> <u>30" Dia x 18" Deep</u>	24590-HLW-M6-RLD-P0003
<u>H-0310A (Melter No. 1</u> 6 <u>Mo</u>	
Equip. Decon. Area El. 0')	
<u>HSH-SUMP-00009</u> <u>70</u> <u>Dry Sump</u> <u>30" Dia x 18" Deep</u>	24590-HLW-M6-RLD-P0003
<u>H-0304A (Melter No. 2</u> <u>6Mo</u>	
Equip. Decon. Area El. 0')	
RLD-ZF-00330-S11B-03 20 Floor Drain Overflow Line Size Pipe Dia	<u>m 3" 24590-HLW-M6-RLD-P0015</u>
H-B021 (SBS Drain 316L Stainless Steel	
Collection Cell No. 1)	
RLD-ZF-03447-S11B-03 20 Floor Drain Overflow Line Size Pipe Dia	<u>m 3" 24590-HLW-M6-RLD-P20004 </u>
H-B005 (SBS Drain 316L Stainless Steel	
Collection Cell No. 2)	
HCP-PC-00057-S12A-011/2 <u>5</u> Floor Drain Overflow Line Size Pipe Di	
H-B014 (Wet Process Cell 1.5" 316L Stainless Stee	1
HCP-PC-00061-S12A-011/2 5 Floor Drain Overflow Line Size Pipe Di	iam 24590-HLW-M6-RLD-P0015
H-B014 (Wet Process Cell 1.5" 316L Stainless Stee	
RESERVED RESERVED RESERVED	RESERVED

Modification to Revision 7

Expiration Date: September 27, 2004 Page 65 of 210

Table III.10.E O - Laboratory Tank Systems Primary Containment Sump Systems

Sump I.D.# & Room Maximum Sump Capacity	Sump Dimensions (feet) & Materials Engineering Description
Location (gallons)	of Construction (Drawing Nos., Specifications
	Nos., etc.)
RESERVED	RESERVED RESERVED

^a Primary sumps are defined in Permit Section III.10.C, and must comply with dangerous waste tank system requirements for tanks as described in WAC-173-303-640.

Table III.10.E P - Laboratory Tank Systems Secondary Containment Systems Including Sumps and Floor Drains

Sump I.D.# & Room Location	Maximum Sump Capacity (gallons)	Sump Type/Nominal Operating Volume (gallons)	Sump Dimensions (inches) & Materials of Construction	Engineering Description (Drawing Nos., Specifications Nos., etc.)
RLD-SUMP-00041 A-B003 (C3 Effluent Vessel Cell, El18'7')	30	Dry	30" Dia. X ~12" Deep 304L or higher grade	24590-LAB -M6-RLD-P0002 -P160-P0007
RLD-SUMP-00042 A-B004 (C5 Effluent Vessel Cell, El19'2')	30	Dry	30" Dia. X ~12" Deep 304L or higher grade	24590-LAB -M6-RLD-P0001 -LAB-P160-P0007
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED


Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 66 of 210

1	III.10.F.	CONTAINMENT BUILDING UNITS
2	III.10.F.1.	Containment Building Units and Storage Limits
3	III.10.F.1.a.	Approved Waste and Storage Limits
4 5 6 7 8 -9 10		i. The Permittees may store and treat, in containment building units listed in Permit Table III.10.F.A., as modified by Permit Condition III.10.F.7.d.iv., all dangerous and mixed waste listed in the Part A Forms, Attachment 51, Chapter 1.0 of this Permit, except for those wastes outside the waste acceptance criteria specified in the WAP, Attachment 51, Chapter 3.0, as approved pursuant to Permit Condition III.10.C.3. Total dangerous and mixed waste storage at the containment building units shall not exceed the sum of the capacities in column 7 of Permit Table III.10.F.A., as modified pursuant to Permit Condition III.10.F.7.d.iv.
12 13 14 15 16 17 18 19 20 21		ii. The Permittees may place and store dangerous and mixed waste only in the containment building units listed in Permit Table III.10.F.A., as modified pursuant to Permit Condition III.10.F.7.d.iv., in accordance with Permit Condition III.10.F., and in accordance with Attachment 51, Chapters 1.0 and 4.0, and Attachment 51, Appendices 8.1, 8.2, 8.4 through 8.10, 8.13, 8.15, 9.1, 9.2, 9.4 through 9.10, 9.13, 9.18, 10.1, 10.2, 10.4 through 10.10, 10.13, and 10.18 of this Permit, as approved pursuant to Permit Conditions III.10.F.7.c. and III.10.F.7.d. The Permittees shall limit the volume of dangerous and mixed waste to quantities specified for the individual areas listed in column 7 of Permit Table III.10.F.A., as modified pursuant to Permit Condition III.10.F.7.d.iv.
22 23 24 25 26	III.10.F.1.b.	The Permittees shall manage any ignitable, reactive, or incompatible waste in these units in accordance with WAC 173-303-395(1). Any containment building units specified in Permit Table III.10.F.A. in which ignitable, reactive, or incompatible waste are managed shall meet the requirements specified in WAC 173-303-640(9) and (10), in accordance with WAC 173-303-680(2).
27 28 29 30	III.10.F.1.c.	The Permittees must maintain documentation in the operating record of the description and quantity of dangerous waste in each containment building unit listed in Permit Table III.10.F.A., as modified pursuant to Permit Condition III.10.F.7.d.iv., in accordance with WAC 173-303-380.
31 32 33	III.10.F.1.d.	The Permittees shall ensure all certifications required by specialists (e.g., qualified, registered, professional engineer, etc.) use the following statement or equivalent pursuant to Permit Condition III.10.C.10., of this Permit:
34 35 36 37 38 39 40		"I, (Insert Name) have (choose one or more of the following: overseen, supervised, reviewed, and/or certified) a portion of the design or installation of a new containment building unit or component located at (address), and owned/operated by (name(s)). My duties were: (e.g., design engineer, etc.), for the following containment building unit components (e.g., the venting piping, etc.), as required by the Resource Conservation and Recovery Act (RCRA) regulation(s), namely, 40 CFR 264.1101(c)(2) in accordance with WAC 173-303-695).
41 42 43 44 45		"I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment."

Modification to Revision 7

Expiration Date: September 27, 2004

Page 67 of 210



Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 68 of 210

1 2		of dangerous and mixed waste.
3 4 5	III.10.F.3.d.	Throughout the active life of the containment building unit, if the Permittees detects a condition that could lead to or has caused a release of dangerous and/or mixed waste, the Permittees must repair the condition promptly, in accordance with the following procedures:
6 7		i. Upon detection of a condition that has lead to the release of dangerous and/or mixed waste (e.g., upon detection of leakage from the primary barrier) the Permittees must:
8		A. Enter a record of the discovery in the facility operating record;
9 10	. **)	B. Immediately remove the portion of the containment building unit affected by the condition from service;
11 12 13		C. Determine what steps must be taken to repair the containment building unit, remove any leakage from the secondary collection system, and establish a schedule for accomplishing the cleanup and repairs; and
14 15 16 17		D. Within seven (7) days after the discovery of the condition, notify Ecology of the condition, and within fourteen (14) working days, provide a written notice to Ecology with a description of the steps taken to repair the containment building unit, and the schedule for accomplishing the work.
18 19 20 21		ii. Ecology will review the information submitted, make a determination regarding whether the containment building unit must be removed from service completely or partially until repairs and cleanup are complete, and notify the Permittees of the determination and underlying rationale in writing.
22 23 24 25		iii. Upon completing all repairs and cleanup the Permittees must notify Ecology in writing and provide verification, signed by a qualified, registered, professional engineer, that repairs have been completed according to the written notice submitted in accordance with Permit Condition III.10.F.3.d.i.D.
26	III.10.F.4	Inspections [WAC 173-303-640(6)]
27 28 29	III.10.F.4.a.	The Permittees shall inspect the containment building units in accordance with the Inspection Schedules in Attachment 51, Chapter 6.0 of this Permit, as modified pursuant to Permit Condition III.10.C.5.c.
30 31 32	III.10.E.4.b.	The inspection data for the containment building units shall be recorded, and the records shall be placed in the WTP Unit operating record, in accordance with Permit Condition III.10.C.4.
33	III.10.F.5	Recordkeeping (WAC 173-303-380)
34 35 36 37		For the containment building units, the Permittees shall record and maintain in the WTP Unit operating record, all monitoring, calibration, recording, maintenance, test data, and inspection data compiled under the conditions of this Permit, in accordance with Permit Condition III.10.C.4. and III.10.C.5.
38	III.10.F.6.	Closure
39 40		The Permittees shall close the containment building units in accordance with Attachment 51, Chapter 11.0 of this Permit, as approved pursuant to Permit Condition III.10.C.8.

Modification to Revision 7

Expiration Date: September 27, 2004

Page 69 of 210



- 2 III.10.F.7.a. All information identified for submittal to Ecology in b. through e. of this compliance 3 schedule must be signed in accordance with requirements in WAC 173-303-810(12), as 4 modified in accordance with Permit Condition III.10.F.1.d. [WAC 173-303-806(4)].
- III.10.F.7.b. Prior to initial receipt of dangerous and/or mixed waste, the Permittees shall submit to Ecology a certification by a qualified, registered, professional engineer that the containment building units design meets the requirements of Permit Conditions II.10.F.1. and III.10.F.2. in accordance with Permit Condition III.10.F.7.a. The certification will also be stored in the WTP Unit operating record. For containment buildings units in Permit Table III.10.F.A., as modified pursuant to Permit Condition III.10.F.7.d.iv., identified as allowed to manage free liquids, the certification shall include an additional demonstration that the containment building meets the requirements specified in 40 CFR 264.1101(b), in accordance with WAC 173-303-695.
 - III.10.F.7.c. The Permittees shall submit to Ecology pursuant to Permit Condition III.10.C.9.f., prior to construction of the containment building unit containment system, and as appropriate, leak detection system for each containment building unit (per level, per WTP Unit building) as identified in Permit Condition III.10.F.1., Permit Tables III.10.F.A., engineering information as specified below, for incorporation, as appropriate, into Attachment 51, Appendices 8.1, 8.2, 8.3, 8.4 through 8.10, 8.13, 8.15, 9.1, 9.2, 9.4 through 9.10, 9.13, 9.18, 10.1, 10.2, 10.4 through 10.10, 10.13, and 10.18 of this Permit. At a minimum, engineering information specified below will show the following as required in accordance with WAC 173-303-695 (the information specified below will include dimensioned engineering drawings showing floors, walls, and ceilings/roof of the containment building units and other information on floor drains and sumps):
 - i. Design drawings (General Arrangement Drawings in plan and cross sections) and specifications for the foundation, containment, including liner/coating installation details and leak detection methodology, as appropriate [40 CFR 264.1101(a)(1) and (b), in accordance with WAC 173-303-695].
 - ii. The Permittees shall provide the design criteria (references to codes and standards, load definitions and load combinations, materials of construction, and analysis/design methodology) and typical design details for the support of the containment system. This information shall demonstrate the foundation will be capable of providing support to the secondary containment system, resistance to pressure gradients above and below the system, and capable of preventing failure due to settlement, compression, or uplift [40 CFR 264.1101(a)(2) in accordance with WAC 173-303-695, in accordance with WAC 173-303-695].
 - iii. The Permittees shall provide documentation addressing how coatings will withstand the movement of personnel, waste, and equipment during the operating life of the containment building per 40 CFR 264.1101(a)(2), (a)(4), and (b) in accordance with WAC 173-303-695.
 - iv. Containment/foundation and, as appropriate, for leak detection systems, materials selection documentation (including, but not limited to, concrete coatings and water stops, and liner materials as applicable [e.g. physical and chemical tolerances]) [40 CFR 264.1101(a)(4) and (b) in accordance with WAC 173-303-695].
 - v. A detailed description of how the containment/foundation and, as appropriate, leak detection systems, will be installed.

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 70 of 210

1 2 3		vi.	Submit Permit Tables III.10.F.B and III.10.F.C, completed to provide for all secondary containment sumps and floor drains, the information as specified in each column heading, consistent with the information to be provided in i. through viii.
 4 -5 6		vii.	A detailed description of how fugitive emissions will be controlled such that any openings (e.g., doors, windows, vents, cracks, etc.) exhibit no visible emissions [40 CFR 264.1101(c)(1)(iv) in accordance with WAC 173-303-695].
7 8 9		viii.	Prior to installation, the Permittees shall submit coating vendor information specific to containment buildings for incorporation into the Administrative Record [40 CFR 264.1101(a)(4) and (b) in accordance with WAC 173-303-695].
10 11 12		ix.,	Prior to installation, leak detection system documentation (e.g. vendor information, etc.) consistent with information submitted under i above, shall be submitted for incorporation into the Administrative Record;
13 14 15		X.	Prior to installation, the Permittees shall submit leak detection system instrumentation control logic narrative description (e.g., software functional specifications, descriptions of fail-safe conditions, etc.);
16 17 18		xi.	Prior to installation, system descriptions related to leak detection systems (including instrument control logic and narrative descriptions) shall be submitted for incorporation into the Administrative Record;
19 20 21 22		xii.	For leak detection system instrumentation for containment buildings as identified in Permit Tables III.10.F.D., a detailed description of how the leak detection system instrumentation will be installed and tested [40 CFR 264.1101(b)(3) in accordance with WAC 173-303-695] shall be submitted prior to installation.
23 24 25 26	III.10.F.7.d	subn infor	to initial receipt of dangerous and mixed waste, in the WTP Unit, the Permittees shall nit the following, as specified below, for incorporation into Attachment 51. The mation specified below into Attachment 51, and incorporated pursuant to Permit dition III.10.C.2.g. shall be followed:
 27 28 29 30		i. Sana Sana Sana Sana Sana Sana Sana San	Registered Professional Engineer certification documentation consistent with the information provided in III.10.F.7.b. and III.10.F.7.c. for incorporation in the Administrative Record. The certification must be maintained in the WTP Unit Operating Record [40 CFR 264.1101(c)(2)];
31 32 33 34 35			Updated Chapter 4.0, Section 4.2.1., and the figures for containment building units identified in Permit Table III.10.F.A. (as modified pursuant to Permit Condition III.10.F.7.d.iv., consistent with Attachment 51, Appendices 8.1, 8.2, 8.4 through 8.10, 8.13, 8.15, 9.1, 9.2, 9.4 through 9.10, 9.13, 9.18, 10.1, 10.2, 10.4 through 10.10, 10.13, and 10.18, as approved pursuant Permit Conditions III.10.F.7.a. through d.);
36 37	· ·	iii.	Description of operating procedures demonstrating compliance with 40 CFR 264.1101(c) and (d) in accordance with WAC 173-303-695;
38		iv.	Permit Table III.10.F.A., amended as follows:
39 40			A. Under column 1, update and complete list of dangerous and mixed waste containment building units including room location and number.
41			B. Under column 2, update unit dimensions.
42 43 44			C. Under column 3, replace the 'Reserved' with the Attachment 51, Appendices 8.0, 9.0, and 10.0, subsections specific to containment building units as listed in column 1.

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 71 of 210

1 2		D.	Under column 4, update and complete list of narrative description, tables, and figures.
3 4 5		E.	Under column 5, replace the 'Reserved' to indicate if container storage is used in each containment building units (Yes or No) consistent with Permit Table III.10.D.A. updated pursuant to Permit Condition III.10.D.10.d.
6	•	F.	Under column 6, replace the 'Reserved' to indicate if tank storage is used in each
7 8			containment building units (Yes or No) consistent with Permit Tables III. 10.E.A.D., updated pursuant to Permit Condition III.10.E.9.e.vi.
9		G.	Under column 7, replace the 'Reserved' with the maximum capacity for each
10	<i>;</i>	rejut 11	containment building unit, to include the container storage capacity specified in
11			Permit Table III. 10.D.A., tank capacity specified in Permit Tables III. 10.E.A-D.
12			and update the total capacity for the containment building units.
13		Н.	Under column 8, update the status of each containment building unit.
14	1.4%	v. Pern	nit Table III 10.F.D. shall be completed for Containment Building leak detection
15		syste	em instrumentation and parameters to provide the information as specified in each
16		colu	mn heading. Leak detection system monitors and instruments for critical systems
17		as st	pecified in Attachment 51, Appendix 2.0 and as updated pursuant to Permit
18			dition III.10.C.9.b. shall be addressed.
10			
19		-	
20			
	YYY 10 E E		
21			nation provided under Permit Condition III.10.F.7.d. must be consistent with
22			on provided pursuant to Permit Conditions III.10.F.7.a. through d., as approved by
23		Ecology.	
24			
25			

Permit Number: WA7890008967 Modification to Revision 7

Expiration Date: September 27, 2004 Page 72 of 210

Table III.10.F.A. - Containment Building Unit Description

Mixed Waste Containment Building Units & Systems	Dimensions (LxWxH) (in feet)	Unit Description	Narrative Description and Figures	Container Storage Areas ^b	Tank Systems ^e	Containment Building Capacity (cu ft)	Manage Free Liquids
Pretreatment Hot Cell Containment Building	414x54x46	RESERVED	Section 4.3.4 Fig. 4A-78	RESERVED	RESERVED	RESERVED	Yes
Pretreatment Maintenance Containment Building	(98x56x18) + (54x5x18) + (54x78x18) + (18x98x18)	RESERVED	Section 4.3.4 Fig. 4A-78	RESERVED	RESERVED	RESERVED	Yes
Pretreatment Air Filtration Containment Building	234x54x19	RESERVED	Section 4.3.4 Fig. 4A-80, -81	RESERVED	RESERVED	RESERVED	No
LAW LSM Gallery Containment Building	151x62x25	RESERVED	Section 4.3.4 Fig. 4A-83	RESERVED	RESERVED	RESERVED	Yes
ILAW Container Finishing Containment Building	98x31x25	RESERVED	Section 4.3.4 Fig. 4A-83	RESERVED	RESERVED	RESERVED	No
Law Vitrification Plant C3 Workshop Containment Building	35x40x20	RESERVED	Section 4.3.4 Fig. 4A-85	RESERVED	RESERVED	RESERVED	Yes
HLW Melters 1 and 2 Containment Buildings	35x107x49	RESERVED	Section 4.3.4 Fig. 4A-87	RESERVED	RESERVED	RESERVED	No
IHLW Container Weld Containment Building	140x18x48	RESERVED	Section 4.3.4 Fig. 4A-88	RESERVED	RESERVED	RESERVED	No
IHLW Container Decontamination Building	10x80x58	RESERVED	Section 4.3.4 Fig. 4A-88	RESERVED	RESERVED	RESERVED	No
HLW Vitrification Plant C3 Workshop Containment Building	30x27x19 + 33x15x19	RESERVED	Section 4.3.4 Fig.4A-89	RESERVED	RESERVED	RESERVED	No
HLW Air Filtration Containment Building	104x38x19	RESERVED	Section 4.3.4 Fig. 4A-88	RESERVED	RESERVED	RESERVED	No
HLW Drum Transfer Containment Building	220x10x10	RESERVED	Section 4.3.4 Fig. 4A-86	RESERVED	RESERVED	RESERVED	Yes
HLW Pour Tunnel No. 1 Containment Building	140x11x21	RESERVED	Section 4.3.4 Fig. 4A-86	RESERVED	RESERVED	RESERVED	<u>No</u>
HLW Pour Tunnel No. 2 Containment Building	140x11x21	RESERVED	Section 4.3.4 Fig. 4A-86	RESERVED	RESERVED	RESERVED	<u>No</u>

Containment Building Units include associated process systems and equipment

Requirements pertaining to the containers in the Containment Building Units are specified in Section III.10.D. of this Permit. Requirements pertaining to the tanks in the Containment Building Units are specified in Section III.10.E. of this Permit.

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 73 of 210

Modification to Revision 7

Expiration Date: September 27, 2004

Page 74 of 210

Table III.10.F.B. - Containment Building Primary^a Containment Sump Systems

Sump I.D.# & Room Location	Maximum Capacity (gallons)	Dimensions (feet) & Materials of Construction	Maximum Allowable Liquid Height (inches)	Secondary Containment Volume (gallons)	Unit Description Drawings#
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

^a Primary sumps are defined in Permit Section III.10.C, and must comply with dangerous waste tank system requirements for tanks as described in WAC-173-303-640.

5

Table III.10.F.C. - Containment Building Secondary Containment Systems Including Sumps and Floor Drains

Sump or Drain Line I.D.# & Room Location	Maximum Sump (gallons) or Drain Line (gallons per minute) Capacity	Sump Type/Nominal Operating Volume (gallons)	Sump or Drain Line Dimensions (inches) & Materials of Construction	Engineering (Drawing Nos., No.'s,	Specifications
PWD-SUMP-00026	73.5	Dry Sump ^a	30" Dia. By ~28" deep	24590-PTF	
P-0123 (Hot Cell, El. 0')			316L	-M6-PWD-P000	10
				-P1-P01T-P0001	- :
				-P1-P01T-P0009	
PWD-SUMP-00028	73.5	Dry Sump*	30" Dia. By ~28" deep	24590-PTF	:
P-0123 (Hot Cell, El. 0')			316L	-M6-PWD-P000	14
			·	-P1-P01T-P0001	
PWD-SUMP-00029	73.5	Dry Sump ^e	30" Dia. By ~28" deep	24590-PTF	
P-0123 (Hot Cell, El. 0')			316L	-M6-PWD-P000	14
				-P1-P01T-P0001	
				-P1-P01T-P0009	
PWD-SUMP-00032	73.5	Dry Sump [®]	30" Dia. By ~28" deep	24590-PTF	!
P-0123A (Maintenance		_	316L	-M6-PWD-P000	10
Cave, El. 0')			·	-P1-P01T-P0001	
				-P1-P01T-P0009	
PWD-SUMP-00033	73.5	Dry Sump ^a	30" Dia. By ~28" deep	24590-PTF	•
P-0123A (Maintenance			316L	-M6-PWD-P000	10
Cave, El. 0')				-P1-P01T-P0001	· · · · · · · · · · · · · · · · · · ·

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 75 of 210

				-P1-P01T-P0009
PWD-ZF-03000-S11B-06	939	N/A	6" Dia.	24590-PTF-M6-PWD-P0011
P-0123 (Hot Cell, El. 0')			316L	
PWD-ZF-03001-S11B-06	939	N/A	6" Dia.	24590-PTF-M6-PWD-P0011
P-0123 (Hot Cell, El. 0')			316L	
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

Table III.10.F.D - Containment Building Leak Detection System Instrumentation and Parameters

Containment Building Locator and Name (including P&ID)	Type of Leak Detection Instrument	Location of Leak Detection Instrument (Tag No.)	Leak Detection Instrument Range	Expected Range	Fail States	Leak Detection Instrument Accuracy	Leak Detection Instrument Calibration Method No. and Range
PWD-SUMP- 00026 P-0123 ^a	Radar	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED
PWD-SUMP- 00028 P-0123 ^a	Radar	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED
PWD-SUMP- 00029 P-0123 ^a	Radar	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED
PWD-SUMP- 00032 P-0123A ^a	Radar	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED
PWD-SUMP- 00033 P-0123A ^a	Radar	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

^aSump locator and name (including P&ID designator) is located on Permit Table III.10.F.C – Containment Building Secondary Containment Systems Including Sumps and Floor Drains.

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 76 of 210

1	III.10.G	PRETREATMENT PLANT MISCELLANEOUS UNIT SYSTEMS
2 3 4 5		For purposes of Permit Section III.10.G., where reference is made to WAC 173-303-640, the following substitutions apply: substitute the terms "Pretreatment Plant Miscellaneous Unit System(s)" for "tank system(s)," "miscellaneous unit(s)" for "tank(s)," "equipment" for "ancillary equipment," and "miscellaneous unit(s) or equipment of a Pretreatment Plant
6 7	III.10.G.1	Miscellaneous Unit System" for "component(s)" in accordance with WAC 173-303-680. Approved Waste and Storage Limits
8 9 10 11 12 13		The Permittees may process, in the Pretreatment Plant Miscellaneous Unit Systems listed in Permit Table III.10.G.A, as approved/modified pursuant to Permit Condition III.10.G.10, all dangerous and mixed waste listed in the Part A Forms, Attachment 51, Chapter 1.0 of this Permit, and in accordance with in the WAP, Attachment 51, Chapter 3.0 of this Permit, as approved pursuant to Permit Condition III.10.C.3. Total Pretreatment Plant Miscellaneous Unit dangerous and mixed waste storage at the Facility shall not exceed the limits specified in Permit Table III.10.G.A.
15 16 17 18 19 20 21	III.10.G.1.b.	The Permittees may process dangerous and mixed waste only in approved Pretreatment Plant Miscellaneous Unit Systems listed in Permit Table III.10.G.A in accordance with Permit Section III.10.G and in accordance with Attachment 51, Chapters 1.0 and 4.0 of this Permit, and Attachment 51, Appendices 8.1 through 8.15 of this Permit, as approved pursuant to Permit Conditions III.10.G.10.b. through e. The Permittees shall limit the total volume of wastes to quantities specified for the individual miscellaneous units listed in Permit Table III.10.G.A.
22 23 24 25 26	III.10.G.1.c.	The Permittees shall manage ignitable and reactive, and incompatible waste in accordance with WAC 173-303-395(1). Any Pretreatment Plant Miscellaneous Unit System specified in Permit Tables III.10.G.A and III.10.G.B in which ignitable, reactive or incompatible waste are managed shall meet the requirements specified in WAC 173-303-640(9) and (10), in accordance to WAC 173-303-680.
27 28 29 30	III.10.G.1.d.	The Permittees shall ensure all certifications required by specialists (e.g., independent, qualified, registered professional engineer; independent corrosion expert; independent, qualified installation inspector; etc.) use the following statement or equivalent pursuant to Permit Condition III.10.C.10:
31 32 33 34 35 36 37		"I, (Insert Name) have (choose one or more of the following: overseen, supervised, reviewed, and/or certified) a portion of the design or installation of a new miscellaneous unit system or component located at (address), and owned/operated by (name(s)). My duties were: (e.g., installation inspector, testing for tightness, etc.), for the following miscellaneous unit system components (e.g., the venting piping, etc.), as required by the Dangerous Waste Regulations, namely, WAC 173-303-640(3) (applicable paragraphs (i.e., (a) through (g)) in accordance with WAC 173-303-680).
38 39 40 41 42		"I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment."
43 44 45	III.10.G.1.e.	In all future narrative permit submittals, the Permittees shall include miscellaneous unit system names with the unit designation (e.g., Waste Feed Evaporator Separator Vessels are designated V11002A and V11002B, respectively).


Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 77 of 210

III.10.G.2. Miscellaneous Unit Systems Design and Construction [WAC 173-303-640, in accordance with WAC 173-303-680(2) and WAC 173-303-340]. III.10.G.2.a. The Permittees shall construct the Pretreatment Plant Miscellaneous Unit Systems identified in Permit Table III.10.G.A, as specified in Attachment 51, Appendices 8.1 through 8.14 of this Permit, as approved pursuant to Permit Conditions III.10.G.10.b., III.10.G.10.c., and III.10.G.10.b. III.10.G.10.c. and III.10.G.10.b. Miscellaneous Unit Systems identified in Permit Tables III.10.G.A and III.10.G.B, as specified in Attachment 51, Appendices 8.2, 8.4 through 8.14 of this Permit, as approved pursuant to Permit Conditions III.10.G.10.b., III.10.G.10.c., and III.10.G.10.d. III.10.G.2.c. Modifications to approved design, plans, and specifications in Attachment 51 of this Permit for the Pretreatment Plant Miscellaneous Unit Systems shall be allowed only in accordance with Permit Conditions III.10.C.2.c. and f., or III.10.C.2.g., III.10.C.9.d., e., and b. III.10.G.3 Miscellaneous Unit System Installation and Certification [WAC 173-303-640, in accordance with WAC 173-303-680(2) and (3), and WAC 173-303-340]. III.10.G.3.a. The Permittees must ensure that proper handling procedures are adhered to in order to reverned damage to Pretreatment Plant Miscellaneous Unit Systems during installation. Prior to covering, enclosing, or placing a new Pretreatment Plant Miscellaneous Unit System(s) or component(s) in use, an independent, qualified, registered professional engineer, either of whom is trained and experienced in the proper installation of similar systems or components, must inspect the system for the presence of any of the following items: i. Weld breaks; ii. Punctures; iii. Serapes of protective coatings; iv. Cracks; v. Corrosion; vi. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pre				
in Permit Table III.10.G.A, as specified in Attachment 51, Appendices 8.1 through 8.14 of this Permit, as approved pursuant to Permit Conditions III.10.G.10.b., III.10.G.10.c., and III.10.G.10.d. III.10.G.2.b. The Permittees shall construct secondary containment systems for the Pretreatment Plant Miscellaneous Unit Systems identified in Permit Tables III.10.G.A and III.10.G.B, as specified in Attachment 51, Appendices 8.2, 84 through 8.14 of this Permit, as approved pursuant to Permit Conditions III.10.G.10.b., III.10.G.10.c., and III.10.G.10.d. III.10.G.2.c. Modifications to approved design, plans, and specifications in Attachment 51 of this Permit for the Pretreatment Plant Miscellaneous Unit Systems shall be allowed only in accordance with Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g., III.10.C.9.d., e., and h. III.10.G.3. Miscellaneous Unit System Installation and Certification [WAC 173-303-640, in accordance with WAC 173-303-680(2) and (3), and WAC 173-303-340]. III.10.G.3.a. The Permittees must ensure that proper handling procedures are adhered to in order to prevent damage to Pretreatment Plant Miscellaneous Unit Systems of covering, enclosing, or placing a new Pretreatment Plant Miscellaneous Unit System(s) or component(s) in use, an independent, qualified, installation inspector or an inspect on the proper installation of similar systems or components, must inspect the system for the presence of any of the following items: i. Weld breaks; ii. Punctures; iii. Scrapes of protective coatings; iv. Cracks; v. Corrosion; vi. Other structural damage or inadequate construction/installation; vii. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-co			III.10.G.2	
III.10.G.2.b. The Permittees shall construct secondary containment systems for the Pretreatment Plant Miscellaneous Unit Systems identified in Permit Tables III.10.G.A and III.10.G.B, as specified in Attachment 51, Appendices 8.2, 8.4 through 8.14 of this Permit, as approved pursuant to Permit Conditions III.10.G.10.b, III.10.G.10.c., and III.10.G.10.d. III.10.G.2.c. Modifications to approved design, plans, and specifications in Attachment 51 of this Permit for the Pretreatment Plant Miscellaneous Unit Systems shall be allowed only in accordance with Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g., III.10.C.9.d., e., and h. III.10.G.3. Miscellaneous Unit System Installation and Certification [WAC 173-303-640, in accordance with WAC 173-303-680(2) and (3), and WAC 173-303-340]. III.10.G.3.a. The Permittees must ensure that proper handling procedures are adhered to in order to prevent damage to Pretreatment Plant Miscellaneous Unit Systems during installation. Prior to covering, enclosing, or placing a new Pretreatment Plant Miscellaneous Unit System(s) or component(s) in use, an independent, qualified, installation inspector or an independent, qualified, registered professional engineer, either of whom is trained and experienced in the proper installation of similar systems or components, must inspect the system for the presence of any of the following items: i. Weld breaks; ii. Punctures; iii. Scrapes of protective coatings; iv. Cracks; v. Corrosion; vi. Other structural damage or inadequate construction/installation; vii. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must be beachfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that			III.10.G.2.a.	in Permit Table III.10.G.A, as specified in Attachment 51, Appendices 8.1 through 8.14 of
Miscellaneous Unit Systems identified in Permit Tables III.10.G.A and III.10.G.B, as specified in Attachment 51, Appendices 8.2, 8.4 tarough 8.14 of this Permit, as approved pursuant to Permit Conditions III.10.G.10.b., III.10.G.10.c., and III.10.G.10.d. III.10.G.2.c. Modifications to approved design, plans, and specifications in Attachment 51 of this Permit for the Pretreatment Plant Miscellaneous Unit Systems shall be allowed only in accordance with Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g., III.10.C.9.d., e., and h. III.10.G.3 Miscellaneous Unit System Installation and Certification [WAC 173-303-640, in accordance with WAC 173-303-680(2) and (3), and WAC 173-303-340]. III.10.G.3.a. The Permittees must ensure that proper handling procedures are adhered to in order to prevent damage to Pretreatment Plant Miscellaneous Unit Systems during installation. Prior to covering, enclosing, or placing a new Pretreatment Plant Miscellaneous Unit System(s) or component(s) in use, an independent, qualified, registered professional engineer, either of whom is trained and experienced in the proper installation of similar systems or components, must inspect the system for the presence of any of the following items: i. Weld breaks; ii. Punctures; iii. Scrapes of protective coatings; iv. Cracks; iv. Cracks; iv. Cracks; v. Corrosion; vi. Other structural damage or inadequate construction/installation; vii. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully a				
for the Pretreatment Plant Miscellaneous Unit Systems shall be allowed only in accordance with Permit Conditions III.10.C.2.e. and f., or III.10.C.2.e., III.10.C.2.d., e., and h. III.10.G.3 Miscellaneous Unit System Installation and Certification [WAC 173-303-640, in accordance with WAC 173-303-680(2) and (3), and WAC 173-303-340]. III.10.G.3.a. The Permittees must ensure that proper handling procedures are adhered to in order to prevent damage to Pretreatment Plant Miscellaneous Unit Systems of component of in use, an independent, qualified, installation inspector or an independent, qualified, registered professional engineer, either of whom is trained and experienced in the proper installation of similar systems or components, must inspect the system for the presence of any of the following items: i. Weld breaks; ii. Punctures; iii. Scrapes of protective coatings; iv. Cracks; v. Corrosion; vi. Other structural damage or inadequate construction/installation; viii. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill material that is a non-corrosive, porous, homogeneous substance. The backfill material that is a non-corrosive, porous, homogeneous substance. The backfill material that is a non-corrosive, porous, homogeneous substance. The backfill material that is a non-corrosive, porous, homogeneous substance. The backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully and uniformly supported [WAC 173-303-640(3)(d), in accordance		8 9	III.10.G.2.b.	Miscellaneous Unit Systems identified in Permit Tables III.10.G.A and III.10.G.B, as specified in Attachment 51, Appendices 8.2, 8.4 through 8.14 of this Permit, as approved
with WAC 173-303-680(2) and (3), and WAC 173-303-340]. III.10.G.3.a. The Permittees must ensure that proper handling procedures are adhered to in order to prevent damage to Pretreatment Plant Miscellaneous Unit Systems during installation. Prior to covering, enclosing, or placing a new Pretreatment Plant Miscellaneous Unit System(s) or component(s) in use, an independent, qualified, installation inspector or an independent, qualified, registered professional engineer, either of whom is trained and experienced in the proper installation of similar systems or components, must inspect the system for the presence of any of the following items: i. Weld breaks; ii. Punctures; iii. Scrapes of protective coatings; iv. Cracks; v. Corrosion; vi. Other structural damage or inadequate construction/installation; vii. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully and uniformly supported [WAC 173-303-640(3)(d), in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.c. The Permittees must test for tightness all new Pretreatment Plant miscellaneous units and equipment, prior to being covered, enclosed, or placed into use. If the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the Pretreatment Plant Miscellaneous Units Systems being covered, enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance		12	III,10.G.2.c.	for the Pretreatment Plant Miscellaneous Unit Systems shall be allowed only in accordance
prevent damage to Pretreatment Plant Miscellaneous Unit Systems during installation. Prior to covering, enclosing, or placing a new Pretreatment Plant Miscellaneous Unit System(s) or component(s) in use, an independent, qualified, installation inspector or an independent, qualified, registered professional engineer, either of whom is trained and experienced in the proper installation of similar systems or components, must inspect the system for the presence of any of the following items: i. Weld breaks; ii. Punctures; iii. Scrapes of protective coatings; iv. Cracks; v. Corrosion; vi. Other structural damage or inadequate construction/installation; vii. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully and uniformly supported [WAC 173-303-640(3)(d), in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.c. The Permittees must test for tightness all new Pretreatment Plant miscellaneous units and equipment, prior to being covered, enclosed, or placed into use. If the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system sure to severed, enclosed, or placed into use [WAC 173-303-640(3)(e), in accordance			III.10.G.3	
iii Punctures; iii. Scrapes of protective coatings; iv. Cracks; v. Corrosion; vi. Other structural damage or inadequate construction/installation; vii. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must provide a back-fill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully and uniformly supported [WAC 173-303-640(3)(d), in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.c. The Permittees must test for tightness all new Pretreatment Plant miscellaneous units and equipment, prior to being covered, enclosed, or placed into use. If the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the Pretreatment Plant Miscellaneous Units Systems being covered, enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance	S.	17 18 19 20 21	III.10.G.3.a.	prevent damage to Pretreatment Plant Miscellaneous Unit Systems during installation. Prior to covering, enclosing, or placing a new Pretreatment Plant Miscellaneous Unit System(s) or component(s) in use, an independent, qualified, installation inspector or an independent, qualified, registered professional engineer, either of whom is trained and experienced in the proper installation of similar systems or components, must inspect the system for the
iii. Scrapes of protective coatings; iv. Cracks; v. Corrosion; vi. Other structural damage or inadequate construction/installation; vii. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully and uniformly supported [WAC 173-303-640(3)(d), in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.c. The Permittees must test for tightness all new Pretreatment Plant miscellaneous units and equipment, prior to being covered, enclosed, or placed into use. If the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the Pretreatment Plant Miscellaneous Units Systems being covered, enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance		23	·	i. Weld breaks;
v. Corrosion; vi. Other structural damage or inadequate construction/installation; vii. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully and uniformly supported [WAC 173-303-640(3)(d), in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.c. The Permittees must test for tightness all new Pretreatment Plant miscellaneous units and equipment, prior to being covered, enclosed, or placed into use. If the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the Pretreatment Plant Miscellaneous Units Systems being covered, enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance		24		ii Punctures;
v. Corrosion; vi. Other structural damage or inadequate construction/installation; vii. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully and uniformly supported [WAC 173-303-640(3)(d), in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.c. The Permittees must test for tightness all new Pretreatment Plant miscellaneous units and equipment, prior to being covered, enclosed, or placed into use. If the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the Pretreatment Plant Miscellaneous Units Systems being covered, enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance		25	1 · · ·	iii. Scrapes of protective coatings;
vi. Other structural damage or inadequate construction/installation; vii. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully and uniformly supported [WAC 173-303-640(3)(d), in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.c. The Permittees must test for tightness all new Pretreatment Plant miscellaneous units and equipment, prior to being covered, enclosed, or placed into use. If the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the Pretreatment Plant Miscellaneous Units Systems being covered, enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance		26		iv. Cracks;
vii. All discrepancies must be remedied before the Pretreatment Plant Miscellaneous Unit Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully and uniformly supported [WAC 173-303-640(3)(d), in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.c. The Permittees must test for tightness all new Pretreatment Plant miscellaneous units and equipment, prior to being covered, enclosed, or placed into use. If the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the Pretreatment Plant Miscellaneous Units Systems being covered, enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance		27	E. C.	v. Corrosion;
Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.b. For Pretreatment Plant Miscellaneous Unit Systems or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully and uniformly supported [WAC 173-303-640(3)(d), in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.c. The Permittees must test for tightness all new Pretreatment Plant miscellaneous units and equipment, prior to being covered, enclosed, or placed into use. If the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the Pretreatment Plant Miscellaneous Units Systems being covered, enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance		28		vi. Other structural damage or inadequate construction/installation;
underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully and uniformly supported [WAC 173-303-640(3)(d), in accordance with WAC 173-303-680(2) and (3)]. III.10.G.3.c. The Permittees must test for tightness all new Pretreatment Plant miscellaneous units and equipment, prior to being covered, enclosed, or placed into use. If the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the Pretreatment Plant Miscellaneous Units Systems being covered, enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance	,	30		Systems are covered, enclosed, or placed in use [WAC 173-303-640(3)(c) in
equipment, prior to being covered, enclosed, or placed into use. If the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the Pretreatment Plant Miscellaneous Units Systems being covered, enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance		33 34 35 36	III.10.G.3.b.	underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the miscellaneous unit and compacted to ensure that the miscellaneous unit and piping are fully and uniformly supported [WAC 173-303-640(3)(d),
		39 40 41 42	III.10.G.3.c.	equipment, prior to being covered, enclosed, or placed into use. If the Pretreatment Plant Miscellaneous Unit Systems are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the Pretreatment Plant Miscellaneous Units Systems being covered, enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance

Modification to Revision 7

Expiration Date: September 27, 2004


Page 78 of 210



Modification to Revision 7

Expiration Date: September 27, 2004


Page 79 of 210



Permit Number: WA7890008967 Modification to Revision 7

Expiration Date: September 27, 2004

Page 80 of 210




Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 81 of 210

systems [WAC 173-303-640(5)(c) and WAC 173-303-640(6), in accordance with WAC 173-303-680(2) and (3), WAC 173-303-320, and WAC 173-303-806(4)(i)(i)(B)]: 2 Immediately and safely stop the flow of dangerous and/or mixed waste into the 3 miscellaneous unit system or secondary containment system; 4 Determine the source of the dangerous and/or mixed waste; 5 ii. Remove the waste from the containment area in accordance with WAC 173-303-680(2) 6 iii. and (3), as specified in WAC 173-303-640(7)(b). The dangerous and/or mixed waste 7 removed from containment areas of miscellaneous unit systems shall be, as a minimum, 8 managed as dangerous and/or mixed waste; 9 If the cause of the release was a spill that has not damaged the integrity of the 10 miscellaneous unit system, the Permittees may return the miscellaneous unit system to 11 service in accordance with WAC 173-303-680(2) and (3), as specified in WAC 173-12 303-640(7)(e)(ii). In such a case, the Permittees shall take action to ensure the incident 13 that caused liquid to enter the containment system will not reoccur [WAC 173-303-14 15 320(3)]; If the source of the dangerous and/or mixed waste is determined to be a leak from a the 16 primary Pretreatment Plant Miscellaneous Unit System into the secondary containment 17 system, or the system is unfit for use as determined through an integrity assessment or 18 other inspection, the Permittees must comply with the requirements of WAC 173-303-19 640(7), and take the following actions: 20 Close the miscellaneous unit following procedures in WAC 173-303-640(7)(e)(i) 21 and in accordance with WAC 173-303-680, and Attachment 51, Chapter 11.0 of 22 this Permit, as approved pursuant to Permit Condition III.10.C.8; or 23 Repair and re-certify (in accordance with WAC 173-303-810(13)(a), as modified 24 pursuant to Permit Condition III.10.G.1.d.) the Pretreatment Plant Miscellaneous 25 Unit System in accordance with Attachment 51, Appendix 8.15 of this Permit, as 26 approved pursuant to Permit Condition III.10.G.10.e.v. before the Pretreatment 27 Plant Miscellaneous Unit System is placed back into service [WAC 173-303-28 640(7)(e)(iii) and WAC 173-303-640(7)(f), in accordance with WAC 173-303-29 30 680]. The Permittees shall document, in the operating record, actions/procedures taken to 31 comply with i. through v. above, as specified in WAC 173-303-640(6)(d) and in 32 accordance with WAC 173-303-680(2) and (3). 33 vii. In accordance with WAC 173-303-680(2) and (3), the Permittees shall notify and 34 report releases to the environment to Ecology as specified in WAC 173-303-640(7)(d). 35 III.10.G.5.k. If liquids (e.g., Dangerous and/or mixed waste leaks and spills, precipitation, fire water, 36 liquids from damaged or broken pipes) cannot be removed from the secondary containment 37 system within twenty-four (24) hours, Ecology will be verbally notified within twenty-four 38 (24) hours of discovery. The notification shall provide the information in A., B., and C. 39 listed below. The Permittees shall provide Ecology with a written demonstration, within 40 seven (7) business days, identifying at a minimum [WAC 173-303-640(4)(c)(iv) and WAC 41 173-303-640(7)(b)(ii), in accordance with WAC 173-303-680(3) and WAC 173-303-42 806(4)(i)(i)(B)]: 43 A. Reasons for delayed removal; 44

Modification to Revision 7

Expiration Date: September 27, 2004


Page 82 of 210



Modification to Revision 7

Expiration Date: September 27, 2004

Page 83 of 210



Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 84 of 210

	1 2 3 4 5			specifications, etc.) already included in Attachment 51, Appendix 8.0 of this Permit may be included in the report by reference and should include drawing and document numbers. IQRPE Reports shall be consistent with the information separately provided in ii. through ix. below [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)];
	6 7 8 9 10 11 12 13 14	*	ii.	Design drawings (General Arrangement Drawings, in plan and cross sections) and specifications for the foundation, secondary containment, including, liner installation details, and leak detection methodology [Note: leak detection systems for areas where daily, direct, or remote visual inspection is not feasible, shall be continuous in accordance with WAC 173-303-640(4)(e)(iii)(C)]. These items should show the dimensions, volume calculations, and location of the secondary containment system, and should include items such as floor/pipe slopes to sumps, tanks, floor drains [WAC 173-303-640(4)(b) through (f) and WAC 173-303-640(3)(a), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)];
	15 16 17 18 19 20 21 22		iii.	The Permittees shall provide the design criteria (references to codes and standards, load definitions, and load combinations, materials of construction, and analysis/design methodology) and typical design details for the support of the secondary containment system. This information shall demonstrate the foundation will be capable of providing support to the secondary containment system, resistance to pressure gradients above and below the system, and capable of preventing failure due to settlement, compression, or uplift [WAC 173-303-640(4)(c)(ii), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(B)];
	23 24 25 26		iv.	A description of materials and equipment used to provide corrosion protection for external metal components in contact with soil, including factors affecting the potential for corrosion [WAC 173-303-640(3)(a)(iii)(B), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(A) through (B)];
	27 28 29		v.	Secondary containment/foundation and leak detection systems materials selection documentation (including, but not limited to, concrete coatings and water stops, and liner materials), as applicable [WAC 173-303-806(4)(i)(i)(A) through (B)];
	30 31 32		vi.	Detailed description of how the secondary containment for each miscellaneous unit system will be installed in compliance with WAC 173-303-640(3)(c), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(A) through (B);
À.,	33 34 35		vii.	Submit Permit Table III.10.G.B. completed to provide for all secondary containment sumps and floor drains, the information as specified in each column heading, consistent with information to be provided in i. through vi. above;
	36 37 38 39		viii.	Documentation that secondary containment and leak detection systems will not accumulate hydrogen gas levels above the lower explosive limit for incorporation into the Administrative Record [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A), and WAC 173-303-806(4)(i)(v)];
•	40 41 42		ix.	A detailed description of how miscellaneous unit design provides access for conducting future miscellaneous unit integrity assessments [WAC 173-303-640(3)(b) and WAC 173-303-806(4)(i)(i)(B)].
	43. 44 45 46 47	Ш.10.G.10.с.	insta Tabl inco	Permittees shall submit to Ecology, pursuant to Permit Condition III.10.C.9.f., prior to allation of each Pretreatment Plant Miscellaneous Unit System as identified in Permit les III.10.G.A and III.10.G.B, engineering information as specified below, for proration into Attachment 51, Appendix 8.1 through 8.14 of this Permit. At a imum, engineering information specified below will show the following as required

Modification to Revision 7

Expiration Date: September 27, 2004

Page 85 of 210


pursuant to WAC 173-303-640 and in accordance with WAC 173-303-680 (the information 1 specified below will include dimensioned engineering drawings): IQRPE Reports (specific to miscellaneous unit) shall include review of design 3 drawings, calculations, and other information on which the certification report is based 4 and shall include as applicable, but not limited to, review of such information described below. Information (drawings, specifications, etc.) already included in 6 Attachment 51, Appendix 8.0 of this Permit may be included in the report by reference 7 and should include drawing and document numbers. The IQRPE Reports shall be consistent with the information separately provided in ii. through xi. below and the IQRPE Report specified in Permit Condition III.10.G.10.b.i. [WAC 173-303-10 640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)]; .11 Design drawings (General Arrangement Drawings in plan and cross sections, Process 12 Flow Diagrams, Piping and Instrumentation Diagrams [including pressure control 13 systems], and Mechanical Drawings) and specifications, and other information 14 specific to miscellaneous units (to show location and physical attributes of each 15 miscellaneous unit), [WAC 173-303-640(3)(a), in accordance with WAC 173-303-16 680(2) and WAC 173-303-806(4)(i)(i)]; 17 Miscellaneous unit design criteria (references to codes and standards, load definitions, 18 and load combinations, materials of construction, and analysis/design methodology) 19 and typical design details for the support of the miscellaneous unit(s). Structural 20 support calculations specific to off-specification, non-standard, and field fabricated 21 miscellaneous units shall be submitted for incorporation into the Administrative 22 Record [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and 23 WAC 173-303-806(4)(i)(i)(B)]; 24 A description of materials and equipment used to provide corrosion protection for 25 external metal components in contact with water, including factors affecting the 26 potential for corrosion [WAC 173-303-640(3)(a)(iii)(B), in accordance with WAC 27 173-303-680(2) and WAC 173-303-806(4)(i)(i)(A) through (B)]; 28 Miscellaneous unit materials selection documentation (e.g., physical and chemical 29 tolerances) [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and -30 31 WAC 173-303-806(4)(i)(i)(A)]; Miscellaneous unit vendor information (including, but not limited to, required 32 performance warranties, as available), consistent with information submitted under ii. 33 above, shall be submitted for incorporation into the Administrative Record [WAC 34 173-303-640(3)(a), in accordance with WAC 173-303-680(2), WAC 173-303-35 806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(v)]; 36 vii. System Description (process) related to miscellaneous units shall be submitted for 37 incorporation into the Administrative Record [WAC 173-303-680, WAC 173-303-38 806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(v)]. 39 viii. Mass and energy balance for normal projected operating conditions used in 40 developing the Piping and Instrumentation Diagrams and the Process Flow Diagrams, 41 including assumptions and formulas used to complete the mass and energy balance, so 42 that they can be independently verified for incorporation into the Administrative 43 Record [WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-44

45

806(4)(i)(v);

Modification to Revision 7
Expiration Date: September 27, 2004


Page 86 of 210



Modification to Revision 7

Expiration Date: September 27, 2004

Page 87 of 210



Permit Number: WA7890008967 Modification to Revision 7

Expiration Date: September 27, 2004 Page 88 of 210

	1 2 3		integrity assessments, age of the system, materials of construction, characteristics of the waste, and any other relevant factors [WAC 173-303-640(3)(b), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(B)];
	4	ii.	
	6		structure or the presence of any release of dangerous and/or mixed waste or
	7 8		accumulated liquid in the secondary containment system within twenty-four (24) hours WAC 173-303-640(4)(c)(iii). Detection of a leak of at least 0.1 gallons per hour
	9		within twenty-four (24) hours is defined as being able to detect a leak within twenty-
	10 11		four (24) hours. Any exceptions to this criteria must be approved by Ecology in accordance with WAC 173-303-680, WAC 173-303-640(4)(c)(iii), and WAC 173-
	12		303-806(4)(i)(i)(B)];
	13 14	iii	Detailed operational plans and descriptions, demonstrating that spilled or leaked waste and accumulated liquids can be removed from the secondary containment system
	15	A STATE OF THE STA	within twenty-four (24) hours [WAC 173-303-806(4)(i)(i)(B)];
•	16	iv	Descriptions of operational procedures demonstrating appropriate controls and
	17 18		practices are in place to prevent spills and overflows from the Pretreatment Plant Miscellaneous Unit Systems, or containment systems, in compliance with WAC 173-
	19		303-640(5)(b)(i) through (iii), in accordance with WAC 173-303-680 [WAC 173-303-
	20		806(4)(i)(i)(B)];
	· 21	v.	Description of procedures for investigation and repair of the Pretreatment Plant Miscellaneous Unit Systems [WAC 173-303-640(6) and WAC 173-303-640(7)(e) and
	23		(f), in accordance with WAC 173-303-680, WAC 173-303-320, WAC 173-303-806(4)(a)(v), and WAC 173-303-806(4)(i)(i)(B)];
	24 25	vi	
	26	V1	Permit Tables III.10.G.A and III.10.G.B., as modified pursuant to Permit Condition
	27 28		III.10.G.10.e.ix., and updated to identify routinely non-accessible Pretreatment Plant Miscellaneous Unit Systems [WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(A)
	29		through (B)];
	30	vi	
	31 32		incompatible dangerous and/or mixed waste, in accordance with WAC 173-303-640(9) and (10), in accordance with WAC 173-303-680 and WAC 173-303-
	33		806(4)(i)(i)(B).
	34 35	γĬ	i. A description of the tracking system used to track dangerous and/or mixed waste generated throughout the Pretreatment Plant Miscellaneous Unit Systems, pursuant to
	36		WAC 173-303-380.
	37 38	ix	Permit Table III.10.G.A, amended as follows [WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(A) through (B)]:
	39 40 41		A. Under column 1, update and complete list of dangerous and mixed waste Pretreatment Plant Miscellaneous Unit Systems, including plant items which comprise each system (listed by item number).
	42		B. Under column 2, update and complete system designations.
	43 44		C. Under column 3, replace the 'Reserved' with the Attachment 51, Appendix 8.0 subsections specific to miscellaneous unit systems as listed in column 1.
	45	. 7 	D. Under column 4, update and complete list of narrative description tables and

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 89 of 210

1			ngures.
2			E. Under column 5, update and complete maximum capacity for each miscellaneou unit, as applicable.
4	·		F. Permit Table III.10.G.A.i., amended as follows:
5 6			 Under column 1, update and complete list of plant items that comprise the Pretreatment Plant Vessel Vent System (listed by item number).
7			2. Under column 2, update and complete designations.
8	•		3. Under column 3, replace the 'Reserved' with the Attachment 51, Appendix 8.0, subsections (e.g., 9.1, 9.2, etc.) specific to systems as listed in column 1
10 11		en Property Property	 Under column 4, update and complete list of narrative description tables and figures.
12 13 14 15 16 17 18 19 20 21 22 23		xi.	Permit Table III.10 G.C. shall be completed for Pretreatment Plant Miscellaneous Un System process and leak detection system monitors and instruments (to include, but not be limited to: instruments and monitors measuring and/or controlling flow, pressure, temperature, density, pH, level, humidity, and emissions) to provide the information as specified in each column heading. Process and leak detection system monitors and instruments for critical systems as specified in Attachment 51, Appendi 2.0 and as updated pursuant to Permit Condition III.10.C.9.b.and for operating parameters as required to comply with Permit Condition III.10.C.3.e.iii. shall be addressed. Process monitors and instruments for non-waste management operations (e.g., utilities, raw chemical storage, non-contact cooling waters, etc.) are excluded from this permit condition [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(v)]; Supporting documentation for operating trips and expected operating range as
25 26 27		XI.	supporting documentation for operating trips and expected operating range as specified in Permit Table III.10.G.C., as approved pursuant to Permit Condition III.10.G.10.e.x. [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(B), WAC 173-303-806(4)(i)(iv), and WAC 173-303-806(4)(i)(v)];
28 29 30 31		xii.	Documentation of process and leak detection instruments and monitors (as listed in Permit Table III.10.G.C.) for the Pretreatment Plant Miscellaneous Unit Systems to include, but not be limited to, the following [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-806(4)(i)(v)]:
32	enga e s	•	A. Procurement Specifications
33		· .	B. Location used
.34			C. Range, precision, and accuracy
35 36 37			D. Detailed descriptions of calibration/functionality test procedures (e.g., method number [ASTM]) or provide a copy of manufacturer's recommended calibration procedures.
38 39 40 41 42 43			E. Calibration/functionality test, inspection, and routine maintenance schedules and checklists, including justification for calibration, inspection and maintenance frequencies, criteria for identifying instruments found to be significantly out of calibration, and corrective action to be taken for instruments found to be significantly out of calibration (e.g., increasing frequency of calibration, instrument replacement, etc.)

Expiration Date: September 27, 2004

Page 90 of 210

F. Equipment instrument control logic narrative description (e.g., software functional specifications, descriptions of fail-safe conditions, etc.) [WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-806(4)(i)(v)].

Modification to Revision 7

Expiration Date: September 27, 2004

Page 91 of 210

Table III.10.G.A – Pretreatment Plant Miscellaneous Unit Systems

Miscellaneous Unit System Description ^a	Miscellaneous Unit System Designation	Description Drawings	Narrative Description, Tables, & Figures	Maximum Capacity (gallons)
Waste Feed Evaporation Process System (Comprised of the following miscellaneous units and equipment: Evaporator Feed Vessels V11001A-B ^b , Waste Feed Evaporator Separator Vessels V11002A-B, Evaporator Process Condensate Pot V11005 ^b , Reboilers, Primary Condensers, Intercondensers, After condensers, Demisters, and Pumps and associated equipment)	FEP	RESERVED	Section 4.1.2.2.; Figure 4A-1, 4A-2, and 4A-6 of Attachment 51, Chapter 4 of this Permit.	V11002A = 21,240 V11002B = 21,240
Cesium Nitric Acid Recovery Process System (Comprised of the following miscellaneous units and equipment: Cs Evaporator (ID RESERVED), Cs Concentrate Reboiler, Eluant Contingency Storage Vessel V13073 ^b , Recovered Nitric Acid Vessel V13028 ^b , Cesium Concentrate Lute Pot V13030 ^b , Cs Rectifier Column, Rectifier Overhead Primary Condenser, After (Secondary) condenser, and Ejectors and associated equipment)	CNP	RESERVED	Section 4.1.2.6.; Figure 4A-1, 4A-2, and 4A-10 of Attachment 51, Chapter 4 of this Permit	Cs Evaporator = RESERVED
Technetium Eluant Recovery Process System (Comprised of the following miscellaneous units and equipment: Technetium Eluant Recovery Evaporator V43069, Tc Concentrate Reboiler, Recovered Tc Eluant Vessel V43071 ^b , Tc Concentrate Lute Pot V43072 ^b , Tc Rectifier Column, Rectifier Overhead Condenser, Aftercondenser, Vacuum Ejectors and associated equipment)	ТЕР	RESERVED	Section 4.1.2.9.; Figure 4A-1, 4A-2, and 4A-13 of Attachment 51, Chapter 4 of this Permit	V43069 = 4,300
Treated LAW Evaporation Process System (Comprised of the following miscellaneous units and equipment: LAW Evaporator Separator Vessel V41011, Process Condensate Hold Vessel V41013 ^b , Plant Wash Vessels A-B V45009A-B ^b , Reboiler, Primary Condenser, Intercondenser, Aftercondenser, Demister, Pumps and associated equipment)	TLP	RESERVED	Section 4.1.2.11; Figure 4A-1, 4A-2, and 4A-16 of Attachment 51, Chapter 4 of this Permit	V41011 = 21,240

^a The Pretreatment Vessel Vent Process System specified in Permit Table III.10.G.A.i is shared between the Pretreatment Plant Miscellaneous Unit Systems. Any references in this Permit to the individual Pretreatment Plant Miscellaneous Unit Systems are also a reference to the Pretreatment Vessel Vent Process System. Any reference in this Permit to Permit Table III.10.G.A.i.

^b Requirements pertaining to the tanks in the Pretreatment Plant Miscellaneous Unit Systems are specified in Section III.10.E. of this Permit.

Expiration Date: September 27, 2004

Page 92 of 210

Table III.10.G.A.i. – Pretreatment Plant Miscellaneous Unit Systems' Pretreatment Vessel Vent Process System

Description	Designation Description Drawings		Narrative Description, Tables & Figures			
Pretreatment Vessel Vent Process System (Comprised of the	PVP/PVV	RESERVED	Section 4.1.2.17; Figure 4A-1, 4A-2, and 4A-19 of			
following: Vessel Vent Header Collection Vessel V15052 ^b ,			Attachment 51, Chapter 4 of this Permit			
Condensate Collection Vessel V15038 ^b , Caustic scrubber, High		•				
Efficiency Mist Eliminators (HEME), HEME Drain Collection						
Vessels V15326-7 ^b , Electric Heaters, Primary & Secondary						
High Efficiency Particulate Air Filters (HEPA), Heat						
Exchanger, Thermal Catalytic Oxidizer, Aftercooler, Carbon		•				
Bed Adsorbere, Vessel Vent Adsorber Outlet Filter, Vessel Vent						
Adsorber Outlet Air Filter, Pumps, Fans, Vessel Vent Heaters,						
Pumps, PVP Stack and associated equipment)		, !				

^a The Pretreatment Vessel Vent Process System specified in Permit Table III.10.G.A.i is shared between the Pretreatment Plant Miscellaneous Unit Systems. Any references in this Permit to the individual Pretreatment Plant Miscellaneous Unit Systems are also a reference to the Pretreatment Vessel Vent Process System. Any reference in this Permit to Permit Table III.10.G.A is also a reference to Permit Table III.10.G.A.i.

^b Requirements pertaining to the tanks in the Pretreatment Plant Miscellaneous Unit Systems are specified in Section III.10.E. of this Permit.

Modification to Revision 7
Expiration Date: September 27, 2004
Page 93 of 210

Table III.10.G.B. - Pretreatment Plant Miscellaneous Unit Secondary Containment **Systems Including Sumps and Floor Drains**

Sump/Floor Drain I.D.# & Room Location	Maximum Sump Capacity (gallons)	Sump Dimensions (feet) & Materials of Construction	Description Drawings#
RESERVED	RESERVED	RESERVED	RESERVED

Table III.10.G.C. - Pretreatment Plant Miscellaneous Unit System Process and Leak Detection Instruments and Parameters

Miscellaneous Unit System Locator and Name (including P&ID)	Control Parameter	Type of Measuring or Leak Detection Instrument	Location of Measuring Instrument (Tag No.)	Instrument Range	Failure State	Expected Range	Instrument Accuracy	Operating Trips (Description & Numerical Limits)	Instrument Calibration Method No. and Range
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

Modification to Revision 7

Expiration Date: September 27, 2004

Page 94 of 210

Table III.10.G.D. – Pretreatment Plant Miscellaneous Unit Systems Estimated Emission Rates

	Chemicals	CAS Number	Emission Rates (grams /second)
	RESERVED	RESERVED	RESERVED
Ш.10.		system – Short Term Miscellaneous and Post Demonstration Test	Thermal Treatment Unit-Shakedown,
	following substitution system(s)," "sub-system(s)," and "su	onit Section III.10.H, where reference ons apply: substituting the terms "Latem(s)" for "tank(s)," "sub-system ob-system(s) or sub-system equipme in accordance with WAC 173-303-6	equipment" for "ancillary nt of a LAW Vitrification System"
III.10.	H.1. General Conditions for LAW Vitrification	During Shakedown, Demonstration on System	Test, and Post-Demonstration Test
III.10.	H.1.a. Construction and Ma 680(2) and (3), and	aintenance [WAC 173-303-640, in a WAC 173-303-340].	accordance with WAC 173-303-
144 1,347	III.10.H.A ar specified in F Permit, and A	es shall construct the LAW Vitrificand B., as approved/modified pursuant Permit Condition III.10.H.1. and Att Attachment 51, Appendices 9.1 throusuant to Permit Conditions III.10.H.	igh 9.15 and 9.17 of this Permit, as
	System as sp Appendices 9	es shall construct all containment sy ecified in Attachment 51, Chapter 4 0.2 and 9.4 through 9.14 of this Pern I.10.H.5.a. through d.	0 of this Permit, and Attachment 51,
	qualified regi qualified inst		nired by specialists (e.g., independent, endent corrosion expert, independent, wing statement or equivalent
		me) have (choose one or more of the	

reviewed, and/or certified) a portion of the design or installation of a new LAW

Vitrification System or component located at (address), and owned/operated by

(name(s)). My duties were: (e.g., installation inspector, testing for tightness, etc.), for

the following LAW Vitrification System components (e.g., the venting piping, etc.), as

Modification to Revision 7

Expiration Date: September 27, 2004

Page 95 of 210

required by the Dangerous Waste Regulations, namely, WAC 173-303-640(3) (applicable paragraphs (i.e., (a) through (g)) in accordance with WAC 173-303-680). 3 "I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my 4 inquiry of those individuals immediately responsible for obtaining the information, I 5 believe that the information is true, accurate, and complete. I am aware that there are 6 significant penalties for submitting false information, including the possibility of fine 7 and imprisonment." 8 The Permittees must ensure that proper handling procedures are adhered to in order to 9 prevent damage to the LAW Vitrification System during installation. Prior to 10 covering, enclosing, or placing the new LAW Vitrification System or component in 11 use, an independent, qualified, installation inspector or an independent, qualified, 12 registered professional engineer, either of whom is trained and experienced in the 13 proper installation of similar systems or components, must inspect the system for the 14 presence of any of the following items: 15 Weld breaks; 16 B. Punctures: 17 C. Scrapes of protective coatings; 18 19 D. Cracks; Ε. Corrosion: 20 F. Other structural damage or inadequate construction/installation. 21 All discrepancies must be remedied before the LAW Vitrification System is covered, 22 enclosed, or placed in use [WAC 173-303-640(3)(c), in accordance with WAC 173-23 24 303-680(2) and (3)]. For the LAW Vitrification System or components that are placed underground and 25 that are back-filled, the Permittees must provide a backfill material that is a non-26 corrosive, porous, homogeneous substance. The backfill must be installed so that it is 27 placed completely around the LAW Vitrification System and compacted to ensure that 28 the LAW Vitrification System is fully and uniformly supported [WAC 173-303-29 640(3)(d), in accordance with WAC 173-303-680(2) and (3)]. 30 The Permittees must test for tightness the LAW Vitrification System or components, 31 prior to being covered, enclosed, or placed into use. If the LAW Vitrification System 32 or components are found not to be tight, all repairs necessary to remedy the leak(s) in 33 the system must be performed prior to the LAW Vitrification System being covered, 34 enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance with WAC 173-35 303-680(2) and (3)1. 36 The Permittees must ensure the LAW Vitrification System equipment is supported and 37 vii. 38 protected against physical damage and excessive stress due to settlement, vibration, expansion, or contraction [WAC 173-303-640(3)(f), in accordance with WAC 173-39 303-680(2) and (3)]. 40

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 96 of 210

1 2	viii.	The Permittees must provide the type and degree of corrosion protection recommended by an independent corrosion expert, based on the information provided
3 4 5 6 7 8 9 10		in Attachment 51, Appendices 9.9 and 9.11 of this Permit, as approved pursuant to Permit Conditions III.10.H.5.b.i., III.10.H.5.b.iv., III.10.H.5.b.v., III.10.H.5.c.i., III.10.H.5.c.iv., III.10.H.5.c.iv., III.10.H.5.c.iv., III.10.H.5.d.iv., and III.10.H.5.d.v., or other corrosion protection if Ecology believes other corrosion protection is necessary to ensure the integrity of the LAW Vitrification System during use of the LAW Vitrification System. The installation of a corrosion protection system that is field fabricated must be supervised by an independent corrosion expert to ensure proper installation [WAC 173-303-640(3)(g), in accordance with WAC 173-303-680(2) and (3)].
12 13 14 15 16 17 18 19 20 21 22	ix.	Prior to initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees shall obtain and keep on file in the WTP Unit operating record, written statements by those persons required to certify the design of the LAW Vitrification System and supervise the installation of the LAW Vitrification System, as specified in WAC 173-303-640(3)(b), (c), (d), (e), (f), and (g), in accordance with WAC 173-303-680, attesting that the LAW Vitrification System and corresponding containment system listed in Permit Tables III.10.H.A and III.10.H.B, as approved/modified pursuant to Permit Condition III.10.H.5., were properly designed and installed, and that repairs, in accordance with WAC 173-303-640(3)(c) and (e) were performed [WAC 173-303-640(3)(a) and WAC 173-303-640(3)(h), in accordance with WAC 173-303-680(3)].
23 24 25 26 27 28	X.	The independent LAW Vitrification System installation inspection and subsequent written statements shall be certified in accordance with WAC 173-303-810(13)(a), as modified pursuant to Permit Condition III.10.H.1.a.iii., comply with all requirements of WAC 173-303-640(3)(h) in accordance with WAC 173-303-680, and shall consider, but not be limited to, the following LAW Vitrification System installation documentation:
29		A. Field installation report with date of installation;
30	and the second of the second o	B. Approved welding procedures;
31		C. Welder qualification and certifications;
32 33 34 35		 D. Hydro-test reports, as applicable, in accordance with the American Society of Mechanical Engineers Boiler and Pressure Vessel Code, Section VIII, Division 1; American Petroleum Institute (API) Standard 620, or Standard 650, as applicable;
36		E. Tester credentials;
37		F. Field inspector credentials;
38		G. Field inspector reports;
39		H. Field waiver reports: and

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 97 of 210

Non-compliance reports and corrective action (including field waiver reports)

2		and repair reports.
3 4 5 6 7 8 9 10	xi.	The Permittees shall ensure periodic integrity assessments are conducted on the LAW Vitrification System, listed in Permit Table III.10.H.A, as approved/modified pursuant to Permit Condition III.10.H.5., over the term of this Permit in accordance with WAC 173-303-680(2) and (3) as specified in WAC 173-303-640(3)(b), following the description of the integrity assessment program and schedule in Attachment 51, Chapter 6.0 of this Permit, as approved pursuant to Permit Conditions III.10.H.5.e.i. and III.10.C.5.c. Results of the integrity assessments shall be included in the WTP Unit operating record until ten (10) years after post-closure, or corrective action is complete and certified, whichever is later.
12 13 14 15	xii.	The Permittees shall address problems detected during the LAW Vitrification System integrity assessments specified in Permit Condition III.10.H.1.a.xi. following the integrity assessment program in Attachment 51, Chapter 6.0 of this Permit, as approved pursuant to Permit Conditions III.10.H.5.e.i. and III.10.C.5.c.
16 17 18 19	xiii.	All process monitors/instruments, as specified in Permit Table III.10.H.F, as approved/modified pursuant to Permit Condition III.10.H.5., shall be equipped with operational alarms to warn of deviation, or imminent deviation from the limits specified in Permit Table III.10.H.F.
20 21 22 23 24	xiv.	The Permittees shall install and test all process and leak detection system monitors/instrumentation as specified in Permit Tables III.10.H.C and III.10.H.F, as approved/modified pursuant to Permit Condition III.10,H.5, in accordance with Attachment 51, Appendices 9.1, 9.2, and 9.14 of this Permit, as approved pursuant to Permit Conditions III.10.H.5.d.x. and III.10.H.5.f.xvi.
25 26 27 28 29 30 31 32 33 34	XVI.	No dangerous and/or mixed waste shall be treated in the LAW Vitrification System unless the operating conditions, specified under Permit Condition III.10.H.1.c. are complied with. The Permittees shall not place dangerous and/or mixed waste, treatment reagents, or other materials in the LAW Vitrification System if these substances could cause the subsystem, subsystem equipment, or the containment system to rupture, leak, corrode, or otherwise fail [WAC 173-303-640(5)(a), in accordance with WAC 173-303-680(2)]. This condition is not applicable to corrosion of LAW Vitrification System sub-system or sub-system equipment that are expected to be replaced as part of normal operations (e.g., melters).
35 36 37 38 39 40	xvii.	The Permittees shall operate the LAW Vitrification System to prevent spills and overflows using controls and practices as required under WAC 173-303-640(5)(b) described in Permit Condition III.10.C.5 and Attachment 51, Appendix 9.18 of this Permit, as approved pursuant to Permit Condition III.10.H.5.e. [WAC 173-303-640(5)(b), in accordance with WAC 173-303-680(2) and (3), and WAC 173-303-806(4)(c)(ix)].

I.

Expiration Date: September 27, 2004

Page 98 of 210

xviii. For routinely non-accessible LAW Vitrification System sub-systems, as specified in Attachment 51, Chapter 4.0 of this Permit, as updated pursuant to Permit Condition III.10.H.5.e.vi., the Permittees shall mark all routinely non-accessible LAW Vitrification System sub-systems access points with labels, or signs, to identify the waste contained in each LAW Vitrification System sub-system. The label, or sign, must be legible at a distance of at least fifty (50) feet, and must bear a legend which identifies the waste in a manner which adequately warns employees, emergency response personnel, and the public of the major risk(s) associated with the waste being stored or treated in the LAW Vitrification System sub-systems. For the purposes of this permit condition, "routinely non-accessible" means personnel are unable to enter these areas while waste is being managed in them [WAC 173-303-640(5)(d), in accordance with WAC 173-303-680(2)].

xix. For all LAW Vitrification System sub-systems not addressed in Permit Condition III.10.H.1.a.xviii., the Permittees shall mark all these LAW Vitrification System sub-

.13

- xix. For all LAW Vitrification System sub-systems not addressed in Permit Condition III.10.H.1.a.xviii., the Permittees shall mark all these LAW Vitrification System sub-systems holding dangerous and/or mixed waste with labels, or signs, to identify the waste contained in the LAW Vitrification System sub-systems. The labels, or signs, must be legible at a distance of at least fifty (50) feet, and must bear a legend which identifies the waste in a manner which adequately warns employees, emergency response personnel, and the public of the major risk(s) associated with the waste being stored or treated in the LAW Vitrification System sub-systems [WAC 173-303-640(5)(d), in accordance with WAC 173-303-680(2)].
- xx. The Permittees shall ensure that the secondary containment systems for the LAW Vitrification System sub-systems listed in Permit Tables III.10.H.A. and III.10.H.B, as approved/modified pursuant to Permit Condition III.10.H.5, are free of cracks or gaps to prevent any migration of dangerous and/or mixed waste or accumulated liquid out of the system to the soil, groundwater, or surface water at any time during use of the LAW Vitrification System sub-systems. Any indication that a crack or gap may exist in the containment systems shall be investigated and repaired in accordance with Attachment 51, Appendix 9.18 of this Permit, as approved pursuant to Permit Condition III.10.H.5.e.v. [WAC 173-303-640(4)(b)(i), WAC 173-303-680(2) and (3), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-320].
- xxi. The Permittees must immediately, and safely, remove from service any LAW Vitrification System or secondary containment system which through an integrity assessment is found to be "unfit for use" as defined in WAC 173-303-040, following Permit Conditions III.10.H.1.a.xxiii.A. through D., and F. The affected LAW Vitrification System or secondary containment system must be either repaired or closed in accordance with Permit Condition III.10.H.1.a.xxiii.E. [WAC 173-303-640(7)(e) and (f), WAC 173-303-640(8), in accordance with WAC 173-303-680(3)].
- xxii. An impermeable coating, as specified in Attachment 51, Appendices 9.4, 9.5, 9.7, 9.9, 9.11, and 9.12 of this Permit, as approved pursuant to Permit Condition III.10.H.5.b.v. shall be maintained for all concrete containment systems and concrete portions of containment systems for each LAW Vitrification System sub-systems listed in Permit

Expiration Date: September 27, 2004

Page 99 of 210

1		Tables III.10.H.A and III.10.H.B, as approved/modified pursuant to Permit Condition
2		III.10.H.5 (concrete containment systems that do not have a liner, pursuant to WAC
3 ·		173-303-640(4)(e)(i), in accordance with WAC 173-303-680(2), and have
4		construction joints, shall meet the requirements of WAC 173-303-640(4)(e)(ii)(C), in
5		accordance with WAC 173-303-680(2). The coating shall prevent migration of any
6		dangerous and mixed waste into the concrete. All coatings shall meet the following
7	$\mathcal{L}_{i} = \{ 1, \dots, n \}$	performance standards:
8		A. The coating must seal the containment surface such that no cracks, seams, or
9	•	other avenues through which liquid could migrate are present;
10	•	B. The coating must be of adequate thickness and strength to withstand the normal
11		operation of equipment and personnel within the given area such that degradation
12		or physical damage to the coating or lining can be identified and remedied before
13		dangerous and mixed waste could migrate from the system; and
1.1		
14		C. The coating must be compatible with the dangerous and mixed waste, treatment reagents, or other materials managed in the containment system [WAC 173-303-
15		640(4)(e)(ii)(D), in accordance with WAC 173-303-680(2) and (3), and WAC
16 17		173-303-806(4)(i)(i)(A)].
18	xxiii.	
19		Vitrification System sub-systems listed in Permit Tables III.10.H.A and III.10.H.B, as
20		approved/modified pursuant to Permit Condition III.10.H.5., in accordance with the
21		Inspection Schedule specified in Attachment 51, Chapter 6.0 of this Permit, as
22	÷	approved pursuant to Permit Conditions III.10.H.5.e.i. and III.10.C.5.c., and take the
23		following actions if a leak or spill of dangerous and/or mixed waste is detected in
24		these containment systems [WAC 173-303-640(5)(c) and WAC 173-303-640(6), in
25		accordance with WAC 173-303-680(2) and (3), WAC 173-303-320, and WAC 173-
26		303-806(4)(i)(i)(B)]:
27		A. Immediately, and safely, stop the flow of dangerous and/or mixed waste into the
28		LAW Vitrification System sub-systems or secondary containment system.
29		B. Determine the source of the dangerous and/or mixed waste.
30		C. Remove the dangerous and/or mixed waste from the containment area in
31	. *	accordance with WAC 173-303-680(2) and (3) as specified in WAC 173-303-
32		640(7)(b). The dangerous and/or mixed waste removed from containment areas
33		of the LAW Vitrification System sub-systems shall be, as a minimum, managed
34		as mixed waste.
35	<u>.</u> .	D. If the cause of the release was a spill that has not damaged the integrity of the
36		LAW Vitrification System sub-system, the Permittees may return the LAW
37	and the same	Vitrification System sub-system to service in accordance with WAC 173-303-
38		680(2) and (3) as specified in WAC 173-303-640(7)(e)(ii). In such case, the
39	4	Permittees shall take action to insure the incident that caused the dangerous
_/		I THE TOTAL PRINTE WITH ANTION TO THOMAN HAS MANAGED WITH ANTIONED

303-320(3)].

and/or mixed waste to enter the containment system will not reoccur [WAC 173-

39

40

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 100 of 210

1 2		E. If the source of the dangerous and/or mixed waste is determined to be a leak from the primary LAW Vitrification System into the secondary containment system, or
3 4 5		the system is unfit for use as determined through an integrity assessment or other inspection, the Permittees shall comply with the requirements of WAC 173-303-640(7) and take the following actions:
6 7 8 9		1. Close the LAW Vitrification System sub-system following procedures in WAC 173-303-640(7)(e)(i), in accordance with WAC 173-303-680 and Attachment 51, Chapter 11.0 of this Permit, as approved pursuant to Permit Condition III.10.C.8., or
10 11 12 13 14 15		 Repair and re-certify (in accordance with WAC 173-303-810(13)(a), as modified pursuant to Permit Condition III.10.H.1.a.iii.) the LAW Vitrification System, in accordance with Attachment 51, Appendix 9.18 of this Permit, as approved pursuant to Permit Condition III.10 H.5.e.v., before the LAW Vitrification System is placed back into service [WAC 173-303-640(7)(e)(iii) and WAC 173-303-640(7)(f), in accordance with WAC 173-303-680].
17 18 19		F. The Permittees shall document in the operating record actions/procedures taken to comply with A. through E. above as specified in WAC 173-303-640(6)(d), in accordance with WAC 173-303-680(2) and (3).
20 21 22		G. In accordance with WAC 173-303-680(2) and WAC 173-303-680 (3), the Permittees shall notify and report releases to the environment to Ecology as specified in WAC 173-303-640(7)(d).
23 24 25 26 27 28 29 30	xxiv.	If liquids (e.g., dangerous and/or mixed waste leaks and spills, precipitation, fire water, liquids from damaged or broken pipes) cannot be removed from the secondary containment system within twenty-four (24) hours, Ecology will be verbally notified within twenty-four (24) hours of discovery. The notification shall provide the information in A, B, and C, listed below. The Permittees shall provide Ecology with a written demonstration within seven (7) business days, identifying at a minimum [WAC 173-303-640(4)(c)(iv) and WAC 173-303-640(7)(b)(ii), in accordance with WAC 173-303-680(3) and WAC 173-303-806(4)(i)(i)(B)]:
31		A. Reasons for delayed removal;
32 33		B. Measures implemented to ensure continued protection of human health and the environment;
34		C Current actions being taken to remove liquids from secondary containment.
35 36 37 38 39 40	XXV.	All air pollution control devices and capture systems in the LAW Vitrification System shall be maintained and operated at all times in a manner so as to minimize the emissions of air contaminants and to minimize process upsets. Procedures for ensuring that the air pollution control devices and capture systems in the LAW Vitrification System are properly operated and maintained so as to minimize the emission of air contaminants and process upsets shall be established.

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 101 of 210

	1 · 2	ing salah salah salah salah salah salah salah salah salah salah salah salah salah salah salah salah salah salah	xxvi.	In all future narrative permit submittals, the Permittees shall include LAW Vitrification sub-system names with the sub-system designation.
	3 4 5 6		xxvii.	Modifications to approved design, plans, and specifications in Attachment 51 of this Permit for the LAW Vitrification System shall be allowed only in accordance with Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g., III.10.C.9.d., III.10.C.9.e., and III.10.C.9.h.
	7 8 9 10		xxyiii.	For any portion of the LAW Vitrification System which has the potential for formation and accumulation of hydrogen gases, the Permittees shall operate the portion to maintain hydrogen levels below the lower explosive limit [WAC 173-303-815(2)(b)(ii)].
	11 12 13 14		xxix.	For each LAW Vitrification System sub-system holding dangerous waste which are acutely or chronically toxic by inhalation, the Permittees shall operate the system to prevent escape of vapors, fumes or other emissions into the air [WAC 173-303-806(4)(i)(i)(B) and WAC 173-303-640(5)(e), in accordance with WAC 173-303-680].
	15	III.10.H.1.b.	Perfor	mance Standards
	16 17 18 19		(<u>]</u>	The LAW Vitrification System must achieve a destruction and removal efficiency DRE) of 99.99% for the principal organic dangerous constituents (PODCs) listed below 40 CFR §63.1203(c)(1), 40CFR 63.1203(c)(2), in accordance with WAC 173-303-80(2)]:
	20			RESERVED
	21 22			DRE in this permit condition shall be calculated in accordance with the formula given below:
•	23			DRE= $[1-(W_{out}/W_{in})] \times 100\%$
Ā.	24 25 26 27	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		Where: W _{in} =mass feed-rate of one principal organic dangerous constituent (PODC) in a waste feedstream; and W _{out} =mass emission rate of the same PODC present in exhaust emissions prior to
	28			release to the atmosphere.
	29 30 31		, n	articulate matter emissions from the LAW Vitrification System shall not exceed 34 ng/dscm (0.015 grains/dscf) [40 CFR §63.1203(b)(7), in accordance with WAC 173-03-680(2)].
	32 33 34		n	Tydrochloric acid and chlorine gas emissions from the LAW Vitrification System shall ot exceed 21 ppmv, combined [40 CFR §63.1203(b)(6), in accordance with WAC 173-03-680(2)].
-	35 36 37		0,	Dioxin and Furan TEQ emissions from the LAW Vitrification System shall not exceed 2 nanograms (ng)/dscm [40 CFR §63.1203(b)(1), in accordance with WAC 173-303-80(2)].

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004

Page 102 of 210

1 2	V.	Mercury emissions from the LAW Vitrification System shall not exceed 45 μ g/dscm [40 CFR §63.1203(b)(2), in accordance with WAC 173-303-680(2)].
3 4 5	vi.	Lead and cadmium emissions from the LAW Vitrification System shall not exceed 120 μg/dscm, combined [40 CFR §63.1203(b)(3), in accordance with WAC 173-303-680(2)].
6 7 8	vii.	Arsenic, beryllium, and chromium emissions from the LAW Vitrification System shall not exceed 97 μg/dscm, combined [40 CFR §63.1203(b)(4), in accordance with WAC 173-303-680(2)].
9 10 11 12	viii.	Carbon monoxide (CO) emission from the LAW Vitrification System shall not exceed 100 parts per million (ppm) by volume, over an hourly rolling average (as measured and recorded by the continuous monitoring system), dry basis [40 CFR §63.1203(b)(5)(i), in accordance with WAC 173-303-680(2)].
13 14 15 16 17	ix.	Hydrocarbon emission from the LAW Vitrification System shall not exceed 10 parts per million (ppm) by volume, over an hourly rolling average (as measured and recorded by the continuous monitoring system during demonstration testing required by this Permit), dry basis, and reported as propane [40 CFR §63.1203(b)(5)(ii), in accordance with WAC 173-303-680(2)].
18 19 20 21	х.	If the emissions from the LAW Vitrification System exceed the emission rates listed in Permit Table III.10.H.E, as approved pursuant to Permit Condition III.10.C.11.b., the Permittees shall notify Ecology in accordance with Permit Condition III.10.H.3.d.vii. [WAC 173-303-680(2) and (3), and WAC 173-303-815(2)(b)(ii)].
22 23 24 25 26 27		The emission limits specified in Permit Conditions III.10.H.1.b.i. through III.10.H.1.b.x. above, shall be met for the LAW Vitrification System by limiting feed-rates as specified in Permit Tables III.10.H.D. and III.10.H.F., as approved/modified pursuant to Permit Condition III.10.H.5., compliance with operating conditions specified in Permit Condition III.10.H.1.c. (except as specified in Permit Condition III.10.H.1.b.xii.), and compliance with Permit Condition III.10.H.1.b.xi.
28 29 30 31 32 33 34 35 36	xi.	Treatment effectiveness, feed-rates and operating rates for dangerous and mixed waste management units contained in the LAW Building, but not included in Permit Table III.10.H.A, as approved/modified pursuant to Permit Condition III.10.H.5., shall be as specified in Permit Sections III.10.D, III.10.E, III.10.F and consistent with assumptions and basis which are reflected in Attachment 51, Appendix 6.3.1 of this Permit, as approved pursuant to Permit Condition III.10.C.11.b. For the purposes of this permit condition, Attachment 51, Appendix 6.3.1 shall be superceded by Appendix 6.4.1 upon its approval pursuant to either Permit Conditions III.10.C.11.c. or III.10.C.11.d. [WAC 173-303-680(2) and (3), and WAC 173-303-815(2)(b)(ii)].
37	xii.	Compliance with the operating conditions specified in Permit Condition III.10.H.1.c.,

shall be regarded as compliance with the required performance standards identified in

effective period of this Permit that compliance with the operating conditions in Permit

Condition III.10.H.1.c. is not sufficient to ensure compliance with the performance

Permit Conditions III.10.H.1.b.i. through x. However, if it is determined that during the

38

39

40

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 103 of 210

2		modified, revoked, or reissued pursuant to Permit Conditions III.10.C.2.e. and
3		III.10.C.2.f., or III.10.C.2.g.
4	III.10.H.1.c. Ope	erating Conditions [WAC-303-670(6), in accordance with WAC 173-303-680(2) and (3)].
5 6 7 8 9	51, Atta III. I Peri	Permittees shall operate the LAW Vitrification System in accordance with Attachment Chapter 4.0 of this Permit, as updated pursuant to Permit Condition III.10.H.5.e.vi., achment 51, Appendix 9.18 of this Permit, as approved pursuant to Permit Condition 10.H.5.e., and Attachment 51, Appendix 9.15 of this Permit, as approved pursuant to mit Condition III.10.H.5.f., except as modified pursuant to Permit Conditions 10.H.1.b.xii., III.10.H.2., III.10.H.3., III.10.H.4., and in accordance with the following:
11 12 13 14	i.	The Permittees shall operate the LAW Vitrification System in order to maintain the systems and process parameters listed in Permit Tables III.10.H.C and III.10.H.F, as approved/modified pursuant to Permit Condition III.10.H.5., within the set-points specified in Permit Table III.10.H.F.
15 16 17 18 19	ii.	The Permittees shall operate the AWFCO systems, specified in Permit Table III.10.H.F, as approved/modified pursuant to Permit Condition III.10.H.5., to automatically cut-off and/or lock-out the dangerous and mixed waste feed to the LAW Vitrification System when the monitored operating conditions deviate from the set-points specified in Permit Table III.10.H.F.
20 21 22 23 24	iii.	The Permittees shall operate the AWFCO systems, specified in Permit Table III.10.H.F, as approved/modified pursuant to Permit Condition III.10.H.5., to automatically cut-off and/or lock-out the dangerous and mixed waste feed to the LAW Vitrification System when all instruments specified on Permit Table III.10.H.F for measuring the monitored parameter fail or exceed its span value.
25 26 27 28 29 30 31	iv.	The Permittees shall operate the AWFCO systems, specified in Permit Table III.10.H.F, as approved/modified pursuant to Permit Condition III.10.H.5., to automatically cut-off and/or lock out the dangerous and/or mixed waste feed to the LAW Vitrification System when any portion of the LAW Vitrification System is bypassed. The terms "bypassed" and "bypass event" as used in Permit Sections III.10.H and III.10.I shall mean if any portion of the LAW Vitrification System is bypassed so that gases are not treated as during the Demonstration Test.
32 33 34 35 36	V.	In the event of a malfunction of the AWFCO systems listed in Permit Table III 10.H.F, as approved/modified pursuant to Permit Condition III.10.H.5., the Permittees shall immediately, manually cut-off the dangerous and mixed waste feed to the LAW Vitrification System. The Permittees shall not restart the dangerous and/or mixed waste feed until the problem causing the malfunction has been identified and corrected.
37 38 39 40 41	vi.	The Permittees shall manually cut-off the dangerous and mixed waste feed to the LAW Vitrification System when the operating conditions deviate from the limits specified in Permit Condition III.10.H.1.c.i., unless the deviation automatically activates the waste feed cut-off sequence specified in Permit Conditions III.10.H.1.c.ii., III.10.H.1.c.iii., and/or III.10.H.1.c.iv.

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 104 of 210

1 2	V	ii. If greater than thirty (30) dangerous and mixed waste feed cut-off, combined, to the LAW Vitrification System occur due to deviations from Permit Table III.10.H.F, as
3 4 5		approved/modified pursuant to Permit Condition III.10.H.5., within a sixty (60) day period, the Permittees shall submit a written report to Ecology within five (5) calendar days of the thirty-first exceedance including the information specified below. These
6 7		dangerous and mixed waste feed cut-offs to the LAW Vitrification System, whether automatically or manually activated, are counted if the specified set points are deviated
8 9 10 11		from while dangerous waste, mixed waste, and waste residues continue to be processed in the LAW Vitrification System. A cascade event is counted at a frequency of one (1) towards the first waste feed cut-off parameter, specified on Permit Table III.10.H.F, from which the set-point is deviated:
12		A. The parameter(s) that deviated from the set-point(s) in Permit Table III.10.H.F;
13		B. The magnitude, dates, and duration of the deviations;
14		C. Results of the investigation of the cause of the deviations; and
15		D. Corrective measures taken to minimize future occurrences of the deviations.
16 17 18 19 20	vi	ii. If any portion of the LAW Vitrification System is bypassed while treating dangerous and/or mixed waste it shall be regarded as non-compliance with the operating conditions specified in Permit Condition III.10.H.1.c. and the performance standards specified in Permit Condition III.10.H.1.b. After such a bypass event, the Permittees shall perform the following actions:
21		A. Investigate the cause of the bypass event;
22 .		B. Take appropriate corrective measures to minimize future bypasses;
23 24		C. Record the investigation findings and corrective measures in the operating record; and
25 26		D. Submit a written report to Ecology within five (5) days of the bypass event documenting the result of the investigation and corrective measures.
27 28	ix	The Permittees shall control fugitive emissions from the LAW Vitrification System by maintaining the melters under negative pressure.
29 30 31 32 33 34	X.	Compliance with the operating conditions specified in Permit Condition III.10.H.1.c. shall be regarded as compliance with the required performance standards identified in Permit Condition III.10.H.1.b. However, evidence that compliance with these operating conditions is insufficient to ensure compliance with the performance standards, shall justify modification, revocation, or re-issuance of this Permit, in accordance with Permit Conditions III.10.C.2.e. and III.10.C.2.f., or III.10.C.2.g.
35	III.10.H.1.d. In	spection Requirements [WAC 173-303-680(3)]
36 37 38	i.	The Permittees shall inspect the LAW Vitrification System in accordance with the Inspection Schedules in Attachment 51, Chapter 6.0 of this Permit, as modified in accordance with Permit Condition III.10.C.5.c.

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 105 of 210

1 2 3		ii.	The inspection data for LAW Vitrification System shall be recorded, and the records shall be placed in the WTP Unit operating record for the LAW Vitrification System, in accordance with Permit Condition III.10.C.4.
3 4 5 6 7		iii.	The Permittees shall comply with the inspection requirements specified in Attachment 51, Appendix 9.15 of this Permit, as approved pursuant to Permit Condition III.10.H.5.f., and as modified by Permit Conditions III.10.H.1.b.xii., III.10.H.2., III.10.H.3., and III.10.H.4.
8	III.10.H.1.e.	Moi 670	nitoring Requirements [WAC 173-303-670(5), WAC 173-303-670(6), WAC -173-303-(7) and WAC 173-303-807(2), in accordance with WAC 173-303-680(3)]
10 11 12 13		i.	Upon receipt of a written request from Ecology, the Permittees shall perform sampling and analysis of the dangerous and mixed waste and exhaust emissions to verify that the operating requirements established in the Permit achieve the performance standards delineated in this Permit.
14 15 16 17		ii,	The Permittees shall comply with the monitoring requirements specified in Attachment 51, Appendices 9.2, 9.3, 9.7, 9.13, 9.15 and 9.18 of this Permit, as approved pursuant to Permit Conditions III.10.H.5.c., III.10.H.5.d., III.10.H.5.e., and III.10.H.5.f., as modified by Permit Conditions III.10.H.1.b.xii., III.10.H.2., III.10.H.3., and III.10.H.4.
18 19 20 21 22 23 24		iii.	The Permittees shall operate, calibrate, and maintain the carbon monoxide and hydrocarbon continuous emission monitors (CEM) specified in this Permit in accordance with Performance Specification 4B and 8A of 40 CFR Part 60, Appendix B, in accordance with Appendix to Subpart EEE of 40 CFR Part 63, and Attachment 51 Appendix 9.15 of this Permit, as approved pursuant to Permit Condition III.10.H.5.f., and as modified by Permit Conditions III.10.H.1.b.xii., III.10.H.2., III.10.H.3., and III.10.H.4.
25 26 27 28 29		iv.	The Permittees shall operate, calibrate, and maintain the instruments specified on Permit Tables HI.10.H.C, and F, as approved/modified pursuant to Permit Condition III.10.H.5., in accordance with Attachment 51, Appendix 9.15 of this Permit, as approved pursuant to Permit Condition III.10.H.5.f., and as modified by Permit Conditions III.10.H.1.b.xii., III.10.H.2., III.10.H.3., and III.10.H.4.
30	III.10.H.1.f.	Rec	ordkeeping Requirements [WAC 173-303-380 and WAC 173-303-680(3)]
31 32 33 34 35		i.	The Permittees shall record and maintain in the WTP Unit operating record for the LAW Vitrification System, all monitoring, calibration, maintenance, test data, and inspection data compiled under the conditions of this Permit, in accordance with Permit Conditions III.10.C.4. and III.10.C.5., as modified by Permit Conditions III.10.H.1.b.xii., III.10.H.2., III.10.H.3., and III.10.H.4.
36 37 38 39 40		ii.	The Permittees shall record in the WTP Unit operating record the date, time, and duration of all automatic waste feed cutoffs and/or lockouts, including the triggering parameters, reason for the deviation, and recurrence of the incident. The Permittees shall also record all incidents of AWFCO system function failures, including the corrective measures taken to correct the condition that caused the failure.

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 106 of 210

1 2	iii	. The Permittees shall submit to Ecology a report semi-annually the first calendar year, and annually thereafter each calendar year within ninety (90) days following the end of
3		the year. The report will include the following information:
4 5		A. Total dangerous and mixed waste feed processing time for the LAW Vitrification System;
6		B. Date/Time of all LAW Vitrification System startups and shutdowns;
7 8 9		C. Date/Time/Duration/Cause/Corrective Action taken for all LAW Vitrification System shutdowns caused by malfunction of either process or control equipment; and
10 11 12		D. Date/Time/Duration/Cause/Corrective Action taken for all instances of dangerous and/or mixed waste feed cut-off due to deviations from Permit Table III.10.H.F, as approved/modified pursuant to Permit Condition III.10.H.5.
13 14 15 16	iv	The Permittees shall submit an annual report to Ecology each calendar year within ninety (90) days following the end of the year of all quarterly CEM Calibration Error and Annual CEM Performance Specification Tests conducted in accordance with Permit Condition III.10.H.1.e.iii.
17	III.10.H.1.g. Cl	osure
18 19		ne Permittees shall close the LAW Vitrification System in accordance with Attachment 51, napter 11.0 of this Permit, as approved pursuant to Permit Condition III.10.C.8.
20 21		akedown Period [WAC 173-303-670(5), WAC 173-303-670(6), WAC -173-303-670(7), d WAC 173-303-807(2), in accordance with WAC 173-303-680(2) and (3)].
22 23 24 25	wi pu	the shakedown period for the LAW Vitrification System shall be conducted in accordance th Permit Condition III.10.H.1., Attachment 51, Appendix 9.15 of this Permit, as approved resuant to Permit Condition III.10.H.5.f., and as modified in accordance with Permit and III.10.H.1.b.xii., III.10.H.2., and III.10.H.3.
26	III.10.H.2.b. Du	iration of the Shakedown Period
27 28 29	i.	The shakedown period for the LAW Vitrification System shall begin with the initial introduction of dangerous waste in the LAW Vitrification System following construction and shall end with the start of the demonstration test.
30 31 32 33 34	11	The shakedown period shall not exceed the following limits, as defined by hours of operation of the LAW Vitrification System with dangerous waste. The Permittees may petition Ecology for one extension of each shakedown phase for seven hundred and twenty (720) additional operating hours in accordance with Permit modification procedures specified in Permit Conditions III.10.C.2.e. and III.10.C.2.f.
35		Shakedown Phase 1: 720 hours
36		Shakedown Phase 2: 720 hours
37 38	iii	Shakedown Phase 2 shall not be commenced until documentation has been submitted to Ecology verifying that the LAW Vitrification System has operated at a minimum of

Expiration Date: September 27, 2004 Page 107 of 210

· 1		75% of the shakedown Phase 1 feed-rate limit for two (2) separate eight (8) consecutive hour periods with no AWFCOs.
3	III.10.H.2.c.	Allowable Waste Feed During the Shakedown Period
4 5 6 7 8		i. The Permittees may feed the dangerous waste specified for the LAW Vitrification System on the Part A Forms (Attachment 51, Chapter 1.0 of this Permit), except for those wastes outside the waste acceptance criteria specified in the WAP, Attachment 1, Chapter 3.0 of this Permit, as approved pursuant to Permit Condition III.10.C.3., except Permit Conditions III.10.H.2.c.ii. through v. also apply.
9 10		ii. The Permittees shall not feed the following wastes to the LAW Vitrification System during Shakedown Phase 1:
. 11		A. Acutely toxic dangerous waste listed in WAC 173-303-081(a)(2)(a)(i).
12		B. Mixed waste
13 14		iii. The Permittees shall not feed the following waste to the LAW Vitrification System during Shakedown Phase 2:
15		A. Mixed waste
16 17 18		iv. The feed-rates to the LAW Vitrification System shall not exceed the limits in Permit Tables III.10.H.D and III.10.H.F, as approved/modified pursuant to Permit Condition III.10.H.5.
19 20 21		v. The Permittees shall conduct sufficient analysis of the dangerous waste treated in the LAW Vitrification System to verify that the waste feed is within the physical and chemical composition limits specified in this Permit.
22 23	Ш.10.Н.3.	Demonstration Test Period [WAC 173-303-670(5), WAC 173-303-670(6), WAC 173-303-670(7), and WAC 173-303-807(2), in accordance with WAC 173-303-680(2) and (3)].
24	Ш.10.Н.3.а.	Demonstration Test Period
25 26 27 28		i. The Permittees shall operate, monitor, and maintain the LAW Vitrification System as specified in Permit Condition III.10.H.1., and Attachment 51, Appendix 9.15 of this Permit, as approved pursuant to Permit Condition III.10.H.5.f., except as modified in accordance with Permit Conditions III.10.H.1.b.xii., and III.10.H.3.
29 30 31 32 33 34 35		ii. Attachment 51, Appendix 9.15 of this Permit, as approved pursuant to Permit Condition III.10.H.5.f., shall be resubmitted to Ecology for approval by the Permittees as a permit modification pursuant to Permit Conditions III.10.C.2.e. and III.10.C.2.f. at least one hundred and eighty (180) days prior to the start date of the demonstration test. The revised Demonstration Test Plan shall include applicable EPA promulgated test methods and procedures in effect at the time of the re-submittal and projected commencement and completion dates for the Demonstration Test.
36 37 38 39		iii. The Permittees shall not commence the demonstration test period until documentation has been submitted to Ecology verifying that the LAW Vitrification System has operated at a minimum of 90% of the demonstration test period feed-rate limit for a minimum of an eight (8) consecutive hours period on two (2) consecutive days.

Expiration Date: September 27, 2004

Page 108 of 210

III.10.H.3.b. Performance Standards

The Permittees shall demonstrate compliance with the performance standards specified in-Permit Condition III.10.H.1.b. during the Demonstration Test Period.

III.10.H.3.c. Allowable Waste Feed During the Demonstration Test Period

- i. The Permittees may feed the dangerous waste specified for the LAW Vitrification System in Part A Forms (Attachment 51, Chapter 1.0 of this Permit), except for those waste outside the waste acceptance criteria specified in the WAP, Attachment 51, Chapter 3.0 of this Permit, as approved pursuant to Permit Condition III.10.C.3., except Permit Conditions III.10.H.3.c.ii. through iv. also apply.
 - ii. The Permittees shall not feed mixed waste to the LAW Vitrification System.
 - iii. The dangerous waste feed-rates to the LAW Vitrification System shall not exceed the limits in Permit Tables III.10.H.D and F, as approved/modified pursuant to Permit Condition III.10.H.5.
 - iv. The Permittees shall conduct sufficient analysis of the dangerous waste treated in the LAW Vitrification System to verify that the dangerous waste is within the physical and chemical composition limits specified in this Permit.

III.10.H.3.d. Demonstration Data Submissions and Certifications

- i. The Permittees shall submit a summary of data collected as required by the Demonstration Test Plan to Ecology upon completion of the Demonstration Test. The Permittees shall submit to Ecology a complete demonstration test report within one-hundred twenty (120) calendar days of completion of the Demonstration Test including all data collected during the Demonstration Test and updated Permit Tables III.10.I.D, III.10.I.E and III.10.I.F.
- ii. The Permittees must submit to Ecology a certification that the Demonstration Test has been carried out in accordance with the approved Demonstration Test Plan and approved modifications within thirty (30) days of the completion of the Demonstration Test [WAC 173-303-807(8)].
- iii. After successful completion of the Demonstration Test, the Permittees shall be authorized to commence feed of dangerous waste and mixed waste to the LAW Vitrification System up to one melter at maximum feed-rates for the post-demonstration test period indicated in Permit Tables III.10.H.D and F, as approved/modified pursuant to Permit Condition III.10.H.5., in compliance with the operating requirements specified in Permit Condition III.10.H.1.c.
- iv. After successful completion of the Demonstration Test, Permittees submittal of the following to Ecology, and the Permittees' receipt of Ecology approval of the following, in writing, the Permittees shall be authorized to commence dangerous waste and mixed waste to the LAW Vitrification System up to two melters at maximum feed-rates for the post-demonstration test period indicated in Permit Tables III.10.H.D and F, as approved/modified pursuant to Permit Condition III.10.H.5., in compliance with the operating requirements specified in Permit Condition III.10.H.1.c.:

Expiration Date: September 27, 2004 Page 109 of 210

1 2		A. Calculations and analytical data showing compliance with the performance standard specified in Permit Condition III.10.H.1.b.i.
3 4 5 6	.v.	After successful completion of the Demonstration Test, Permittees submittal of the following to Ecology and the Permittees receipt of approval of the following in writing, the Permittees shall be authorized to feed dangerous waste and mixed waste to the LAW Vitrification System pursuant to Permit Section III.10.I.
7 8 9 10 11		A. A complete Demonstration Test Report for the LAW Vitrification System and updated Permit Tables III.10.I.D, III.10.I.E, and III.10.I.F, as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.C.11.c or III.10.C.11.d. The test report shall be certified in accordance with WAC 173-303-807(8), in accordance with WAC 173-303-680(2) and (3).
12 13		B. A Final Risk Assessment Report completed pursuant to Permit Conditions III.10.C.11.c. or III.10.C.11.d.
14 15 16 17	vi.	If any calculations or testing results show that one or more of the performance standards listed in Permit Condition III.10.H.1.b., with the exception of Permit Condition III.10.H.1.b.x., for the LAW Vitrification System were not met during the Demonstration Test, the Permittees shall perform the following actions:
18 19 20		A. Immediately stop dangerous and mixed waste feed to the LAW Vitrification System under the mode of operation that resulted in not meeting the performance standard(s).
21 22		B. Verbally notify Ecology within twenty-four (24) hours of discovery of not meeting the performance standard(s) as specified in Permit Condition I.E.21.
23 24 25		C. Investigate the cause of the failure and submit a report of the investigation findings to Ecology within fifteen (15) days of discovery of not meeting the performance standard(s).
26 27 28 29 30		D. Submit to Ecology within fifteen (15) days of discovery of not meeting the performance standard(s), documentation supporting a mode of operation where all performance standards listed in Permit Condition III.10.H.1.b., with the exception of Permit Condition III.10.H.1.b.x., for the LAW Vitrification System were met during the demonstration test, if any such mode was demonstrated.
31 32 33 34 35 36 37		E. Based on the information provided to Ecology by the Permittees pursuant to Permit Conditions III.10.H.3.d.vi.A through D above, and any additional information, Ecology may submit in writing, direction to the Permittees to stop dangerous and/or mixed waste feed to the LAW Vitrification System and/or amend the mode of operation the Permittees are allowed to continue operations prior to Ecology approval of a compliance schedule and/or revised Demonstration Test Plan pursuant to Permit Conditions III.10.H.3.d.vi.F and G.
38 39 40		F. If the performance standard listed in Permit Condition III.10.H.1.b.i. was not met during the Demonstration Test, the Permittees shall submit within one hundred and twenty (120) days of discovery of not meeting the performance standard, a revised

Demonstration Test Plan (if appropriate), and a compliance schedule for Ecology

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 110 of 210

1 2	approval to address this deficiency. If a revised Demonstration Test Plan is submitted, it shall be accompanied by a request for approval to retest as a permit
3 4 5	modification pursuant to Permit Conditions III.10.C.2.e. and III.10.C.2.f. The revised Demonstration Test Plan (if submitted) must include substantive changes to prevent failure from reoccurring.
6 7 8 9 10 11 12 13	G. If any of the performance standards listed in Permit Condition III.10.H.1.b., with the exception of Permit Conditions III.10.H.1.b.i. or III.10.H.1.b.x., were not met during the Demonstration Test the Permittees shall submit to Ecology within one hundred twenty (120) days of discovery of not meeting the performance standard(s), a revised Demonstration Test Plan requesting approval to retest as a permit modification pursuant to Permit Conditions III.10.C.2.e. and III.10.C.2.f. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring.
14 15 16 17	vii. If any calculations or testing results show that any emission rate for any constituent listed in Permit Table III.10.H.E, as approved pursuant to Permit Condition III.10.C.11.b., is exceeded for LAW Vitrification System during the Demonstration Test, the Permittees shall perform the following actions:
18 19	A. Verbally notify Ecology within twenty-four (24) hours of the discovery of exceeding the emission rate(s) as specified in Permit Condition I.E.21.
20 21 22 23 24 25	B. Submit to Ecology additional risk information to indicate that the increased emissions impact is offset by decreased emission impact from one or more constituents expected to be emitted at the same time, and/or investigate the cause and impact of the exceedance of the emission rate(s) and submit a report of the investigation findings to Ecology within fifteen (15) days of the discovery of exceeding the emission rate(s); and
26 27 28 29 30 31	C. Based on the notification and any additional information, Ecology may submit, in writing, direction to the Permittees to stop dangerous and/or mixed waste feed to the LAW Vitrification System and/or to submit a revised Demonstration Test Plan as a permit modification pursuant to Permit Conditions III.10.C.2.e. and III.10.C.2.f., or III.10.C.2.g. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring.
32 33	III.10.H.4. Post Demonstration Test Period [WAC 173-303-670(5), WAC 173-303-670(6), and WAC 173-303-807(2), in accordance with WAC 173-303-680(2) and (3)]
34 35 36 37	III.10.H.4.a. The Permittees shall operate, monitor, and maintain the LAW Vitrification System as specified in Permit Condition III.10.H.1. and Attachment 51, Appendix 9.15 of this Permit, as approved pursuant to Permit Condition III.10.H.5., except as modified in accordance with Permit Conditions III.10.H.1.b.xii., III.10.H.3., and III.10.H.4.
38	III.10.H.4.b. Allowable Waste Feed During the Post-Demonstration Test Period
39 40 41	 The Permittees may feed the dangerous and/or mixed waste specified for the LAW Vitrification System on the Part A Forms (Attachment 51, Chapter 1.0 of this Permit), except for those wastes outside the waste acceptance criteria specified in the WAP,

Modification to Revision 7

Expiration Date: September 27, 2004

Page 111 of 210

Attachment 51, Chapter 3.0 of this Permit, as approved pursuant to Permit Condition 1 III.10.C.3., and except Permit Conditions III.10.H.4.b.ii. and III.10.H.4.b.iii. also apply. 2 The dangerous waste and mixed waste feed-rates to the LAW Vitrification System shall 3 not exceed the limits in Permit Tables III.10.H.D and F, as approved/modified pursuant 4 to Permit Condition III.10.H.5., or in Permit Condition III.10.H.3 5 The Permittees shall conduct sufficient analysis of the dangerous waste and mixed waste 6 treated in LAW Vitrification System to verify that the waste feed is within the physical 7 and chemical composition limits specified in this Permit. 8 Compliance Schedules III.10.H.5. 9 III.10.H.5.a. All information identified for submittal to Ecology in a. through f. of this compliance 10 schedule must be signed and certified in accordance with requirements in WAC 173-303-11 810(12), as modified in accordance with Permit Condition III.10.H.1.a.iii. [WAC 173-303-12 806(4)]. 13 III.10.H.5.b. The Permittees shall submit to Ecology, pursuant to Permit Condition III. 10.C.9.f., prior to 14 construction of each secondary containment and leak detection system for the LAW 15 Vitrification System (per level) as identified in Permit Tables III.10.H.A and III.10.H.B, 16 engineering information as specified below, for incorporation into Attachment 51, 17 Appendices 9.2, 9.4, 9.5, 9.7, 9.8, 9.9, 9.11, and 9.12 of this Permit. At a minimum, 18 engineering information specified below will show the following as described in WAC 173-19 303-640, in accordance with WAC 173-303-680 (the information specified below will 20 include dimensioned engineering drawings and information on sumps and floor drains): 21 IORPE Reports (specific to foundation, secondary containment, and leak detection 22 system) shall include review of design drawings, calculations, and other information on 23 which the certification report is based and shall include as applicable, but not limited to, 24 review of such information described below. Information (drawings, specifications, 25 etc.) already included in Attachment 51, Appendix 9.0 of this Permit, may be included 26 in the report by reference and should include drawing and document numbers. IQRPE 27 Reports shall be consistent with the information separately provided in ii. through ix. 28 below [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680 and WAC 173-29 303-806(4)(i)(i)]; 30 Design drawings (General Arrangement Drawings, in plan and cross sections) and 31 specifications for the foundation, secondary containment including liner installation 32 details, and leak detection methodology. These items should show the dimensions, 33 volume calculations, and location of the secondary containment system, and should 34 include items such as floor/pipe slopes to sumps, tanks, floor drains [WAC 173-303-35 640(4)(b) through (f) and WAC 173-303-640(3)(a), in accordance with WAC 173-303-36 680 and WAC 173-303-806(4)(i)(i)]; 37 The Permittees shall provide the design criteria (references to codes and standards, load 38 definitions, and load combinations, materials of construction, and analysis/design 39 methodology) and typical design details for the support of the secondary containment 40 system. This information shall demonstrate the foundation will be capable of providing 41

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 112 of 210

1 2			support to the secondary containment system, resistance to pressure gradients above and below the system, and capable of preventing failure due to settlement, compression, or
3 4			uplift [WAC 173-303-640(4)(c)(ii), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(B)];
5 6 7 8		iv.	A description of materials and equipment used to provide corrosion protection for external metal components in contact with soil, including factors affecting the potential for corrosion [WAC 173-303-640(3)(a)(iii)(B), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(A) through (B)];
9 10 11		v.	Secondary containment/foundation, and leak detection system, materials selection documentation (including, but not limited to, concrete coatings and water stops, and liner materials) as applicable [WAC 173-303-806(4)(i)(i)(A) through (B)];
12 13 14		vi.	Detailed description of how the secondary containment for the LAW Vitrification System will be installed in compliance with WAC 173-303-640(3)(c), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(A) through (B);
15 16 17		vii.	Submit Permit Tables III.10.H.B and III.10.I.B completed to provide for all secondary containment sumps and floor drains the information as specified in each column heading consistent with information to be provided in i. through vi., above;
18 19 20 21		viii.	Documentation that secondary containment and leak detection systems will not accumulate hydrogen gas levels above the lower explosive limit for incorporation into the Administrative Record [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A), and WAC 173-303-806(4)(i)(v)];
22 23 24		ix.	A detailed description of how LAW Vitrification System design provides access for conducting future LAW Vitrification System integrity assessments [WAC 173-303-640(3)(b) and WAC 173-303-806(4)(i)(i)(B)].
25 26 27 28 29 30 31	III.10.H.5:c.	insta infor thro belo with	Permittees shall submit to Ecology, pursuant to Permit Condition III.10.C.9.f, prior to allation of each sub-system as identified in Permit Table III.10.H.A, engineering rmation as specified below, for incorporation into Attachment 51, Appendices 9.1 augh 9.14, and 9.17 of this Permit. At a minimum, engineering information specified w will show the following, as required pursuant to WAC 173-303-640, in accordance WAC 173-303-680 (the information specified below will include dimensioned neering drawings):
32 33 34 35 36 37 38 39 40		**************************************	IQRPE Reports (specific to sub-system) shall include review of design drawings, calculations, and other information on which the certification report is based and shall include as applicable, but not limited to, review of such information described below. Information (drawings, specifications, etc.) already included in Attachment 51, Appendix 9.0 of this Permit, may be included in the report by reference and should include drawing and document numbers. The IQRPE Reports shall be consistent with the information separately provided in ii. through xii. below, and the IQRPE Report specified in Permit Condition III.10.H.5.b. [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)];

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 113 of 210

1 2	ii.	Design drawings [General Arrangement Drawings in plan and cross section, Process Flow Diagrams, Piping and Instrumentation Diagrams (including pressure control
3 4 5 6		systems), Mechanical Drawings, and specifications, and other information specific to subsystems (to show location and physical attributes of each subsystem)] [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)];
7 8 9 10 11 12 13 14 15	iii.	Sub-system design criteria (references to codes and standards, load definitions, and load combinations, materials of construction, and analysis/design methodology) and typical design details to support the subsystems. Structural support calculations specific to off-specification, non-standard and field fabricated subsystems shall be submitted for incorporation into the Administrative Record. Documentation shall include but not limited to, supporting specifications, test data, treatment effectiveness report, etc. supporting projected operational capability (e.g., WESP projected removal efficiency for individual metals, halogens, particulates, etc.) and compliance with performance standards specified in Permit Condition III.10.H.1.b [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(B)];
17 18 19 20	iv.	A description of materials and equipment used to provide corrosion protection for external metal components in contact with water, including factors affecting the potential for corrosion [WAC 173-303-640(3)(a)(iii)(B), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(A) through (B)];
21 22 23	v.	Sub-system materials selection documentation (e.g., physical and chemical tolerances) [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(A)];
24 25 26 27 28	vi.	Sub-system vendor information (including, but not limited to, required performance warranties, as available), consistent with information submitted under ii. above, shall be submitted for incorporation into the Administrative Record [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(v)];
29 30 31	vii.	System descriptions (process) related to sub-system units shall be submitted for incorporation into the Administrative Record [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(v)];
32 33 34 35 36	viii.	Mass and energy balance for normal projected operating conditions used in developing the Piping and Instrumentation Diagrams and Process Flow Diagrams, including assumptions and formulas used to complete the mass and energy balance, so that they can be independently verified for incorporation into the Administrative Record [WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-806(4)(i)(v)];
37	ix.	Detailed description of all potential LAW Vitrification System bypass events including:
38 39 40		A. A report which includes an analysis of credible potential bypass events and recommendations for prevention/minimization of the potential, impact, and frequency of the bypass event to include at a minimum:
41		1. Operating procedures

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 114 of 210

1		2. Maintenance procedures
2		3. Redundant equipment
3		4. Redundant instrumentation
4		5. Alternate equipment
5		6. Alternate materials of construction
6 7 8		x. A detailed description of how the sub-systems will be installed in compliance with WAC 173-303-640(3)(c), (d), and (e), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(B);
9 10 11 12		xi. Sub-system design to prevent escape of vapors and emissions of acutely or chronically toxic (upon inhalation) EHW, for incorporation into the Administrative Record [WAC 173-303-640(5)(e), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(B)];
13 14 15 16		xii. Documentation that sub-systems are designed to prevent the accumulation of hydrogen gases levels above the lower explosive limit for incorporation into the Administrative Record [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A), and WAC 173-303-806(4)(i)(v)].
17 18 19 20 21 22 23 24	III.10.H.5.d.	The Permittees shall submit to Ecology, pursuant to Permit Condition III.10.C.9.f, prior to installation of equipment for each sub-system as identified in Permit Tables III.10.H.A and III.10.H.B, not addressed in Permit Conditions III.10.H.5.b. or III.10.H.5.c., engineering information as specified below, for incorporation into Attachment 51, Appendices 9.1 through 9.14 of this Permit. At a minimum, engineering information specified below will show the following as required pursuant to WAC 173-303-640, in accordance with WAC 173-303-680 (the information specified below will include dimensioned engineering drawings):
25 26 27 28 29 30 31 32 33 34		i. IQRPE Reports (specific to sub-system equipment) shall include a review of design drawings, calculations, and other information as applicable on which the certification report is based. The reports shall include, but not be limited to, review of such information described below. Information (drawings, specifications, etc.) already included in Attachment 51, Appendix 9.0 of this Permit, may be included in the report by reference and should include drawing and document numbers. The IQRPE Reports shall be consistent with the information provided separately in ii. through xiii. below and the IQRPE Reports specified in Permit Conditions III.10.H.5.b. and III.10.H.5.c. [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(A) through (B)];
35 36 37 38	Alberta.	ii. Design drawings [Process Flow Diagrams, Piping and Instrumentation Diagrams (including pressure control systems), specifications and other information specific to equipment (these drawings should include all equipment such as pipes, valves, fittings, pumps, instruments, etc.)] [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(A) through (B)];

Modification to Revision 7

Expiration Date: September 27, 2004

Page 115 of 210

	1 2	 iii.	Sub-system equipment design criteria (references to codes and standards, load definitions, and load combinations, materials of construction, and analysis/design	
	3 4 5		methodology) and typical design details for the support of the sub-system equipment [WAC 173-303-640(3)(a) and WAC 173-303-640(3)(f), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(B)];	
	6 7 8 9	iv.	A description of materials and equipment used to provide corrosion protection for external metal components in contact with soil and water, including factors affecting the potential for corrosion [WAC 173-303-640(3)(a)(iii)(B), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(A)];	
	10 11 12	v.	Materials selection documentation for equipment for each sub-system (e.g., physical and chemical tolerances) [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(A)];	
	13 14 15 16 17	vi.	Vendor information (including, but not limited to, required performance warranties, as available), consistent with information submitted under ii. above, for sub-system equipment shall be submitted for incorporation into the Administrative Record. [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(iv)];	
-	18 19 20 21	vii.	Sub-system, sub-system equipment, and leak detection system instrument control logic narrative description (e.g., software functional specifications, descriptions of fail-safe conditions, etc.) [WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-806(4)(i)(v)].	
	22 23 24 25	viii.	System description (process) related to sub-system equipment, and system descriptions related to leak detection systems, (including instrument control logic and narrative descriptions), for incorporation into the Administrative Record [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(v)];	
	26 27 28	ix.	A detailed description of how the sub-system equipment will be installed and tested [WAC 173-303-640(3)(c) through (e), WAC 173-303-640(4)(b) and (c), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(B)];	
	29 30 31 32 33 34	X.	For process monitoring, control, and leak detection system instrumentation for the LAW Vitrification System as identified in Permit Tables III.10.H.C. and III.10.H. F., a detailed description of how the process monitoring, control, and leak detection system instrumentation, will be installed and tested [WAC 173-303-640(3)(c) through (e), WAC 173-303-640(4)(b) and (c), WAC 173-303-806(4)(c)(vi), and WAC 173-303-806(4)(i)(i)(B)];	
	35 36 37 38 39	xi.	Mass and energy balance for projected normal operating conditions used in developing the Piping and Instrumentation Diagrams and Process Flow Diagrams, including assumptions and formulas used to complete the mass and energy balance, so that they can be independently verified, for incorporation into the Administrative Record [WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-806(4)(i)(v)];	
	40 41		Documentation that sub-systems equipment are designed to prevent the accumulation of hydrogen gas levels above the lower explosive limit for incorporation into the	

hydrogen gas levels above the lower explosive limit for incorporation into the

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 116 of 210

Administrative Record [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A), and WAC <u>173-303-806(4)(i)(v)];</u> 3 xiii. Leak detection system documentation (e.g. vendor information, etc.) consistent with information submitted under Permit Condition III.10.H.5.c.ii. and Permit Conditions 4 III.10.H.5.d.ii., vii., viii., and x. above, shall be submitted for incorporation into the 5 Administrative Record. 6 III.10.H.5.e. Prior to initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees shall .7 submit to Ecology, pursuant to Permit Condition III. 10.C.9.f., the following as specified 8 below for incorporation into Attachment 51, Appendix 9.18 of this Permit, except Permit 9 Condition III.10.H.5.e.i., which will be incorporated into Attachment 51, Chapter 6.0 of this 10 Permit. All information provided under this permit condition must be consistent with 11 information provided pursuant to Permit Conditions III.10.H.5.b., c., d., e., and f., 12 III.10.C.3.e. and III.10.C.11.b., as approved by Ecology: 13 Integrity assessment program and schedule for the LAW Vitrification System shall 14 address the conducting of periodic integrity assessments on the LAW Vitrification 15 System over the life of the system, as specified in Permit Condition III.10.H.5.b.ix. and 16 WAC 173-303-640(3)(b), in accordance with WAC 173-303-680, and descriptions of 17 procedures for addressing problems detected during integrity assessments. The schedule 18 19 must be based on past integrity assessments, age of the system, materials of construction, characteristics of the waste, and any other relevant factors [WAC 173-7 20 640(3)(b), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(B) 21 Detailed plans and descriptions, demonstrating the leak detection system is operated so 22 that it will detect the failure of either the primary or secondary containment structure or 23 the presence of any release of dangerous and/or mixed waste or accumulated liquid in 24 the secondary containment system within twenty-four (24) hours [WAC 173-303-25 640(4)(c)(iii)]. Detection of a leak of at least 0.1 gallons per hour within twenty-four 26 (24) hours is defined as being able to detect a leak within twenty-four (24) hours. Any 27 exceptions to this criteria must be approved by Ecology in accordance with WAC 173-28 303-680, WAC 173-303-640(4)(c)(iii), and WAC 173-303-806(4)(i)(i)(b). 29 Detailed operational plans and descriptions, demonstrating that spilled or leaked waste 30 and accumulated liquids can be removed from the secondary containment system within 31 twenty-four (24) hours [WAC 173-303-806(4)(i)(i)(B)]. 32 Descriptions of operational procedures demonstrating appropriate controls and practices 33 are in place to prevent spills and overflows from the LAW Vitrification System or 34 containment systems in compliance with WAC 173-303-640(5)(b)(i) through (iii), in 35 accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(B); 36 Description of procedures for investigation and repair of the LAW Vitrification System 37 [WAC 173-303-640(6) and WAC 173-303-640(7)(e) and (f), in accordance with WAC 38 173-303-680, WAC 173-303-320, WAC 173-303-806(4)(a)(v), and WAC 173-303-39 806(4)(a)(ii)(B)].

Expiration Date: September 27, 2004

Page 117 of 210

Updated Chapter 4.0, Narrative Description, Tables and Figures as identified in Permit

3 4		Tables III.10.H.A and III.10.H.B, as modified pursuant to Permit Condition III.10.H.5.e.x. and updated to identify routinely non-accessible LAW Vitrification subsystems.
5 6 7	vii.	Description of procedures for management of ignitable and reactive, and incompatible dangerous and/or mixed waste as specified in WAC 173-303-640(9) and (10), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(B).
8 9	yiif.	A description of the tracking system used to track dangerous and/or mixed waste generated throughout the LAW Vitrification system, pursuant to WAC 173-303-380.
10 11 12 13 14 15 16 17 18 19 20 21	ix	Permit Tables III.10.H.C and III.10.I.C shall be completed for LAW Vitrification System process and leak detection system monitors and instruments (to include, but not be limited to: instruments and monitors measuring and/or controlling flow, pressure, temperature, density, pH, level, humidity, and emissions) to provide the information as specified in each column heading. Process and leak detection system monitors and instruments for critical systems as specified in Attachment 51, Appendix 2.0 and as updated pursuant to Permit Condition III.10.C.9.b., and for operating parameters as required to comply with Permit Condition III.10.C.3.e.iii. shall be addressed. Process monitors and instruments for non-waste management operations (e.g., utilities, raw chemical storage, non-contact cooling waters, etc.) are excluded from this permit condition [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(v)];
22 · 23	х.	Permit Tables III.10.H.A and III.10.I.A amended as follows [WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(A) through (B)]:
24 25 26		A. Under column 1, update and complete list of dangerous and mixed waste LAW Vitrification System sub-systems, including plant items that comprise each system (listed by item number).
27		B. Under column 2, update and complete system designations.
28 29 30		C. Under column 3, replace the 'Reserved' with Attachment 51, Appendix 9.0 subsections (e.g., 9.1, 9.2, etc.) designated in Permit Conditions III.10.H.5.b., c., and d. specific to LAW Vitrification System sub-system as listed in column 1.
31 32		D. Under column 4, update and complete list of narrative description, tables, and figures.
33	III.10.H.5.f. One	hundred and eighty (180) days prior to initial receipt of dangerous and/or mixed waste in

the WTP Unit, the Permittees shall submit for review and receive approval for incorporation into Attachment 51, Appendix 9.15 of this Permit, a Demonstration Test Plan for the LAW Vitrification System to demonstrate that the LAW Vitrification Systems meets the performance standards specified in Permit Condition III.10.H.1.b. In order to incorporate the Demonstration Test Plan for the LAW Vitrification System into Attachment 51, Appendix 9.15, Permit Condition III.10.C.2.g. process will be followed. The Demonstration Test Plan shall include, but not be limited to, the following information. The Demonstration Test Plan shall also be consistent with the information provided pursuant to Permit Conditions

34

35

36

37

38 39

40

Permit Number: WA7890008967 Modification to Revision 7
Expiration Date: September 27, 2004
Page 118 of 210

	1 · 2		III.10.H.5.b., c., d., and e., III.10.C.3.e., and III.10.C.11.b., as approved by Ecology and consistent with the schedule described in Attachment 51, Appendix 1.0 of this Permit. The
	3 4 5		documentation required pursuant to Permit Condition III.10.H.5.f.x., in addition to being incorporated into Attachment 51, Appendix 9.15, shall be incorporated by reference in Attachment 51, Chapter 6.0 of this Permit.
	6 7 8 9 10 11		Notes: (1) The following should be consulted to prepare this Demonstration Test Plan: "Guidance on Setting Permit Conditions and Reporting Trial Burn Results Volume II of the Hazardous Waste Incineration Guidance Series," (EPA/625/6-89/019) and Risk Burn Guidance For Hazardous Waste Combustion Facilities," (EPA-R-01-001, July 2001), WAC 173-303-807(2), WAC 173-303-670(5), WAC-173-303-670(6), 40 CFR §63.1207(f)(2), 40 CFR §63.1209, and Appendix to 40 CFR Part 63 EEE.
	12 13 14		(2) Cross-referencing to the information provided pursuant to permit Conditions III.H.5.b., c., d., e., and III.10.C.3.e.v., as approved by Ecology, that are redundant to elements of the Demonstration Test Plan for the LAW Vitrification System is acceptable.
	15 16 17 18 19		i. Analysis of each feed-stream to be fed during the demonstration test, including dangerous waste, glass formers and reductants, process streams (e.g., volumes of air leakage including, control air, process air, steam, sparge bubbler air, air in-leakage from melter cave, and gases from LAW Vitrification Vessel Ventilation System, process water, etc.) that includes:
٠	20 21		A. Levels of ash, metals, total chlorine (organic and inorganic), other halogens and radionuclide surrogates;
	22		B. Description of the physical form of the feed-streams;
	23 24	1	 C. An identification and quantification of organics that are present in the feed-stream, including constituents proposed for DRE demonstration;
	25 26 27 28 29 30		A comparison of the proposed demonstration test feed streams to the mixed waste feed envelopes to be processed in the melters must be provided that documents that the proposed demonstration test feed streams will serve as worst case surrogates for organic destruction, formation of products of incomplete oxidation, and metals, total chlorine (organic and inorganic), other halogens, particulate formation, and radionuclides.
	31 32 33 34 35 36		ii. Specification of trial principal organic dangerous constituents (PODCs) for which destruction and removal efficiencies are proposed to be calculated during the demonstration test and for inclusion in Permit Conditions III.10.H.1.b.i. and III.10.I.1.b.i. These trial PODCs shall be specified based on destructibility, concentration or mass in the waste and the dangerous waste constituents or constituents in WAC 173-303-9905;
	37 38		iii. A description of the blending procedures, prior to introducing the feed-streams into the melter, including analysis of the materials prior to blending, and blending ratios;

iv. A description of how the surrogate feeds are to be introduced for the demonstration.

This description should clearly identify the differences and justify how any of

39

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 119 of 210

1 2			erences would impact the surrogate feed introduction as representative of how mixed te feeds will be introduced;
3	v.	A d	etailed engineering description of the LAW Vitrification System, including:
4		A.	Manufacturer's name and model number for each sub-system;
5 6 7 8 9		В.	Design capacity of each sub-system including documentation (engineering calculations, manufacturer/vendor specifications, operating data, etc.) supporting projected operational efficiencies (e.g., WESP projected removal efficiency for individual metals, halogens, particulates, etc.) and compliance with performance standards specified in Permit Condition III.10.H.1.b.;
10 11 12		Ć.	Detailed scaled engineering drawings, including Process Flow Diagrams, Piping and Instrumentation Diagrams, Vessel Drawings (plan, and elevation with cross sections) and General Arrangement Drawings;
13		D.	Process Engineering Descriptions;
14 15 16 17		E.	Mass and energy balance for each projected operating condition and each demonstration test condition, including assumptions and formulas used to complete the mass and energy balance, so that they can be independently verified for incorporation into the Administrative Record;
18 19		F.	Engineering Specifications/data sheets (materials of construction, physical and chemical tolerances of equipment, and fan curves);
20 21 22		G.	Detailed Description of Automatic Waste Feed Cutoff System addressing critical operating parameters for all performance standards specified in Permit Condition III.10.H.1.b.;
23 24 25		H .	Documentation to support compliance with performance standards specified in Permit Condition III.10.H.1.b., including engineering calculations, test data, and manufacturer/vendor's warranties, etc.;
26 27		I.	Detailed description of the design, operation, and maintenance practices for air pollution control system;
28 29		J.	Detailed description of the design, operation, and maintenance practices of any stack gas monitoring and pollution control monitoring system;
30 31 32 33 34 35 36 37		К.	Documentation based on current WTP Unit design either confirming the Permittees' demonstration that it is not technically appropriate to correct standards listed in Permit Conditions III.H.1.b.ii. through III.H.1.b.ix. to seven (7) percent oxygen, or a request, pursuant to Permit Conditions III.10.C.9.e. and III.10.C.9.f., to update Permit Conditions III.H.1.b.ii. through III.H.1.b.ix., III.I.b.ii. through III.H.1.b.ix., III.I.b.ii. through III.I.D.I.C., III.10.I.F., III.10.I.C., III.10.I.F. and Attachment 51, Appendix 9.0 to reflect the addition of an oxygen monitor and the correction of the standards to seven percent (7%) oxygen.
38 39	vi.		ailed description of sampling and monitoring procedures including sampling and itoring locations in the system, the equipment to be used, sampling and monitoring

Expiration Date: September 27, 2004

Page 120 of 210

frequency, and planned analytical procedures for sample analysis including, but not limited to:

- A. A short summary narrative description of each stack sample method should be included within the main body of the demonstration test plan, which references an appendix to the plan that would include for each sampling train: (1) detailed sample method procedures, (2) sampling train configuration schematic, (3) sampling recovery flow sheet, (4) detailed analytical method procedures, and (5) sampling preparation and analysis flow sheet. The detailed procedures should clearly flag where the method has provided decision points (e.g., choices of equipment materials of construction, choices of clean-up procedures or whether additional clean-up procedures will be incorporated, whether pretest surveys or laboratory validation work will be performed, enhancements to train to accommodate high moisture content in stack gas, etc.) and what is being proposed along with the basis for the decision.
- B. A short summary narrative description of the feed and residue sampling methods should be included within the main body of the demonstration test plan, which references an appendix that would include for each sample type: (1) detailed sample method procedures, (2) sampling recovery/compositing procedures, and (3) detailed analytical method procedures. The detailed procedures should clearly flag where the method has provided decision points (e.g., choices of equipment materials of construction, choices of clean-up procedures or whether additional clean-up procedures will be incorporated, whether pretest surveys or laboratory validation work will be performed, etc.) and what is being proposed along with the basis for the decision
- vii. A detailed test schedule for each condition for which the demonstration test is planned, including projected date(s), duration, quantity of dangerous waste to be fed, and other relevant factors;
- viii. A detailed test protocol including, for each test condition, the ranges of feed-rate for each feed system, and all other relevant parameters that may affect the ability of the LAW Vitrification System to meet performance standards specified in Permit Condition III.10.H.1.b.;
- ix. A detailed description of planned operating conditions for each demonstration test condition, including operating conditions for shakedown, demonstration test, post-demonstration test and normal operations. This information shall also include submittal of Permit Tables III.10.H.D, III.10.H.F, III.10.I.D, and III.10.I.F completed with the information as specified in each column heading for each LAW Vitrification System waste feed cutoff parameter and submittal of supporting documentation for Permit Tables III.10.H.D, III.10.H.F, III.10.I.D, and III.10.I.F set-point values;
- x. The test conditions proposed must demonstrate meeting the performance standards specified in Permit Condition III.10.H.1.b. with the simultaneous operation of all three (3) melters at capacity and input from the LAW Vitrification Vessel Ventilation System at capacity to simulate maximum loading to the LAW Vitrification System off-gas

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 121 of 210

2				extent that operation of one (1) melter or two (2) melters can not be sustained within the
3 4 5 6				operating parameter range established at this maximum load, additional demonstration test conditions must be included in the plan and performed to establish operating parameter ranges for each proposed operating mode while demonstrating meeting the performance standards specified in Permit Condition III.10.H.1.b.;
7 8 9			xi.	Detailed description of procedures for start-up and shutdown of waste feed and controlling emissions in the event of an equipment malfunction, including off-normal and emergency shutdown procedures;
10		:	xii.	A calculation of waste residence time;
11 12	· *			Any request to extrapolate metal feed-rate limits from Demonstration Test levels must include:
13 14 15		•		A. A description of the extrapolation methodology and rationale for how the approach ensures compliance with the performance standards as specified in Permit Condition III.10.H.1.b.
16 17				B. Documentation of the historical range of normal metal feed-rates for each feedstream.
18 19 20 21				C. Documentation that the level of spiking recommended during the demonstration test will mask sampling and analysis imprecision and inaccuracy to the extent that extrapolation of feed-rates and emission rates from the Demonstration Test data will be as accurate and precise as if full spiking were used.
22 23 24 25			xiv.	Documentation of the expected levels of constituents in LAW Vitrification System inputs treams including, but not limited to, waste feed, glass former and reactants, control air, process air, steam, sparge bubbler air, air in-Leakage from melter cave, gases from LAW Vitrification Vessel Ventilation System, and process water.
26 27 28			XV.	Documentation justifying the duration of the conditioning required to ensure the LAW Vitrification System had achieved steady-state operations under Demonstration Test operating conditions.
29 30 31			xvi.	Documentation of LAW Vitrification System process and leak detection system instruments and monitors as listed on Permit Tables III.10.H.C, III.10.H.F, III.10.I.C, and III.10.I.F to include:
32			. •	A. Procurement specifications;
33				B. Location used;
34				C. Range, precision, and accuracy;
35 36 37		-		D. Detailed descriptions of calibration/functionality test procedures (either method number ASTM) or provide a copy of manufacturer's recommended calibration procedures;
38 39				E. Calibration/functionality test, inspection, and routine maintenance schedules and checklists, including justification for calibration, inspection and maintenance

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 122 of 210

frequencies, criteria for identifying instruments found to be significantly out of calibration, and corrective action to be taken for instruments found to be significantly out of calibration (e.g., increasing frequency of calibration, instrument replacement, etc.);

F. Equipment instrument control logic narrative description (e.g., software functional specifications, descriptions of fail safe conditions, etc.) [WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-806(4)(i)(v)].

xvii. Outline of demonstration test report.

Table III.10.H.A - LAW Vitrification System Description

Sub-system Description Sub-system Description (Drawing Description (Drawing Nos., Specification Nos., etc.) Section 4.2.3.1; Tables 4-4 and 4-11, and Figures 4A-1, 4A-3, and 4A-20 of Attachment 51, Chapter 4 of this Permit		集 5 			
LAW Melters 1,2, & 3	Sub-system Description		Description (Drawing Nos., Specification	Narrative Description, Tables and Figures	
21 of Attachment 51, Chapter 4 of this Permit	Melter Feed ^a Systems-Melter 1,2, & 3		RESERVED	Figures 4A-1, 4A-3, and 4A-20 of	N/A
1,2, & 3 Primary & Secondary Film Coolers- Melter 1, 2, & 3 Melter 1 & 2 Submerged Bed Scrubbers LAW-MK-LOP-SCB- 00001 & -00002, Melter 1 & 2 SBS Condensate Vessels LAW-MV- LOP-VSL-00001 & & -00002 & . Melter 1, 2, & 3 Melter 1, 2, & 3 Melter 1, 2, & 3 Of this Permit Section 4.2.3.3 and Figure 4A-21 of Attachment 51, Chapter 4 of this Permit Section 4.2.3.3; Tables 4-4 and 4-11, and Figure 4A-22 of Attachment 51, Chapter 4 of this Permit LOP-SCB-00001 = 4,948 LOP-SCB-00002 = 4,948 Melter 1, 2, & 3	LAW Melters 1,2, & 3	LMP	RESERVED	21 of Attachment 51, Chapter 4 of this	<u>N/A</u>
Melter 1, 2, & 3 Attachment 51, Chapter 4 of this Permit Melter 1 & 2 Submerged Bed LOP Scrubbers LAW-MK-LOP-SCB- 24590-LAW Mo001 & -00002, Melter 1 & 2 SBS 2 SBS Condensate Vessels LAW-MV- M6-LOP-P0001 LOP-VSL-00001 & -00002 & Scrubbers/Condensate Vessels a- Melter 1, 2, & 3 MR-LOP-P0001002 Melter 1, 2, & 3 MKD-LOP-P0002 MCD-LOP-P0004		LMP	RESERVED	I am a first the	<u>N/A</u>
Scrubbers LAW-MK-LOP-SCB- 00001 & -00002, Melter 1 & 2 SBS Condensate Vessels LAW-MV- LOP-VSL-00001 & -00002 & -00002 & -00002 & -00002 & -00002 & -00001001 -00001 & -00001001 Submerged Bed Scrubbers/Condensate Vessels a-Melter 1, 2, & 3 -MK-LOP-P0001002 & -00001003 MKD-LOP-P0001 -00002 & -00002 & -00002 -MKD-LOP-P0001 -00002 & -00002 -MKD-LOP-P0001 -00002 & -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001 -00002 -MKD-LOP-P0001		LOP	RESERVED		
	Scrubbers LAW-MK-LOP-SCB- 00001 & -00002, Melter 1 & 2 SBS Condensate Vessels LAW-MV- LOP-VSL-00001 & -00002 & Submerged Bed Scrubbers/Condensate Vessels a-	LOP	24590-LAW -M6-LOP-P0001 -M6-LOP-P0002 -MK-LOP-P0001001 -MK-LOP-P0001003 -MK-LOP-P0002 -MKD-LOP-P0004	Figure 4A-22 of Attachment 51, Chapter 4 of	LOP-SCB-00001 = 4,948 LOP-SCB-00002 = 4,948

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 124 of 210

Sub-system Description	Sub-system Designation	Engineering Description (Drawing Nos., Specification Nos., etc.)	Narrative Description, Tables and Figures	Maximum Capacity (gallons)
Wet electrostatic Precipitators- Melter 1, 2, & 3	LOP	RESERVED	Section 4.2.3.3 and Figure 4A-22 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
High Efficiency Particulate Air Filters	LVP	RESERVED	Section 4.2.3.3 and Figure 4A-23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Thermal Catalytical Oxidation Unit	LVP	RESERVED	Section 4.2.3.3 and Figure 4A-23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Selective Catalytical Reduction Units	LVP	RESERVED	Section 4.2.3.3 and Figure 4A-23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Caustic Scrubber/Blowdown Vessel	LVP	RESERVED	Section 4.2.3.3 and Figure 4A-23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Electric Heaters	LVP	RESERVED	Section 4.2.3.3 and Figure 4A-23 of Attachment 51, Chapter 4 of this Permit	N/A
Heat Exchangers	LVP	RESERVED	Section 4.2.3.3 and Figure 4A-23 of Attachment 51, Chapter 4 of this Permit	N/A
Pumps	LVP	RESERVED	Section 4.2.3.3 and Figure 4A-23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Exhaust Fans	LVP	RESERVED	Section 4.2.3.3 of Attachment 51, Chapter 4 of this Permit	N/A
Mist Eliminators	LVP	RESERVED	Section 4.2.3.3 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
LAW Stack	LVP	RESERVED	Section 4.2.3.3 and Figure 4A-23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>

Permit Number: WA7890008967

Modification to Revision 7
Expiration Date: September 27, 2004
Page 125 of 210

^a Requirements pertaining to the tanks in LAW Vitrification System Melter Feed System, Submerged Bed Scrubbers/Condensate Vessels, and Caustic Scrubber/Blowdown Vessel are specified in Permit Section III.10.E.

Permit Number: WA7890008967 Modification to Revision 7
Expiration Date: September 27, 2004
Page 126 of 210

Table III.10.H.B.-LAW Vitrification System Secondary Containment Systems Including Sumps and Floor Drains

Sump/Floor Drain I.D.# & Room Location	Maximum Sump Capacity (gallons)	Sump Dimensions (feet) & Materials of Construction	Engineering Description (Drawing Nos., Specification Nos.,
	e.		etc.)
RESERVED	RESERVED	RESERVED	RESERVED

2 3

Table III.10.H.C - LAW Vitrification System Process and Leak Detection System Instruments and Parameters

Sub-system Locator and Name (including	Control Parameter	Type of Measuring or Leak Detection Instrument	Location of Measuring Instrument (Tag No.)	Instrument Range	Failure State	Expected Range	Instrument Accuracy	Instrument Calibration Method No, and Range
P&ID)								
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

Permit Number: WA7890008967
Modification to Revision 7

Expiration Date: September 27, 2004

Page 127 of 210

Table III.10.H.D - Maximum Feed-rates to LAW Vitrification System (RESERVED)

Description of Waste Shakedown 1 and Post Demonstration Test

Dangerous and Mixed Waste Feed-rate

Total Chlorine/Chloride Feed-rate

Total Metal Feed-rates

Total Ash Feed-rate

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 128 of 210

Table III.10.H.E - LAW Vitrification System Estimated Emission Rates (RESERVED)

	Chemic	als			CAS Numb	er		Emission Rates			
. ,				·	· · · · · · · · · · · · · · · · · · ·				(grar	ns /second)	
	enselven en en de Militaria per la Prophibilita de la consent de la del Carlo de la consent de la del Carlo de		· .								
Seg.					i aw Nis		in .	* * * * * * * * * * * * * * * * * * *			

2

5

6

8

9

10 11

12

13

14

15

16

17

18

19

20

21

TABLE III.10.H.F - LAW Vitrification System Waste Feed Cutoff Parameters* (RESERVED)

Sub-system Designation	Instrument Tag Number	Parameter Description	Setpoints During Shakedown 1 and Post Demonstration Test	Setpoints During Shakedown 2 and Demonstration Test
		/		

^{*} A continuous monitoring system shall be used as defined in Permit Section III.10.C.1.

III.10.I LAW Vitrification System - Long Term Miscellaneous Thermal Treatment Unit

For purposes of Permit Section III.10.I, where reference is made to WAC 173-303-640, the following substitutions apply: substitute the terms "LAW Vitrification System" for "tank system(s)," "sub-system(s)" "sub-system equipment" for "ancillary equipment," and "sub-system(s) or sub-system equipment of a LAW Vitrification System" for "component(s)," in accordance with WAC 173-303-680.

III.10.I.1 Requirements For LAW Vitrification System Beginning Normal Operation

Prior to commencing normal operations provided in Permit Section III.10.I, all requirements in Permit Section III.10.H shall have been met by the Permittees and approved by Ecology, including the following: The LAW Vitrification System Demonstration Test results and the revised Final Risk Assessment provided for in Permit Condition III.10.C.11.c. or III.10.C.11.d. and Permit Section III.10.H, shall have been evaluated and approved by Ecology, Permit Tables III.10.I.D and F, as approved/modified pursuant to Permit Condition III.10.H.5., shall have been completed, submitted and approved pursuant to Permit Condition III.10.H.3.d.v. and Permit Table III.10.I.E, as approved/modified pursuant to

¹ Maximum Feed-rate shall be set based on not exceeding any of the constituent (e.g., ash, metals, and chlorine/chloride) feed limits specified on Table III.10.H.D. of this Permit

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 129 of 210

	1 2		Permit Condition III.10.H.5, shall have been completed, submitted and approved pursuant to Permit Condition III.10.C.11.c. or d.
	3 4	III.10.I.1.a.	Construction and Maintenance [WAC 173-303-640, in accordance with WAC 173-303-680(2) and (3) and WAC 173-303-340].
	5 6 7 8		i. The Permittees shall maintain the design and construction of the LAW Vitrification System as specified in Permit Condition III.10.I.1., Attachment 51, Chapter 4.0 of this Permit, and Attachment 51, Appendices 9.1 through 9.17 of this Permit, as approved pursuant to Permit Conditions III.10.H.5.a. through d. and III.10.H.5.f.
	9 10 11 12		ii. The Permittees shall maintain the design and construction of all containment systems for the LAW Vitrification System, as specified in Attachment 51, Chapter 4.0 of this Permit, and Attachment 51, Appendices 9.2 and 9.4 through 9.14 of this Permit, as approved pursuant to Permit Conditions III.10.H.5.a. through d.
	13 14 15		iii. Modifications to approved design, plans, and specifications in Attachment 51 of this Permit for the LAW Vitrification System shall be allowed only in accordance with Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g., III.10.C.9.d., e., and h.
	16 17 18 19 20		iv. The Permittees shall ensure all certifications required by specialists (e.g., independent, qualified, registered professional engineer; registered professional engineer; independent corrosion expert; independent, qualified installation inspector; installation inspector; etc.) use the following statement or equivalent pursuant to Permit Condition III.10.C.10:
As a second	21 22 23 24 25 26 27		"I, (Insert Name) have (choose one or more of the following: overseen, supervised, reviewed, and/or certified) a portion of the design or installation of a new LAW Vitrification system or component located at (address), and owned/operated by (name(s)). My duties were: (e.g., installation inspector, testing for tightness, etc.), for the following LAW Vitrification System components (e.g., the venting piping, etc.), as required by the Dangerous Waste Regulations, namely, WAC 173-303-640(3) (applicable paragraphs [i.e., (a) through (g)], in accordance with WAC 173-303-680.
(· ·	28 29 30 31 32 33		"I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment."
	34 35 36 37 38 39 40		v. The Permittees shall ensure periodic integrity assessments are conducted on the LAW Vitrification System listed in Permit Table III.10.I.A, as approved/modified pursuant to Permit Condition III.10.H.5, over the term of this Permit in accordance with WAC 173-303-680(2) and (3) as specified in WAC 173-303-640(3)(b), following the description of the integrity assessment program and schedule in Attachment 51, Chapter 6.0 of this Permit, as approved pursuant to Permit Conditions III.10.H.5.e.i. and III.10.C.5.c. Results of the integrity assessments shall be included in the WTP Unit operating record

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 130 of 210

1 2		until ten (10) years after post closure, or corrective action is complete and certified, whichever is later.
3 4 5 6	vi.	The Permittees shall address problems detected during the LAW Vitrification System integrity assessments specified in Permit Condition III.10.I.1.a.v. following the description of the integrity assessment program in Attachment 51, Chapter 6.0 of this Permit, as approved pursuant to Permit Conditions III.10.H.5.e.i. and III.10.C.5.c.
7 8 9 10	vii.	All process monitors/instruments as specified in Permit Table III.10.I.F, as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.H.3.d.v., shall be equipped with operational alarms to warn of deviation, or imminent deviation from the limits specified in Permit Table III.10.I.F.
11 12 13 14 15	viii.	The Permittees shall install and test all process and leak detection system monitors/instruments, as specified in Permit Tables III.10.I.C and III.10.I.F, as approved/modified pursuant to Permit Condition III.10.H.5 and III.10.H.3.d.v., in accordance with Attachment 51, Appendices 9.1, 9.2, and 9.14 of this Permit, as approved pursuant to Permit Conditions III.10.H.5.d.x. and III.10.H.5.fxvi.
16 17 18	ix.	No dangerous and/or mixed waste shall be treated in the LAW Vitrification System unless the operating conditions, specified under Permit Condition III.10.I.1.c. are complied with.
19 20 21 22 23 24 25	x .	The Permittees shall not place dangerous and/or mixed waste, treatment reagents, or other materials in the LAW Vitrification System if these substances could cause the sub-system, sub-system equipment, or the containment system to rupture, leak, corrode, or otherwise fail [WAC 173-303-640(5)(a), in accordance with WAC 173-303-680(2)]. This condition is not applicable to corrosion of LAW Vitrification System sub-system or sub-system equipment that are expected to be replaced as part of normal operations (e.g., melters).
26 27 28 29 30 31	xi .	The Permittees shall operate the LAW Vitrification System to prevent spills and overflows using description of controls and practices as required under WAC 173-303-640(5)(b), described in Permit Condition III.10.C.5 and Attachment 51, Appendix 9.18 of this Permit, as approved pursuant to Permit Condition III.10.H.5.e. [WAC 173-303-640(5)(b), in accordance with WAC 173-303-680(2) and (3), and WAC 173-303-806(4)(c)(ix)].
32 33 34 35 36 37 38 39 40 41	xii.	For routinely non-accessible LAW Vitrification System sub-systems, as specified in Attachment 51, Chapter 4.0 of this Permit, as updated pursuant to Permit Condition III.10.H.5.e.vi., the Permittees shall mark all routinely non-accessible LAW Vitrification System sub-systems access points with labels or signs to identify the waste contained in each LAW Vitrification System sub-system. The label, or sign, must be legible at a distance of at least fifty (50) feet and must bear a legend which identifies the waste in a manner which adequately warns employees, emergency response personnel, and the public of the major risk(s) associated with the waste being stored or treated in the LAW Vitrification System sub-systems. For the purposes of this permit condition, "routinely non-accessible" means personnel are unable to enter these areas

Permit Number: WA7890008967 Modification to Revision 7

Expiration Date: September 27, 2004

Page 131 of 210

while waste is being managed in them [WAC 173-303-640(5)(d), in accordance with 2 WAC 173-303-680(2)]. 3 xiii. For the LAW Vitrification System sub-systems not addressed in Permit Condition III.10.I.1.a.xii., the Permittees shall mark these LAW Vitrification System sub-systems 4 holding dangerous and/or mixed waste with labels or signs to identify the waste 5 6 contained in the LAW Vitrification System sub-systems. The labels, or signs, must be 7 legible at a distance of at least fifty (50) feet and must bear a legend which identifies the waste in a manner which adequately warns employees, emergency response 8 personnel, and the public of the major risk(s) associated with the waste being stored or 9 10 treated in the LAW Vitrification System sub-systems [WAC 173-303-640(5)(d), in accordance with WAC 173-303-680(2)]. 11 xiv. The Permittees shall ensure that the secondary containment systems for the LAW .12 13 Vitrification System sub-systems listed in Permit Tables III.10.I.A and III.10.I.B, as approved/modified pursuant to Permit Condition III.10.H.5, are free of cracks or gaps 14 to prevent any migration of dangerous and/or mixed waste or accumulated liquid out of 15 the system to the soil, groundwater, or surface water at any time during use of the LAW 16 Vitrification System sub-systems. Any indication that a crack or gap may exist in the 17 18 containment systems shall be investigated and repaired in accordance with Attachment 51, Appendix 9.18 of this Permit, as approved pursuant to Permit Condition 19 III.10.H.5.e.v. [WAC 173-303-640(4)(b)(i), WAC 173-303-640(4)(e)(i)(C), and WAC 20 173-303-640(6), in accordance with WAC 173-303-680(2) and (3), WAC 173-303-21 806(4)(i)(i)(B), and WAC 173-303-320]. 22 23 xv. The Permittees must immediately, and safely, remove from service any LAW Vitrification System or secondary containment system which through an integrity 24 assessment is found to be "unfit for use" as defined in WAC 173-303-040, following 25 Permit Condition III.10.I.1.a.xvii. A through D, and F. The affected LAW Vitrification 26 27 System or secondary containment system must be either repaired or closed in accordance with Permit Condition III.10.I.1.a.xvii.E [WAC 173-303-640(7)(e) and (f) 28 and WAC 173-303-640(8), in accordance with WAC 173-303-680(3)]. 29 xvi. An impermeable coating, as specified in Attachment 51, Appendices 9.4, 9.5, 9.7, 9.9, 30 9.11, and 9.12 of this Permit, as approved pursuant to Permit Condition III.10.H.5.b.v., 31 shall be maintained for all concrete containment systems and concrete portions of 32 containment systems for the LAW Vitrification System sub-systems listed in Permit 33 Tables III.10.I.A and III.10.I.B, as approved/modified pursuant to Permit Condition 34 35 III.10.H.5 (concrete containment systems that do not have a liner, pursuant to WAC 173-303-640(4)(e)(i), in accordance with WAC 173-303-680(2), and have construction 36 joints, shall meet the requirements of WAC 173-303-640(4)(e)(ii)(C), in accordance 37 38 with WAC 173-303-680(2). The coating shall prevent migration of any dangerous and/or mixed waste into the concrete. All coatings shall meet the following 39 performance standards: 40

41

42

A. The coating must seal the containment surface such that no cracks, seams, or other avenues through which liquid could migrate are present;

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004

Page 132 of 210

1 2		B. The coating must be of adequate thickness and strength to withstand the normal operation of equipment and personnel within the given area such that degradation
3 4		or physical damage to the coating or lining can be identified and remedied before dangerous and mixed waste could migrate from the system; and
5 6 7 8		C. The coating must be compatible with the dangerous and/or mixed waste, treatment reagents, or other materials managed in the containment system [WAC 173-303-640(4)(e)(ii)(D), in accordance with WAC 173-303-680(2) and (3) and WAC 173-303-806(4)(i)(i)(A)].
9 10 11 12 13 14 15 16 17	xvii.	The Permittees shall inspect all secondary containment systems for the LAW Vitrification System sub-systems listed in Permit Tables III.10.I.A and III.10.I.B, as approved/modified pursuant to Permit Condition III.10.H.5, in accordance with the Inspection Schedule specified in Attachment 51, Chapter 6.0 of this Permit, as approved pursuant to Permit Conditions III.10.H.5.e.i. and III.10.C.5.c., and take the following actions if a leak or spill of dangerous and/or mixed waste is detected in these containment systems [WAC 173-303-640(5)(c) and WAC 173-303-640(6), in accordance with WAC 173-303-680(2) and (3), WAC 173-303-320, and WAC 173-303-806(4)(i)(i)(B)].
18 19		A. Immediately, and safely, stop the flow of dangerous and/or mixed waste into the LAW Vitrification System sub-systems or secondary containment system.
20		B. Determine the source of the dangerous and/or mixed waste.
21 22 23 24		C. Remove the waste from the containment area in accordance with WAC 173-303-680(2) and (3) as specified in WAC 173-303-640(7)(b). The waste removed from containment areas of the LAW Vitrification System sub-systems shall be, as a minimum, managed as dangerous and/or mixed waste.
25 26 27 28 29 30		D. If the cause of the release was a spill that has not damaged the integrity of the LAW Vitrification System sub-system, the Permittees may return the LAW Vitrification System sub-system to service in accordance with WAC 173-303-680(2) and (3) as specified in WAC 173-303-640(7)(e)(ii). In such case, the Permittees shall take action to ensure the incident that caused the dangerous and/or mixed waste to enter the containment system will not reoccur.
31 32 33 34 35		E. If the source of the dangerous and/or mixed waste is determined to be a leak from the primary LAW Vitrification System into the secondary containment system, or the system is unfit for use as determined through an integrity assessment or other inspection, the Permittees shall comply with the requirements of WAC 173-303-640(7) and take the following actions:
36 37 38	eta in	1. Close the LAW Vitrification System sub-system following procedures in WAC 173-303-640(7)(e)(i), in accordance with WAC 173-303-680 and Attachment 51, Chapter 11.0 of this Permit, as approved pursuant to Permit

Condition III.10.C.8; or

Repair and re-certify (in accordance with WAC 173-303-810(13)(a), as

modified pursuant to Permit Condition III.10.I.1.a.iii.) the LAW Vitrification

39

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 133 of 210

1 2 3 4			System in accordance with Attachment 51, Appendix 9.18 of this Permit, as approved pursuant to Permit Condition III.10.H.5.e.v., before the LAW Vitrification System is placed back into service [WAC 173-303-640(7)(e)(iii and WAC 173-303-640(7)(f), in accordance with WAC 173-303-680].
5 6 7			F. The Permittees shall document in the WTP Unit operating record actions/procedures taken to comply with A through E above, as specified in WAC 173-303-640(6)(d), in accordance with WAC 173-303-680(2) and (3).
8 9 10			G. In accordance with WAC 173-303-680(2) and (3), the Permittees shall notify and report releases to the environment to Ecology, as specified in WAC 173-303-640(7)(d).
11 12 13 14 15 16 17 18		xviii	i. If liquids (e.g., dangerous and/or mixed waste, leaks and spills, precipitation, fire water, liquids from damaged or broken pipes) cannot be removed from the secondary containment system within twenty-four (24) hours, Ecology will be verbally notified within twenty-four (24) hours of discovery. The notification shall provide the information in A, B, and C, listed below. The Permittees shall provide Ecology with a written demonstration within seven (7) business days, identifying at a minimum [WAC 173-303-640(4)(c)(iv) and WAC 173-303-640(7)(b)(ii), in accordance with WAC 173-303-680(3) and WAC 173-303-806(4)(i)(i)(B)]:
19			A. Reasons for delayed removal;
20 21			B. Measures implemented to ensure continued protection of human health and the environment;
22			C. Current actions being taken to remove liquids from secondary containment.
23 24 25 26 27 28		xix.	All air pollution control devices and capture systems in the LAW Vitrification System shall be maintained and operated at all times in a manner so as to minimize the emissions of air contaminants and to minimize process upsets. Procedures for ensuring that the air pollution control devices and capture systems in the LAW Vitrification System are properly operated and maintained so as to minimize the emission of air contaminants and process upsets shall be established.
29 30		XX.	In all future narrative permit submittals, the Permittees shall include LAW Vitrification sub-system names with the sub-system designation.
31 32 33 34		xxi.	For any portion of the LAW Vitrification System that has the potential for formation and accumulation of hydrogen gases, the Permittees shall operate the portion to maintain hydrogen levels below the lower explosive limit [WAC 173-303-815(2)(b)(ii)].
35 36 37 38 39			For each LAW Vitrification System sub-system holding dangerous and/or mixed waste that are acutely or chronically toxic by inhalation, the Permittees shall operate the system to prevent escape of vapors, fumes, or other emissions into the air [WAC 173-303-806(4)(i)(i)(B) and WAC 173-303-640(5)(e), in accordance with WAC 173-303-680].
40	TTT 10 7 1 1	nc.	

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 134 of 210

1 2		į i.	The LAW Vitrification System must achieve a destruction and removal efficiency (DRE) of 99.99% for the principal organic dangerous constituents (PODCs) listed
3 4			below [40 CFR §63.1203(c)(1) and 40CFR §63.1203(c)(2), in accordance with WAC 173-303-680(2)]:
5			RESERVED
6 7			DRE in this permit condition shall be calculated in accordance with the formula given below:
8			DRE= $[1-(W_{out}/W_{in})] \times 100\%$
9		•	Where:
10 11			W _{in} =mass feedrate of one principal organic dangerous constituent (PODC) in a waste feedstream; and
12 13			W _{out} =mass emission rate of the same PODC present in exhaust emissions prior to release to the atmosphere.
14 15 16		ii.	Particulate matter emissions from the LAW Vitrification System shall not exceed 34 mg/dscm (0.015 grains/dscf) [40 CFR §63.1203(b)(7), in accordance with WAC 173-303-680(2)];
17 18 19		iii.	Hydrochloric acid and chlorine gas emissions from the LAW Vitrification System shall not exceed 21 ppmv, combined [40 CFR §63.1203(b)(6), in accordance with WAC 173-303-680(2)];
20 21 22		iv.	Dioxin and Furan TEQ emissions from the LAW Vitrification System shall not exceed 0.2 nanograms (ng)/dscm, [40 CFR §63.1203(b)(1), in accordance with WAC 173-303-680(2)];
23 24		v .	Mercury emissions from the LAW Vitrification System shall not exceed 45 μg/dscm [40 CFR §63.1203(b)(2), in accordance with WAC 173-303-680(2)];
25 26 27		vi.	Lead and cadmium emissions from the LAW Vitrification System shall not exceed 120 µg/dscm, combined [40 CFR §63.1203(b)(3), in accordance with WAC 173-303-680(2)];
28 29 30		vii.	Arsenic, beryllîum, and chromium emissions from the LAW Vitrification System shall not exceed 97 µg/dscm, combined [40 CFR §63.1203(b)(4), in accordance with WAC 173-303-680(2)];
31 32 33 34	!-	viii.	Carbon monoxide (CO) emission from the LAW Vitrification System shall not exceed 100 parts per million (ppm) by volume, over an hourly rolling average (as measured and recorded by the continuous monitoring system), dry basis [40 CFR §63.1203(b)(5)(i), in accordance with WAC 173-303-680(2) and (3)];
35 36 37 38 39		ix.	Hydrocarbon emission from the LAW Vitrification System shall not exceed 10 parts per million (ppm) by volume, over an hourly rolling average (as measured and recorded by the continuous monitoring system during demonstration testing required by this Permit), dry basis and reported as propane [40 CFR §63.1203(b)(5)(ii), in accordance with WAC 173-303-680(2) and (3)];

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 135 of 210

If the emissions from the LAW Vitrification System exceed the emission rates listed in Permit Table III.10.I.E, as approved pursuant to Permit Condition III.10.C.11.c. or d., the Permittees shall perform the following actions [WAC 173-303-680(2) and (3), and WAC 173-303-815(2)(b)(ii)]: Verbally notify Ecology within twenty-four (24) hours of the discovery of exceeding the emission rate(s) as specified in Permit Condition I.E.21. Submit to Ecology additional risk information to indicate that the increased emissions impact is offset by decreased emission impact from one or more constituents expected to be emitted at the same time, and/or investigate the cause and impact of the exceedance of the emission rate(s) and submit a report of the investigation findings to Ecology within fifteen (15) days of the discovery of

exceeding the emission rate(s); and

C. Based on the notification and any additional information, Ecology may submit, in writing, direction to the Permittees to stop dangerous and/or mixed waste feed to the LAW Vitrification System and/or to submit a revised Demonstration Test Plan as a permit modification pursuant to Permit Conditions III.10.C.2.e. through g. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring.

The emission limits specified in Permit Conditions III.10.I.1.b.i. through x. above, shall be met for the LAW Vitrification System by limiting feed rates as specified in Permit Tables III.10.I.D and III.10.I.F, as approved/modified pursuant to Permit Conditions III.10.H.5. and III.10.H.3.d.v., compliance with operating conditions specified in Permit Condition III.10.I.1.c. (except as specified in Permit Condition III.10.I.1.b.xii.), and compliance with Permit Condition III.10.I.1.b.xii.;

- xi. Treatment effectiveness, feed-rates and operating rates for dangerous and/or mixed waste management units contained in the LAW Building, but not included in Permit Table III.10.I.A, as approved/modified pursuant to Permit Condition III.10.H.5, shall be as specified in Permit Sections III.10.D through F and consistent with assumptions and basis which are reflected in Attachment 51, Appendix 6.3.1 of this Permit, as approved pursuant to Permit Condition III.10.C.11.b. For the purposes of this permit condition, Attachment 51, Appendix 6.3.1 shall be superceded by Appendix 6.4.1 upon its approval pursuant to either Permit Condition III.10.C.11.c or III.10.C.11.d. [WAC 173-303-680(2) and (3), and WAC 173-303-815(2)(b)(ii)];
- xii. Compliance with the operating conditions specified in Permit Condition III.10.I.1.c., shall be regarded as compliance with the required performance standards identified in Permit Conditions III.10.I.1.b.i. through x. However, if it is determined that during the effective period of this Permit that compliance with the operating conditions in Permit Condition III.10.I.1.c. is not sufficient to ensure compliance with the performance standards specified in Permit Conditions III.10.I.1.b.i. through x., the Permit may be modified, revoked, or reissued pursuant to Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g.
- III.10.I.1.c. Operating Conditions [WAC-303-670(6), in accordance with WAC 173-303-680(2) and (3)]

Permit Number: WA7890008967
Modification to Revision 7

Explication Data: Soutamber 27, 200

Expiration Date: September 27, 2004

Page 136 of 210

The Permittees shall operate the LAW Vitrification System in accordance with Attachment 51, Chapter 4.0 of this Permit, as updated pursuant to Permit Condition III.10.H.5.e.vi. and Attachment 51, Appendix 9.18 of this Permit, as approved pursuant to Permit Condition III.10.H.5.e., and Attachment 51, Appendix 9.15 of this Permit, as approved pursuant to Permit Condition III.10.H.5.f., except as modified pursuant to Permit Conditions III.10.H.3, III.10.I.1.b.x., III.10.I.1.b.xii., III.10.I.1.h., and in accordance with and the following:

- i. The Permittees shall operate the LAW Vitrification System in order to maintain the systems and process parameters listed in Permit Tables III.10.I.C and III.10.I.F, as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.H.3.d.v., within the set-points specified in Permit Table III.10.I.F.
- ii. The Permittees shall operate the AWFCO systems, specified in Permit Table III.10.I.F, as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.H.3.d.v., to automatically cut-off and/or lock-out the dangerous and/or mixed waste feed to LAW Vitrification System when the monitored operating conditions deviate from the setpoints specified in Permit Table III.10.I.F.
- iii. The Permittees shall operate the AWFCO systems, specified in Permit Table III.10.I.F, as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.H.3.d.v., to automatically cut-off and/or lock-out the dangerous and/or mixed waste feed to LAW Vitrification System when all instruments specified in Permit Table III.10.H.F for measuring the monitored parameters fails or exceeds its span value.
- iv. The Permittees shall operate the AWFCO systems, specified in Permit Table III.10.I.F, as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.H.3.d.v., to automatically cut-off and/or lock out the dangerous waste and/or mixed waste feed to the LAW Vitrification System when any portion of the LAW Vitrification System is bypassed. The terms "bypassed" and "bypass event," as used in Permit Sections III.10.H and III.10.I, shall mean if any portion of the LAW Vitrification System is bypassed so that gases are not treated as during the Demonstration Test.
- v. In the event of a malfunction of the AWFCO systems listed in Permit Table III.10.I.F, as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.H.3.d.v., the Permittees shall immediately, manually cut-off the dangerous and/or mixed waste feed to the LAW Vitrification System. The Permittees shall not restart the dangerous and/or mixed waste feed until the problem causing the malfunction has been identified and corrected.
- vi. The Permittees shall manually cut-off the dangerous and/or mixed waste feed to the LAW Vitrification System when the operating conditions deviate from the limits specified in Permit Condition III.10.I.1.c.i., unless the deviation automatically activates the waste feed cut-off sequence specified in Permit Conditions III.10.I.1.c.ii., iii., and/or iv.
- vii. If greater than thirty (30) dangerous and/or mixed waste feed cut-off, combined, to the LAW Vitrification System occur due to deviations from Permit Table III.10.I.F, as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.H.3.d.v., within a sixty (60) day period, the Permittees shall submit a written report to Ecology within

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 137 of 210

36

37 38

39

five (5) calendar days of the thirty-first exceedance, including the information specified below. These dangerous and/or mixed waste feed cut-offs to the LAW Vitrification System, whether automatically or manually activated, are counted if the specified setpoints are deviated from while dangerous and/or mixed waste and waste residues continue to be processed in the LAW Vitrification System. A cascade event is counted at a frequency of one (1) towards the first waste feed cut-off parameter, specified in Permit Table III.10.I.F, from which the set-point is deviated:

- The parameter(s) that deviated from the set-point(s) in Permit Table III.10.I.F;
- The magnitude, dates, and duration of the deviations;
- Results of the investigation of the cause of the deviations; and
- Corrective measures taken to minimize future occurrences of the deviations.
- viii. If greater than thirty (30) dangerous and/or mixed waste feed cut-off, combined, to the LAW Vitrification System occur due to deviations from Permit Table III.10.I.F, as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.H.3.d.v., within a thirty (30) day period, the Permittees shall submit the written report required to be submitted pursuant to Permit Condition III.10.I.1.c.vii. to Ecology on the first business day following the thirty-first exceedance. These dangerous and/or mixed waste feed cut-offs to the LAW Vitrification System, whether automatically or manually activated, are counted if the specified set-points are deviated from while dangerous and/or mixed waste and waste residues continue to be processed in the LAW Vitrification System. A cascade event is counted at a frequency of one (1) towards the first waste feed cut-off parameter, specified on Permit Table III.10.I.F, from which the set-point is deviated:

In accordance with WAC 173-303-680(2) and (3), the Permittees may not resume dangerous and/or mixed waste feed to the LAW Vitrification System until this written

- Ecology has authorized the Permittees, in writing, to resume dangerous and/or
- Ecology has not, within seven (7) days, notified the Permittees in writing of the
 - The Permittees written report does not document that the corrective measures taken will minimize future exceedances; and
 - The Permittees must take further corrective measures and document that these further corrective measures will minimize future exceedances.
- If any portion of the LAW Vitrification System is bypassed while treating dangerous and/or mixed waste, it shall be regarded as non-compliance with the operating conditions specified in Permit Condition III.10.I.1.c. and the performance standards specified in Permit Condition III.10,I.1.b. After such a bypass event, the Permittees shall perform the following actions:
 - Investigate the cause of the bypass event;

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 138 of 210

1			B. Take appropriate corrective measures to minimize future bypasses;
_2			C. Record the investigation findings and corrective measures in the WTP Unit operating record; and
4 :			D. Submit a written report to Ecology within five (5) days of the bypass event documenting the result of the investigation and corrective measures.
6 7			The Permittees shall control fugitive emissions from the LAW Vitrification System by maintaining the melters under negative pressure.
8 9 10 11 12 13			Compliance with the operating conditions specified in Permit Condition III.10.I.1.c. shall be regarded as compliance with the required performance standards identified in Permit Condition III.10.I.1.b. However, evidence that compliance with these operating conditions is insufficient to ensure compliance with the performance standards, shall justify modification, revocation, or re-issuance of this Permit, in accordance with Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g.
14	III.10.I.1.d.	Inspe	ection Requirements [WAC 173-303-680(3)]
15 16 17			The Permittees shall inspect the LAW Vitrification System in accordance with the Inspection Schedules in Attachment 51, Chapter 6.0 of this Permit, as modified in accordance with Permit Condition III.10.C.5.c.
18 19 20			The inspection data for LAW Vitrification System shall be recorded, and the records shall be placed in the WTP Unit operating record for LAW Vitrification System, in accordance with Permit Condition III.10.C.4.
21 22 23 24			The Permittees shall comply with the inspection requirements specified in Attachment 51, Appendix 9.15 of this Permit, as approved pursuant to Permit Condition III.10.H.5.f. and as modified by Permit Conditions III.10.H.3, III.10.I.1.b.x., III.10.I.1.b.xii., and III.10.I.1.h.
25 26	III.10.I.1.e.	Moni 670(7	itoring Requirements [WAC 173-303-670(5), WAC 173-303-670(6), WAC 173-303-670, and WAC 173-303-807(2), in accordance with WAC 173-303-680(3)]
27 28 29 30			Upon receipt of a written request from Ecology, the Permittees shall perform sampling and analysis of the dangerous and/or mixed waste and exhaust emissions to verify that the operating requirements established in the Permit achieve the performance standards delineated in this Permit.
31 32 33 34			The Permittees shall comply with the monitoring requirements specified in the Attachment 51, Appendices 9.2, 9.3, 9.7, 9.13, 9.15 and 9.18 of this Permit, as approved pursuant to Permit Condition III.10.H.5, and as modified by Permit Conditions III.10.H.3, III.10.I.1.h., III.10.I.1.b.x., and III.10.I.1.b.xii.
35 36 37 38 39			The Permittees shall operate, calibrate, and maintain the carbon monoxide and hydrocarbon continuous emission monitors (CEM) specified in this Permit in accordance with Performance Specifications 4B and 8A of 40 CFR Part 60, Appendix B, in accordance with Appendix to Subpart EEE of 40 CFR Part 63, and Attachment 51 Appendix 9.15 of this Permit, as approved pursuant to Permit Condition III.10.H.5.f.,

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 139 of 210

2	· · · · · · · · · · · · · · · · · · ·	and as modified by Permit Conditions III.10. H.3, III.10.1.1.n., III.10.1.1.b.x., and III.10.I.1.b.xii.
3 4 5 6 7		iv. The Permittees shall operate, calibrate, and maintain the instruments specified in Permit Tables III.10.I.C and F, as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.H.3.d.v., in accordance with Attachment 51, Appendix 9.15 of this Permit, as approved pursuant to Permit Condition III.10.H.5.f., and as modified by Permit Conditions III.10.H.3, III.10.I.1.h., III.10.I.1.b.x., and III.10.I.1.b.xii.
8	III.10.I.1.f.	Recordkeeping Requirements [WAC 173-303-380 and WAC 173-303-680(3)]
9 10 11 12 13		i. The Permittees shall record and maintain in the WTP Unit operating record for the LAW Vitrification System, all monitoring, calibration, maintenance, test data, and inspection data compiled under the conditions of this Permit, in accordance with Permit Conditions III.10.C.4 and 5, as modified by Permit Conditions III.10.H.3, III.10.I.1.h., III.10.I.1.b.x., and III.10.I.1.b.xii.
14 15 16 17 18		ii. The Permittees shall record in the WTP Unit operating record the date, time, and duration of all automatic waste feed cutoffs and/or lockouts, including the triggering parameters, reason for the deviation, and recurrence of the incident. The Permittees shall also record all incidents of AWFCO system function failures, including the corrective measures taken to correct the condition that caused the failure.
19 20 21		iii. The Permittees shall submit to Ecology an annual report each calendar year within ninety (90) days following the end of the year. The report will include the following information:
22 23		A. Total dangerous and/or mixed waste feed processing time for the LAW Vitrification System;
24		B. Date/Time of all LAW Vitrification System startups and shutdowns;
25 26 27		C. Date/Time/Duration/Cause/Corrective Action taken for all LAW Vitrification System shutdowns caused by malfunction of either process or control equipment; and
28 29 30		D. Date/Time/Duration/Cause/Corrective Action taken for all instances of dangerous and/or mixed waste feed cut-off due to deviations from Permit Table III.10.I.F, as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.H.3.d.v.
31 32 33 34	and the second of the second o	iv. The Permittees shall submit an annual report to Ecology each calendar year within ninety (90) days following the end of the year of all quarterly CEM Calibration Error and Annual CEM Performance Specification Tests conducted, in accordance with Permit Condition III.10.I.1.e.iii.
35	III.10.I.1.g.	Closure
36 37		The Permittees shall close the LAW Vitrification System in accordance with Attachment 51, Chapter 11.0 of this Permit, as approved pursuant to Permit Condition III.10.C.8.
38 39	III.10.I.1.h.	Periodic Emission Re-testing Requirements [WAC 173-303-670(5), WAC 173-303-670(7), and WAC 173-303-807(2), in accordance with WAC 173-303-680(2) and (3)]

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004

Page 140 of 210

Dioxin and Furan Emission Testing

- A. Within eighteen (18) months of commencing operation pursuant to Permit Section III.10.I, the Permittees shall submit to Ecology for approval, a Dioxin and Furan Emission Test Plan (DFETP) for the performance of emission testing of the LAW Vitrification System gases for dioxin and furans during "Normal Operating Conditions" as a permit modification in accordance with Permit Conditions III.10.C.2.e. and III.10.C.2.f. The DFETP shall include all elements applicable to dioxin and furan emission testing included in the "Previously Approved Demonstration Test Plan," applicable EPA promulgated test methods and procedures in effect at the time of the submittal, and projected commencement and completion dates for dioxin and furan emission test. "Normal Operating Conditions" shall be defined for the purposes of this permit condition as follows:
 - 1. Carbon monoxide emissions, dangerous and/or mixed waste feed-rate, and automatic waste feed cut-off parameters specified in Permit Table III.10.I.F (as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.H.3.d.v.), that were established to maintain compliance with Permit Condition III.10.I.1.b.iv. as specified in Attachment 51, Appendix 9.15 of this Permit (as approved pursuant to Permit Condition III.10.H.3.d., and in accordance with III.10.I.1.b.xii. and III.10.I.1.c.xi.), are held within the range of the average value over the previous twelve (12) months and the set-point value specified in Permit Table III.10.I.F. The average value is defined as the sum of the rolling average values recorded over the previous twelve (12) months divided by the number of rolling averages recorded during that time. The average value shall not include calibration data, malfunction data, and data obtained when not processing dangerous and/or mixed waste; and
 - 2. Feed-rate of metals, ash, and chlorine/chloride are held within the range of the average value over the previous twelve (12) months and the set-point value specified on Permit Table III.10.1.D (as approved/modified pursuant to Permit Conditions III.10.H.5 and III.10.H.3.d.v.). Feed-rate of organics as measured by TOC are held within the range of the average value over the previous twelve (12) months. The average value is defined as the sum of the rolling average values recorded over the previous twelve (12) months divided by the number of rolling averages recorded during that time. The average value shall not include data obtained when not processing dangerous and/or mixed waste.

For purposes of this permit condition, the "Previously Approved Demonstration Test Plan" is defined to include the Demonstration Test Plan approved pursuant to Permit Condition III.10.H.5.f.

B. Within sixty (60) days of Ecology's approval of the DFETP, or within thirty-one (31) months of commencing operation pursuant to Permit Section III.10.I, whichever is later, the Permittees shall implement the DFETP approved pursuant to Permit Condition III.10.I.1.h.i.A.

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 141 of 210

C. The Permittees shall resubmit the DFETP, approved pursuant to Permit Condition III.10.I.1.h.i.A, revised to include applicable EPA promulgated test methods and procedures in effect at the time of the submittal, and projected commencement and completion dates for dioxin and furan emission test as a permit modification in accordance with Permit Conditions III.10.C.2.e. and III.10.C.2.f. at twenty-four (24) months from the implementation date of the testing required pursuant to Permit Condition III.10.I.1.h.i.A and at reoccurring eighteen (18) month intervals from the implementation date of the previously approved DFETP. The Permittees shall implement these newly approved revised DFETPs, every thirty-one (31) months from the previous approved DFETP implementation date or within sixty (60) days of the newly Ecology approved revised DFETP, whichever is later, for the duration of this Permit.

- D. The Permittees shall submit a summary of operating data collected pursuant to the DFETPs in accordance with Permit Conditions III.10.I.1.h.i.A and C to Ecology upon completion of the tests. The Permittees shall submit to Ecology the complete test report within ninety (90) calendar days of completion of the testing. The test reports shall be certified as specified in WAC 173-303-807(8), in accordance with WAC 173-303-680(2) and (3).
- E. If any calculations or testing results collected pursuant to the DFETPs in accordance with Permit Conditions III.10.I.1.h.i.A and C. show that one or more of the performance standards listed in Permit Condition III.10.I.1.b., with the exception of Permit Condition III.10.I.1.b.x., for the LAW Vitrification System were not met during the emission test, the Permittees shall perform the following actions:
 - 1. Immediately stop dangerous and/or mixed waste feed to the LAW Vitrification System under the mode of operation that resulted in not meeting the performance standard(s);
 - 2. Verbally notify Ecology within twenty-four (24) hours of discovery of not meeting the performance standard(s), as specified in Permit Condition I.E.21.;
 - 3. Investigate the cause of the failure and submit a report of the investigation findings to Ecology within fifteen (15) days of discovery of not meeting the performance standard(s);
 - 4. Submit to Ecology within fifteen (15) days of discovery of not meeting the performance standard(s) documentation supporting a mode of operation where all performance standards listed in Permit Condition III.1.b., with the exception of Permit Condition III.10.I.1.b.x., for the LAW Vitrification System were met during the demonstration test, if any such mode was demonstrated;
 - 5. Based on the information provided to Ecology by the Permittees pursuant to Permit Conditions III.10.I.1.h.i.E.1 through 4 above, and any additional information, Ecology may submit in writing, direction to the Permittees to

Permit Number: WA7890008967 Modification to Revision 7
Expiration Date: September 27, 2004
Page 142 of 210

	,	
1 2 3 4		stop dangerous waste and mixed waste feed to the LAW Vitrification System and/or amend the mode of operation the Permittees are allowed to continue operations prior to Ecology approval of the revised Demonstration Test Plan pursuant to Permit Condition III.10. I.1.h.i.E.6; and
5 6 7 8 9 10 11 12		6. Submit to Ecology within one hundred and twenty (120) days of discovery of not meeting the performance standard(s) a revised Demonstration Test Plan requesting approval to retest as a permit modification pursuant to Permit Conditions III.10.C.2.e. and III.10.C.2.f. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring reflecting performance under operating conditions representative of the extreme range of normal conditions, and include revisions to Permit Tables III.10.I.D and F.
13 14 15 16 17 18	F.	If any calculations or testing results collected pursuant to the DFETPs in accordance with Permit Conditions III.10.I.1.h.i.A and C show that any emission rate for any constituent listed in Permit Table III.10.I.E, as approved/modified pursuant to Permit Conditions III.10.C.11.c. or d. is exceeded for LAW Vitrification System during the emission test, the Permittees shall perform the following actions:
19 20		1. Verbally notify Ecology within twenty-four (24) hours of the discovery of exceeding the emission rate(s), as specified in Permit Condition I.E.21.;
21 22 23 24 25 26		2. Submit to Ecology additional risk information to indicate that the increased emissions impact is off-set by decreased emission impact from one or more constituents expected to be emitted at the same time, and/or investigate the cause and impact of the exceedance and submit a report of the investigation findings to Ecology within fifteen (15) days of this discovery of exceeding the emission rate(s); and
27 28 29 30 31 32 33 34 35		3. Based on the notification and any additional information, Ecology may submit, in writing, direction to the Permittees to stop dangerous and/or mixed waste feed to the LAW Vitrification System and/or to submit a revised Demonstration Test Plan as a permit modification pursuant to Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring reflecting performance under operating conditions representative of the extreme range of normal conditions, and include revisions to Permit Tables III.10.I.D and III.10.I.F.
36	ii. Nor	-organic Emission Testing
37 38 39 40 41 42	A .	Within forty-eight (48) months of commencing operation pursuant to Permit Section III.10.I, the Permittees shall resubmit to Ecology for approval the "Previously Approved Demonstration Test Plan" revised as a permit modification in accordance with Permit Conditions III.10.C.2.e. and III.10.C.2f. The revised Demonstration Test Plan (RDTP) shall include applicable EPA promulgated test methods and procedures in effect at the time of the submittal, projected

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004

Page 143 of 210

commencement and completion dates for emission testing to demonstrate performance standards specified in Permit Conditions III.10.I.1.b.ii., iii., v., vi., and vii., and non-organic emissions as specified in Permit Table III.10.I.E, as approved/modified pursuant to Permit Conditions III.10.H.3.d. and III.10.C.11.c. or d., under "Normal Operating Conditions." "Normal Operating Conditions" shall be defined for the purposes of this permit condition as follows:

- 1. Carbon monoxide emissions, dangerous and/or mixed waste feed-rate, and automatic waste feed cut-off parameters specified in Permit Table III.10.I.F, as approved/modified pursuant to Permit Conditions III.10.H.3.d. and III.10.C.11.c. or d., that were established to maintain compliance with Permit Conditions III.10.I.1.b.ii., iii., v., vi., and vii., and non-organic emissions, as specified in Permit Table III.10.I.E, as specified in Attachment 51, Appendix 9.15 of this Permit (as approved pursuant to Permit Conditions III.10.H.3.d. and III.10.C.11.c. or d.), are held within the range of the average value over the previous twelve (12) months and the set-point value specified in Permit Table III.10.I.F. The average value is defined as the sum of the rolling average values recorded over the previous twelve (12) months divided by the number of rolling averages recorded during that time. The average value shall not include calibration data, malfunction data, and data obtained when not processing dangerous or mixed waste; and
- 2. Feed-rate of metals, ash, and chlorine/chloride are held within the range of the average value over the previous twelve (12) months and the set-point value specified in Permit Table III.10.I.D, as approved/modified pursuant to Permit Conditions III.10.H.3.d. and III.10.C.11.c. or d. The average value is defined as the sum of all rolling average values recorded over the previous twelve (12) months divided by the number of rolling averages recorded during that time. The average value shall not include data obtained when not processing dangerous or mixed waste.

For purposes of this permit condition, the "Previously Approved Demonstration Test Plan" is defined to include the Demonstration Test Plan approved pursuant to Permit Condition III.10.H.5.f.

- B. Within sixty (60) days of Ecology's approval of the RDTP, or within sixty (60) months of commencing operation pursuant to Permit Section III.10.I, whichever is later, the Permittees shall implement the RDTP approved pursuant to Permit Condition III.10.I.1.h.ii.A.
- C. The Permittees shall resubmit the RDTP, approved pursuant to Permit Condition III.10.I.1.h.ii.A, revised to include applicable EPA promulgated test methods and procedures in effect at the time of the submittal, and projected commencement and completion dates for emission test as a permit modification in accordance with Permit Conditions III.10.C.2.e. and f. at forty-eight (48) months from the implementation date of the testing required pursuant to Permit Condition III.10.I.1.h.ii.A and at reoccurring forty-eight (48) month intervals from the implementation date of the previously approved RDTP. The Permittees shall

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004

Page 144 of 210

implement these newly approved revised RDTP, every sixty (60) months from the previous approved RDTP implementation date or within sixty (60) days of the newly Ecology approved revised RDTP, whichever is later, for the duration of this Permit. The Permittees shall submit a summary of operating data collected pursuant to the D. RDTPs in accordance with Permit Conditions III.10.I.1.h.ii.A and C to Ecology upon completion of the tests. The Permittees shall submit to Ecology the complete test report within ninety (90) calendar days of completion of the testing. The test reports shall be certified pursuant to WAC 173-303-807(8), in accordance with WAC 173-303-680(2) and (3).

- E. If any calculations or testing results collected pursuant to the DFETPs in accordance with Permit Conditions III.10.I.1.h.ii.A and C show that any emission rate for any constituent listed in Permit Table III.10.I.E, as approved/modified pursuant to Permit Conditions III.10.H.3.d. and III.10.C.11.c. or d., is exceeded for LAW Vitrification System during the emission test, the Permittees shall perform the following actions:
 - 1. Verbally notify Ecology within twenty-four (24) hours of the discovery of exceeding the emission rate(s), as specified in Permit condition I.E.21.;
 - 2. Submit to Ecology additional risk information to indicate that the increased emissions impact is off-set by decreased emission impact from one or more constituents expected to be emitted at the same time, and/or investigate the cause and impact of the exceedance and submit a report of the investigation findings to Ecology within fifteen (15) days of this discovery of exceeding the emission rate(s); and
 - 3. Based on the notification and any additional information, Ecology may submit, in writing, direction to the Permittees to stop dangerous and/or mixed waste feed to the LAW Vitrification System and/or to submit a revised Demonstration Test Plan as a permit modification pursuant to Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring reflecting performance under operating conditions representative of the extreme range of normal conditions, and include revisions to Permit Tables III.10.I.D and III.10.I.F.
- F. If any calculations or testing results collected pursuant to the DFETPs in accordance with Permit Conditions III.10.I.1.h.ii.A and C show that one or more of the performance standards listed in Permit Condition III.10.I.1.b., with the exception of Permit Condition III.10.I.1.b.x., for the LAW Vitrification System were not met during the emission test, the Permittees shall perform the following actions:
 - Immediately stop dangerous and/or mixed waste feed to the LAW
 Vitrification System under the mode of operation that resulted in not meeting
 the performance standard(s);

Permit Number: WA7890008967 Modification to Revision 7

Expiration Date: September 27, 2004

Page 145 of 210

Verbally notify Ecology within twenty-four (24) hours of discovery of not 1 meeting the performance standard(s), as specified in Permit condition I.E.21.; 2 3. Investigate the cause of the failure and submit a report of the investigation 3 findings to Ecology within fifteen (15) days of discovery of not meeting the 4 performance standard(s); 5 Submit to Ecology within fifteen (15) days of discovery of not meeting the 6 performance standard(s) documentation supporting a mode of operation :7 where all performance standards listed in Permit Condition III.1.b., with the exception of Permit Condition III.10.I.1.b.x., for the LAW Vitrification System were met during the demonstration test, if any such mode was 10 demonstrated: 11 Based on the information provided to Ecology by the Permittees pursuant to 12 Permit Conditions III.10.I.1.h.ii.F.1 through 4 above, and any additional 13 information, Ecology may submit in writing, direction to the Permittees to 14 stop dangerous and/or mixed waste feed to the LAW Vitrification System 15 and/or amend the mode of operation the Permittees are allowed to continue 16 operations prior to Ecology approval of the revised Demonstration Test Plan 17 pursuant to Permit Condition III.10.I.1.h.ii.F.6; and 18 Submit to Ecology within one hundred and twenty (120) days of discovery of 19 not meeting the performance standard(s) a revised Demonstration Test Plan 20 requesting approval to retest as a permit modification pursuant to Permit 21 Conditions III.10.C.2.e. and f. The revised Demonstration Test Plan must 22 include substantive changes to prevent failure from reoccurring reflecting 23 performance under operating conditions representative of the extreme range 24 of normal conditions, and include revisions to Permit Tables III.10.I.D and F. 25 Other Emission Testing 26 Within seventy-eight (78) months of commencing operation pursuant to Permit 27 Section III.10.1, the Permittees shall resubmit to Ecology for approval the 28 "Previously Approved Demonstration Test Plan" revised as a permit modification 29 in accordance with Permit Conditions III.10.C.2.e. and f. The revised 30 Demonstration Test Plan (RDTP) shall include applicable EPA promulgated test 31 methods and procedures in effect at the time of the submittal, projected 32 commencement and completion dates for emission testing to demonstrate 33 performance standards as specified in Permit Conditions III.10.I.1.b.viii. and ix., 34 and emissions as specified in Permit Table III.10.I.E, as approved/modified 35 pursuant to Permit Conditions III.10.H.3.d. and III.10.C.11.c. or d., not addressed 36 under Permit Conditions III.10.I.1.h.i. or ii. under "Normal Operating 37 Conditions." "Normal Operating Conditions" shall be defined for the purposes of 38 this permit condition as follows: 39

40

41

42

 Carbon monoxide emissions, dangerous and/or mixed waste feed-rate, and automatic waste feed cut-off parameters specified in Permit Table III.10.I.F, as approved/modified pursuant to Permit Condition III.10.H.3.d. and

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004

Page 146 of 210

III.10.C.11.c. or d., that were established to maintain compliance with Permit Conditions III.10.I.1.b.viii. and ix., and emissions as specified in Permit Table III.10.I.E, not addressed under Permit Conditions III.10.I.1.h.i. or ii. as specified in Attachment 51, Appendix 9.15 of this Permit, as approved pursuant to Permit Condition III.10.H.3.d., and in accordance with Permit Conditions III.10.I.1.b.xii. and III.10.I.1.c.xi. are held within the range of the average value over the previous twelve (12) months and the set-point value specified on Permit Table III.10.I.F. The average value is defined as the sum of all rolling average values recorded over the previous twelve (12) months divided by the number of rolling averages recorded during that time. The average value shall not include calibration data, malfunction data, and data obtained when not processing dangerous and/or mixed waste; and

2. Feed-rate of metals, ash, and chlorine/chloride are held within the range of the average value over the previous twelve (12) months and the set-point value specified in Permit Table III.10.I.D, as approved/modified pursuant to Permit Conditions III.10.H.3.d. and III.10.C.11.c. or d. Feed-rate of organics as measured by TOC are held within the range of the average value over the previous twelve (12) months. The average value is defined as the sum of the rolling average values recorded over the previous twelve (12) months divided by the number of rolling averages recorded during that time. The average value shall not include data obtained when not processing dangerous and/or mixed waste.

For purposes of this permit condition, the "Previously Approved Demonstration Test Plan" is defined to include the Demonstration Test Plan approved pursuant to Permit Condition III.10.H.5.f.

- B. Within sixty (60) days of Ecology's approval of the RDTP, or within ninety-one (91) months of commencing operation pursuant to Permit Section III.10.I, whichever is later, the Permittees shall implement the RDTP approved pursuant to Permit Condition III.10.I.1.h.iii.A.
- C. The Permittees shall submit a summary of operating data collected pursuant to the RDTPs in accordance with Permit Condition III.10.I.1.h.iii.A to Ecology upon completion of the tests. The Permittees shall submit to Ecology the complete test report within ninety (90) calendar days of completion of the testing. The test reports shall be certified as specified in WAC 173-303-807(8), in accordance with Permit Condition WAC 173-303-680(2) and (3).
- D. If any calculations or testing results show that one or more of the performance standards listed in Permit Condition III.10.I.1.b., with the exception of Permit Condition III.10.I.1.b.x., for the LAW Vitrification System were not met during the emission test, the Permittees shall perform the following actions:
 - Immediately stop dangerous and/or mixed waste feed to the LAW
 Vitrification System under the mode of operation that resulted in not meeting
 the performance standard(s);

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004
Page 147 of 210

		Page 147 01 210
1 2		2. Verbally notify Ecology within twenty-four (24) hours of discovery of not meeting the performance standard(s), as specified in Permit Condition
3		I.E.21.;
4		3. Investigate the cause of the failure and submit a report of the investigation
5 6		findings to Ecology within fifteen (15) days of discovery of not meeting the performance standard(s);
7 8 9 10 11 12		4. Submit to Ecology within fifteen (15) days of discovery of not meeting the performance standard(s) documentation supporting a mode of operation where all performance standards listed in Permit Condition III.I.1.b., with the exception of Permit Condition III.10.I.1.b.x., for the LAW Vitrification System were met during the demonstration test, if any such mode was demonstrated;
13 14 15 16 17 18 19		5. Based on the information provided to Ecology by the Permittees pursuant to Permit Conditions III.10.I.1.h.iii.D.1 through 4 above, and any additional information, Ecology may submit in writing, direction to the Permittees to stop dangerous and/or mixed waste feed to the LAW Vitrification System and/or amend the mode of operation the Permittees are allowed to continue operations prior to Ecology approval of the revised Demonstration Test Plan, pursuant to Permit Condition III.10. I.h.1.iii.D.6.; and
20 21 22 23 24 25 26 27		6. Submit to Ecology within one hundred and twenty (120) days of discovery of not meeting the performance standard(s) a revised Demonstration Test Plan requesting approval to retest as a permit modification pursuant to Permit Conditions II.10.C.2.e. and f. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring reflecting performance under operating conditions representative of the extreme range of normal conditions, and include revisions to Permit Tables III.10.I.D and III.10.I.F.
28 29 30 31	E.	If any calculations or testing results show that any emission rate for any constituent listed in Permit Table III.10.I.E, as approved/modified pursuant to Permit Conditions III.10.C.11.c. or d., is exceeded for LAW Vitrification System during the emission test, the Permittees shall perform the following actions:
32 33		1. Verbally notify Ecology within twenty-four (24) hours of the discovery of exceeding the emission rate(s), as specified in Permit Condition I.E.21.;
34 35 36 37 38 39		2. Submit to Ecology additional risk information to indicate that the increased emissions impact is off-set by decreased emission impact from one or more constituents expected to be emitted at the same time, and/or investigate the cause and impact of the exceedance of the emission rate(s) and submit a report of the investigation findings to Ecology within fifteen (15) days of the discovery of the exceedance of the emission rate(s); and

Based on the notification and any additional information, Ecology may

submit, in writing, direction to the Permittees to stop dangerous and/or mixed

39

Permit Number: WA7890008967 Modification to Revision 7

Expiration Date: September 27, 2004

Page 148 of 210

waste feed to the LAW Vitrification System and/or to submit a revised Demonstration Test Plan as a permit modification pursuant to Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring reflecting performance under operating conditions representative of the extreme range of normal conditions, and include revisions to Permit Tables III.10.I.D and F.

2

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 149 of 210

Table III.10.I.A - LAW Vitrification System Description

Sub-system Description	Sub-system Designation	Engineering Description (Drawing Nos, Specification Nos, etc.)	Narrative Description, Tables `and Figures	Maximum Capacity (gallons)
Melter Feed ^a Systems- Melter 1,2, & 3	LFP LCP GFR	RESERVED	Section 4.2.3.1; Tables 4-4 and 4-11, and Figures 4A-1, 4A-3, and 4A-20 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
LAW Melters 1,2, & 3	LMP	RESERVED	Section 4.2.3.2; Tables 4-4, and Figure 4A-21 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
LAW Glass Product Systems-Melter 1,2, & 3	LMP	RESERVED	Section 4.2.3.2 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Primary & Secondary Film Coolers-Melter 1, 2, & 3	LOP	RESERVED	Section 4.2.3.3 and Figure 4A- 21 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Submerged Bed Scrubbers/Condensate Vessels *-Melter 1, 2, & 3	LOP	RESERVED	Section 4.2.3.3; Tables 4 4 and 4-11, and Figure 4A 22 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Melter 1 & 2 Submerged Bed Scrubbers LAW- MK-LOP-SCB-00001 & -00002, Melter 1 & 2 SBS Condensate Vessels LAW-MV-LOP-VSL- 00001 & -00002 & Submerged Bed Scrubbers/Condensate Vessels a-Melter 1, 2, & 3	LOP	RESERVED 24590-LAW -M6-LOP-P0001 -M6-LOP-P0002 -MK-LOP-P0001002 -MK-LOP-P0001003 -MK-LOP-P0002 -MKD-LOP-P0004 -MKD-LOP-P0008	Section 4.2.3.3; Tables 4-4 and 4-11, and Figure 4A-22 of Attachment 51, Chapter 4 of this Permit	LOP-SCB-00001 = 4,948 LOP-SCB-00002 = 4,948
Wet electrostatic Precipitators-Melter 1, 2, & 3	LOP	RESERVED	Section 4.2.3.3 and Figure 4A- 22 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
High Efficiency Particulate Air Filters	LVP	RESERVED	Section 4.2.3.3 and Figure 4A- 23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Thermal Catalytical	LVP	RESERVED	Section 4.2.3.3 and Figure 4A-	<u>N/A</u>

Permit Number: WA7890008967 Modification to Revision 7

Expiration Date: September 27, 2004

Page 150 of 210

Sub-system Description	Sub-system Designation	Engineering Description (Drawing Nos, Specification Nos,	Narrative Description, Tables and Figures	Maximum Capacity
		etc.)		(gallons)
Oxidation Unit			23 of Attachment 51, Chapter 4 of this Permit	
Selective Catalytical Reduction Units	LVP	RESERVED	Section 4.2.3.3 and Figure 4A- 23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Caustic Scrubber/Blowdown Vessel ^a	LVP	RESERVED	Section 4.2.3.3 and Figure 4A- 23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Electric Heaters	LVP	RESERVED	Section 4.2.3.3 and Figure 4A- 23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Heat Exchangers	LVP	RESERVED	Section 4.2.3.3 and Figure 4A- 23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Pumps	LVP	RESERVED	Section 4.2.3.3 and Figure 4A- 23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Exhaust Fans	LVP	RESERVED	Section 4.2.3.3 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
Mist Eliminators	LVP	RESERVED	Section 4.2.3.3 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>
LAW Stack	LVP	RESERVED	Section 4.2.3.3 and Figure 4A- 23 of Attachment 51, Chapter 4 of this Permit	<u>N/A</u>

a. Requirements pertaining to the tanks in LAW Vitrification System Melter Feed System, Submerged Bed

Scrubbers/Condensate Vessels, and Caustic Scrubber/Blowdown Vessel are specified in Permit Section III.10.E.

Permit Number: WA7890008967 Modification to Revision 7

Expiration Date: September 27, 2004 Page 151 of 210

1

3

Table III.10.I.B - LAW Vitrification System Secondary Containment Systems Including Sumps and Floor Drains

Sump/Floor Drain I.D.# & Room Location	Maximum Sump Capacity (gallons)	Sump Dimensions (feet) & Materials of Construction	Engineering Description (Drawing Nos, Specification Nos, etc.)
RESERVED	RESERVED	RESERVED	RESERVED

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 152 of 210

Table III.10.I.C - LAW Vitrification Systems Process and Leak Detection System Instruments and Parameters

Sub-system Locator and Name (including P&ID)	Control Parameter	Type of Measuring or Leak Detection Instrument	Location of Measuring Instrument (Tag No.)	Instrument Range	Failure State	Expected Range	Instrument Accuracy	Instrument Calibration Method No. and Range
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 153 of 210

Table III.10.I.D - Maximum Feed-rates to LAW Vitrification System (RESERVED)

Description of Waste	Normal Operation				
Dangerous and/or Mixed Waste Feed Rate					
Ash Feed Rate					
Total Chlorine/Chloride Feed Rate					
Total Metal Feedrates					

1

Table III.10.I.E - LAW Vitrification System Estimated Emission Rates (RESERVED)

6

	C	hemicals	CAS Number	Emission Rates (grams /second)
.				
		-		
L			 	

8

TABLE III.10.I.F - LAW Vitrification System Waste Feed Cut-off Parameters* (RESERVED)

10

Sub-system Designation	Instrument Tag	Parameter	Set-points During
	Number	Description	Normal Operation
	* .		

^{*}A continuous monitoring system shall be used as defined in Permit Section III.10.C.1.

14

Maximum Feed-rate shall be set based on not exceeding any of the constituent (e.g., metals, ash, and
 chlorine/chloride) feed limits specified on Table III.10.I.D. of this Permit

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 154 of 210

2	III.10.J	HLW Vitrification System – Short Term Miscellaneous Thermal Treatment Unit-
3		Shakedown, Demonstration Test, and Post Demonstration Test
4 5 6 7 8		For purposes of Permit Section III.10.J, where reference is made to WAC 173-303-640, the following substitutions apply: substituting the terms "HLW Vitrification System" for "tank system(s)," "sub-system(s)" for "tank(s)," "sub-system equipment" for "ancillary equipment," and "sub-system(s) or sub-system equipment of a HLW Vitrification System" for "component(s)," in accordance with WAC 173-303-680.
9 10	III.10.J.1.	General Conditions During Shakedown, Demonstration Test, and Post-Demonstration Test for HLW Vitrification System
11 12	Ш.10.Ј.1.а.	Construction and Maintenance [WAC 173-303-640, in accordance with WAC 173-303-680(2) and (3), and WAC 173-303-340].
13 14 15 16 17 18		i. The Permittees shall construct the HLW Vitrification System (listed in Permit Tables III.10.J.A and III.10.J.B, as approved/modified pursuant to Permit Condition III.10.J.5.) as specified in Permit Condition III.10.J.1. and Attachment 51, Chapter 4.0 of this Permit, and Attachment 51, Appendices 10.1 through 10.15 and 10.17 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.a. through d., and III.10.J.5.f.
19 20 21 22		ii. The Permittees shall construct all containment systems for the HLW Vitrification System as specified in Attachment 51, Chapter 4.0 of this Permit, and Attachment 51, Appendices 10.2, 10.4, through 10.14 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.a. through d.
23 24 25 26		iii. The Permittees shall ensure all certifications required by specialists (e.g., independent, qualified, registered professional engineer, independent corrosion expert, independent qualified installation inspector, etc.) use the following statement or equivalent pursuant to Permit Condition III.10.C.10.:
27 28 29 30 31 32 33		"I, (Insert Name) have (choose one or more of the following: overseen, supervised, reviewed, and/or certified) a portion of the design or installation of a new HLW Vitrification system or component located at (address), and owned/operated by (name(s)). My duties were: (e.g., installation inspector, testing for tightness, etc.), for the following HLW Vitrification system components (e.g., the venting piping, etc.), as required by the Dangerous Waste Regulations, namely, WAC 173-303-640(3) (applicable paragraphs (i.e., (a) through (g)) in accordance with WAC 173-303-680).
34 35 36 37 38 39	***	"I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment."
40 41		iv. The Permittees must ensure that proper handling procedures are adhered to in order to prevent damage to the HLW Vitrification System during installation. Prior to

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 155 of 210

covering, enclosing, or placing the new HLW Vitrification System or component in use, an independent, qualified, installation inspector or an independent, qualified, registered professional engineer, either of whom is trained and experienced in the proper installation of similar systems or components, must inspect the system for the presence of any of the following items:

G. Weld breaks;

H. Punctures:

11 ×,

- I. Scrapes of protective coatings;
- J. Cracks;
- K. Corrosion;
- L. Other structural damage or inadequate construction/installation.

All discrepancies must be remedied before the HLW Vitrification system is covered, enclosed, or placed in use [WAC 173-303-640(3)(c), in accordance with WAC 173-303-680(2) and (3)].

- For the HLW Vitrification System or components that are placed underground and that are back-filled, the Permittees must provide a backfill material that is a non-corrosive, porous, homogeneous substance. The backfill must be installed so that it is placed completely around the HLW Vitrification System and compacted to ensure that the HLW Vitrification System is fully and uniformly supported [WAC 173-303-640(3)(d), in accordance with WAC 173-303-680(2) and (3)].
- vi. The Permittees must test for tightness the HLW Vitrification System or components, prior to being covered, enclosed, or placed into use. If the HLW Vitrification System or components are found not to be tight, all repairs necessary to remedy the leak(s) in the system must be performed prior to the HLW Vitrification System being covered, enclosed, or placed in use [WAC 173-303-640(3)(e), in accordance with WAC 173-303-680(2) and (3)].
- vii. The Permittees must ensure the HLW Vitrification System equipment is supported and protected against physical damage and excessive stress due to settlement, vibration, expansion, or contraction [WAC 173-303-640(3)(f), in accordance with WAC 173-303-680(2) and (3)].
- viii. The Permittees must provide the type and degree of corrosion protection recommended by an independent corrosion expert, based on the information provided in Attachment 51, Appendices 10.9 and 10.11 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.b.i., III.10.J.5.b.iv., III.10.J.5.b.v., III.10.J.5.c.i., III.10.J.5.c.iv., III.10.J.5.c.iv., III.10.J.5.d.iv., and III.10.J.5.d.v., or other corrosion protection if Ecology believes other corrosion protection is necessary to ensure the integrity of the HLW Vitrification System during use of the HLW Vitrification System. The installation of a corrosion protection system that is field fabricated must be supervised by an independent corrosion expert to ensure proper

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 156 of 210

1 2		installation [WAC 173-303-640(3)(g), in accordance with WAC 173-303-680(2) and (3)].
3 4 5 6 7 8 9 10 11	ix.	Prior to initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees shall obtain and keep on file in the WTP Unit operating record, written statements by those persons required to certify the design of the HLW Vitrification System and supervise the installation of the HLW Vitrification System, as specified in WAC 173-303-640(3)(b), (c), (d), (e), (f), and (g), in accordance with WAC 173-303-680, attesting that the HLW Vitrification system and corresponding containment system listed in Permit Tables III 10.J.A and III.10.J.B, as approved/modified pursuant to Permit Condition III.10.J.5., were properly designed and installed, and that repairs, in accordance with WAC 173-303-640(3)(c) and (e), were performed [WAC 173-303-640(3)(a) and WAC 173-303-640(3)(h), in accordance with WAC 173-303-680(3)].
14 15 16 17 18 19	x.	The independent HLW Vitrification System installation inspection and subsequent written statements shall be certified in accordance with WAC 173-303-810(13)(a), as modified pursuant to Permit Condition III.10.J.1.a.iii., comply with all requirements of WAC 173-303-640(3)(h) in accordance with WAC 173-303-680, and shall consider, but not be limited to, the following LAW Vitrification System installation documentation:
20		A. Field installation report with date of installation;
21		B. Approved welding procedures;
22		C. Welder qualification and certifications;
23 24 25 26		 D. Hydro-test reports, as applicable, in accordance with the American Society of Mechanical Engineers Boiler and Pressure Vessel Code, Section VIII, Division 1; American Petroleum Institute (API) Standard 620, or Standard 650, as applicable;
27		E. Tester credentials;
28		F. Field inspector credentials;
29		G. Field inspector reports;
30		H. Field waiver reports; and
31 32	•	I. Non-compliance reports and corrective action (including field waiver reports) and repair reports.
33 34 35 36 37 38 39	xi.	The Permittees shall ensure periodic integrity assessments are conducted on the HLW Vitrification System, listed in Permit Table III.10.J.A, as approved/modified pursuant to Permit Condition III.10.J.5., over the term of this Permit, in accordance with WAC 173-303-680(2) and (3) as specified in WAC 173-303-640(3)(b), following the description of the integrity assessment program and schedule in Attachment 51, Chapter 6.0 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.e.i. and III.10.C.5.c. Results of the integrity assessments shall be included in the WTP

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004
Page 157 of 210

	•	
1 2	 	Unit operating record until ten (10) years after post-closure, or corrective action is complete and certified, whichever is later.
3 4 5 6	xii.	The Permittees shall address problems detected during the HLW Vitrification System integrity assessments specified in Permit Condition III.10.J.1.a.xi. following the integrity assessment program in Attachment 51, Chapter 6.0 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.e.i. and III.10.C.5.c.
7 8 9 10	xiii.	All process monitors/instruments as specified in Permit Table III.10.J.F, as approved/modified pursuant to Permit Condition III.10.J.5., shall be equipped with operational alarms to warn of deviation, or imminent deviation from the limits specified in Permit Table III.10.J.F.
11 12 13 14 15	xiv.	The Permittees shall install and test all process and leak detection system monitors/instrumentation as specified in Permit Tables III.10.J.C and III.10.J.F, as approved/modified pursuant to Permit Condition III.10.J.5, in accordance with Attachment 51, Appendices 10.1, 10.2, and 10.14 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.d.x. and III.10.J.5.f.xvi.
16 17 18	xv.	No dangerous and/or mixed waste shall be treated in the HLW Vitrification System unless the operating conditions, specified under Permit Condition III.10.J.1.c. are complied with.
19 20 21 22 23 24 25	xvi.	The Permittees shall not place dangerous and/or mixed waste, treatment reagents, or other materials in the HLW Vitrification System if these substances could cause the subsystem, subsystem equipment, or the containment system to rupture, leak, corrode, or otherwise fail [WAC 173-303-640(5)(a), in accordance with WAC 173-303-680(2)]. This condition is not applicable to corrosion of HLW Vitrification System sub-system and sub-system equipment that are expected to be replaced as part of normal operations (e.g., melters).
26 27 28 29 30 31	xvii.	The Permittees shall operate the HLW Vitrification System to prevent spills and overflows using description of controls and practices as required under WAC 173-303-640(5)(b) described in Permit Condition III.10.C.5, and Attachment 51, Appendix 10.18 of this Permit, as approved pursuant to Permit Condition III.10.J.5.e. [WAC 173-303-640(5)(b), in accordance with WAC 173-303-680(2) and (3), and WAC 173-303-806(4)(c)(ix)].
32 33 34 35 36 37 38 39 40 41	xviii.	For routinely non-accessible HLW Vitrification System sub-systems, as specified in Attachment 51, Chapter 4.0 of this Permit, as updated pursuant to Permit Condition III.10.J.5.e.vi., the Permittees shall mark all routinely non-accessible HLW Vitrification System sub-systems access points with labels or signs to identify the waste contained in each HLW Vitrification System sub-system. The label, or sign, must be legible at a distance of at least fifty (50) feet, and must bear a legend which identifies the waste in a manner which adequately warns employees, emergency response personnel, and the public of the major risk(s) associated with the waste being stored or treated in the HLW Vitrification System sub-systems. For the purposes of this permit condition, "routinely non-accessible" means personnel are

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004
Page 158 of 210

1 2		unable to enter these areas while waste is being managed in them [WAC 173-303-640(5)(d), in accordance with WAC 173-303-680(2)].
3 4 5 6 7 8 9 10	xix.	For all HLW Vitrification System sub-systems not addressed in Permit Condition III.10.J.1.a.xviii., the Permittees shall mark all these HLW Vitrification System sub-systems holding dangerous and/or mixed waste with labels or signs to identify the waste contained in the HLW Vitrification System sub-systems. The labels, or signs, must be legible at a distance of at least fifty (50) feet, and must bear a legend which identifies the waste in a manner which adequately warns employees, emergency response personnel, and the public of the major risk(s) associated with the waste being stored or treated in the HLW Vitrification System sub-systems [WAC 173-303-640(5)(d), in accordance with WAC 173-303-680(2)].
12 13 14 15 16 17 18 19 20 21 22	XX.	The Permittees shall ensure that the containment systems for the HLW Vitrification System sub-systems listed in Permit Tables III.10 J.A. and III.10 J.B, as approved/modified pursuant to Permit Condition III.10 J.5, are free of cracks or gaps to prevent any migration of dangerous and/or mixed waste or accumulated liquid out of the system to the soil, groundwater, or surface water at any time during use of the HLW Vitrification System sub-systems. Any indication that a crack or gap may exist in the containment systems shall be investigated and repaired in accordance with Attachment 51, Appendix 10.18 of this Permit, as approved pursuant to Permit Condition III.10 J.5.e.v. [WAC 173-303-640(4)(b)(i), WAC 173-303-640(4)(e)(i)(C), and WAC 173-303-640(6), in accordance with WAC 173-303-680(2) and (3), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-320].
23 24 25 26 27 28 29 30	xxi.	The Permittees must immediately, and safely, remove from service any HLW Vitrification System or secondary containment system which, through an integrity assessment, is found to be "unfit for use" as defined in WAC 173-303-040, following Permit Conditions III.10.J.1.a.xxiii.A. through D., and F. The affected HLW Vitrification System, or secondary containment system, must be either repaired or closed in accordance with Permit Condition III.10.J.1.a.xxiii.E. [WAC 173-303-640(7)(e) and (f), and WAC 173-303-640(8), in accordance with WAC 173-303-680(3)].
31 32 33 34 35 36 37 38 39 40 41	xxii.	An impermeable coating, as specified in Attachment 51, Appendices 10.4, 10.5, 10.7, 10.9, 10.11, and 10.12 of this Permit, as approved pursuant to Permit Condition III.10.J.5.b.v., shall be maintained for all concrete containment systems and concrete portions of containment systems for each HLW Vitrification System sub-systems listed in Permit Tables III.10.J.A and III.10.J.B as approved/modified pursuant to Permit Condition III.10.J.5 (concrete containment systems that do not have a liner, pursuant to WAC 173-303-640(4)(e)(i), in accordance with WAC 173-303-680(2), and have construction joints, shall meet the requirements of WAC 173-303-640(4)(e)(ii)(C), in accordance with WAC 173-303-680(2). The coating shall prevent migration of any dangerous and mixed waste into the concrete. All coatings shall meet the following performance standards:
42 43		A. The coating must seal the containment surface such that no cracks, seams, or other avenues through which liquid could migrate, are present;

Permit Number: WA7890008967 Modification to Revision 7

Expiration Date: September 27, 2004

Page 159 of 210

1 2		B. The coating must be of adequate thickness and strength to withstand the normal operation of equipment and personnel within the given area such that
3 4		degradation or physical damage to the coating or lining can be identified and remedied before dangerous and mixed waste could migrate from the system; and
5 6 7 8		C. The coating must be compatible with the dangerous and mixed waste, treatment reagents, or other materials managed in the containment system [WAC 173-303-640(4)(e)(ii)(D), in accordance with WAC 173-303-680(2) and (3), and WAC 173-303-806(4)(i)(i)(A)].
9 10 11 12 13 14 15 16	xxiii.	The Permittees shall inspect all containment systems for the HLW Vitrification System sub-systems listed in Permit Tables III.10.J.A and III.10.J.B, as approved/modified pursuant to Permit Condition III.10.J.5., in accordance with the Inspection Schedule specified in Attachment 51, Chapter 6.0 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.e.i. and III.10.C.5.c., and take the following actions if a leak or spill of dangerous and/or mixed waste is detected in these containment systems [WAC 173-303-640(5)(c) and WAC 173-303-640(6), in accordance with WAC 173-303-680(2) and (3), WAC 173-303-320, and WAC 173-303-806(4)(i)(i)(B)]:
18 19		A. Immediately, and safely, stop the flow of dangerous and/or mixed waste into the HLW Vitrification System sub-systems or secondary containment system.
20		B. Determine the source of the dangerous and/or mixed waste.
21 22 23 24 25		C. Remove the dangerous and/or mixed waste from the containment area in accordance with WAC 173-303-680(2) and (3), as specified in WAC 173-303-640(7)(b). The dangerous and/or mixed waste removed from containment areas of the HLW Vitrification System sub-systems shall be, as a minimum, managed as mixed waste.
26 27 28 29 30 31		D. If the cause of the release was a spill has not damaged the integrity of the HLW Vitrification System sub-system, the Permittees may return the HLW Vitrification System sub-system to service in accordance with WAC 173-303-680(2) and (3), as specified in WAC 173-303-640(7)(e)(ii). In such case, the Permittees shall take action to ensure the incident that caused the dangerous and/or mixed waste to enter the containment system will not re-occur [WAC 173-303-320(3)].
33 34 35 36 37		E. If the source of the dangerous and/or mixed waste is determined to be a leak from the primary HLW Vitrification System into the secondary containment system, or the system is unfit for use as determined through an integrity assessment or other inspection, the Permittees shall comply with the requirements of WAC 173-303-640(7) and take the following actions:
38 39 40		1. Close the HLW Vitrification System Sub-system following procedures in WAC 173-303-640(7)(e)(i), in accordance with WAC 173-303-680 and Attachment 51, Chapter 11.0 of this Permit, as approved pursuant to Permit

Condition III.10.C.8., or

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 160 of 210

1 2		2. Repair and re-certify (in accordance with WAC 173-303-810(13)(a), as modified pursuant to Permit Condition III.10.J.1.a.iii.) the HLW
3 4 5 6 7		Vitrification System in accordance with Attachment 51, Appendix 10.18 of this Permit, as approved pursuant to Permit Condition HI.10.J.5.e.v., before the HLW Vitrification System is placed back into service [WAC 173-303-640(7)(e)(iii) and WAC 173-303-640(7)(f), in accordance with WAC 173-303-680].
8 9 10		F. The Permittees shall document, in the WTP Unit operating record, actions/procedures taken to comply with A. through E. above, as specified in WAC 173-303-640(6)(d), in accordance with WAC 173-303-680(2) and (3).
11 12 13		G. In accordance with WAC 173-303-680(2) and WAC 173-303-680 (3), the Permittees shall notify and report releases to the environment to Ecology, as specified in WAC 173-303-640(7)(d).
14 15 16 17 18 19 20 21	xxiv.	If liquids (e.g., dangerous and/or mixed waste leaks and spills, precipitation, fire water, liquids from damaged or broken pipes) cannot be removed from the secondary containment system within twenty-four (24) hours, Ecology will be verbally notified within twenty-four (24) hours of discovery. The notification shall provide the information in A, B, and C, listed below. The Permittees shall provide Ecology with a written demonstration within seven (7) business days, identifying at a minimum [WAC 173-303-640(4)(c)(iv) and WAC 173-303-640(7)(b)(ii), in accordance with WAC 173-303-680(3) and WAC 173-303-806(4)(i)(i)(B)]:
22		A. Reasons for delayed removal;
23 24		B. Measures implemented to ensure continued protection of human health and the environment;
25		C. Current actions being taken to remove liquids from secondary containment.
26 27 28 29 30 31	XXV	All air pollution control devices and capture systems in the HLW Vitrification System shall be maintained and operated at all times in a manner so as to minimize the emissions of air contaminants and to minimize process upsets. Procedures for ensuring that the air pollution control devices and capture systems in the HLW Vitrification System are properly operated and maintained so as to minimize the emission of air contaminants and process upsets shall be established.
32 33	xxvi.	In all future narrative permit submittals, the Permittees shall include HLW Vitrification sub-system names with the sub-system designation.
34 35 36	xxvii.	Modifications to approved design, plans, and specifications in Attachment 51 of this Permit for the HLW Vitrification System shall be allowed only in accordance with Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g., III.10.C.9.d., e., and h.
37 38 39		For any portion of the HLW Vitrification System that has the potential for formation and accumulation of hydrogen gases, the Permittees shall operate the portion to maintain hydrogen levels below the lower explosive limit [WAC 173-303-815(2)(b)(ii)]
40		815(2)(b)(ii)].

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 161 of 210

1 2	XX	ix. For each HLW Vitrification System sub-system holding dangerous waste which are acutely or chronically toxic by inhalation, the Permittees shall operate the system to
3, · 4		prevent escape of vapors, fumes or other emissions into the air [WAC 173-303-806(4)(i)(i)(B) and WAC 173-303-640(5)(e) in accordance with WAC 173-303-680].
5	III.10.J.1.b. Per	rformance Standards
6 7 8 9	i.	The HLW Vitrification System must achieve a destruction and removal efficiency (DRE) of 99.99% for the principal organic dangerous constituents (PODCs) listed below [40 CFR §63.1203(c)(1) and 40 CFR 63.1203(c)(2), in accordance with WAC 173-303-680(2)].
10		RESERVED
11 12		DRE in this this Permit condition shall be calculated in accordance with the formula given below:
13		$DRE=[1-(W_{out}/W_{in})] \times 100\%$
14		Where:
15 16		W_{in} =mass feedrate of one principal organic dangerous constituent (PODC) in a waste feedstream; and
17 18		W _{out} =mass emission rate of the same PODC present in exhaust emissions prior to release to the atmosphere.
19 20 21	ii.	Particulate matter emissions from the HLW Vitrification System shall not exceed 34 mg/dscm (0.015 grains/dscf) [40 CFR §63.1203(b)(7), in accordance with WAC 173-303-680(2)]:
22 23 24	iii.	Hydrochloric acid and chlorine gas emissions from the HLW Vitrification System shall not exceed 21 ppmv, combined [40 CFR §63.1203(b)(6), in accordance with WAC 173-303-680(2)]:
25 26 27	į v .	Dioxin and Furan TEQ emissions from the HLW Vitrification System shall not exceed 0.2 nanograms (ng)/dscm [40 CFR §63.1203(b)(1), in accordance with WAC 173-303-680(2)]:
28 29	V .	Mercury emissions from the HLW Vitrification System shall not exceed 45 μg/dscm, [40 CFR §63.1203(b)(2), in accordance with WAC 173-303-680(2)].
30 31 32	vi.	Lead and cadmium emissions from the HLW Vitrification System shall not exceed 120 μg/dscm, combined [40 CFR §63.1203(b)(3), in accordance with WAC 173-303-680(2)].
33 34 35	vii.	Arsenic, beryllium, and chromium emissions from the HLW Vitrification System shall not exceed 97 μ g/dscm, combined [40 CFR §63.1203(b)(4), in accordance with WAC 173-303-680(2)].
36 37	viii	. Carbon monoxide (CO) emission from the HLW Vitrification System shall not exceed 100 parts per million (ppm) by volume, over an hourly rolling average (as measured

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 162 of 210

1 2		and recorded by the continuous monitoring system), dry [40 CFR §63.1203(b)(5)(i), in accordance with WAC 173-303-680(2)].
3 4 5 6 7		ix. Hydrocarbon emission from the HLW Vitrification System shall not exceed 10 parts per million (ppm) by volume, over an hourly rolling average (as measured and recorded by the continuous monitoring system during demonstration testing required by this Permit), dry basis, and reported as propane [40 CFR §63.1203(b)(5)(ii), in accordance with WAC 173-303-680(2)]:
8 9 10 11		x. If the emissions from the HLW Vitrification System exceed the emission rates listed in Permit Table III.10.J.E, as approved pursuant to Permit Condition III.10.C.11.b., the Permittees shall notify Ecology, in accordance with Permit Condition III.10.J.3.d.vii. [WAC 173-303-680(2) and (3), and WAC 173-303-815(2)(b)(ii)].
12 13 14 15 16		The emission limits specified in Permit Conditions III.10.J.1.b.i. through III.10.J.1.b.x. above, shall be met for the HLW Vitrification System by limiting feed rates as specified in Permit Tables III.10.J.D and III.10.J.F, as approved/modified pursuant to Permit Condition III.10.J.5., compliance with operating conditions specified in Permit Condition III.10.J.1.c. (except as specified in Permit Condition III.10.J.1.b.xii.), and compliance with Permit Condition III.10.J.1.b.xi.
18 19 20 21 22 23 24 25 26		xi. Treatment effectiveness, feed-rates and operating rates for dangerous and mixed waste management units contained in the HLW Building, but not included in Permit Table III.10.J.A, as approved/modified pursuant to Permit Condition III.10.J.5., shall be as specified in Permit Sections III.10.D, III.10.E, III.10.F and consistent with assumptions and basis which are reflected in Attachment 51, Appendix 6.3.1 of this Permit, as approved pursuant to Permit Condition III.10.C.11.b. For the purposes of this permit condition, Attachment 51, Appendix 6.3.1 shall be superceded by Appendix 6.4.1 upon its approval pursuant to either Permit Conditions III.10.C.11.c. or III.10.C.11.d. [WAC 173-303-680(2) and (3), and WAC 173-303-815(2)(b)(ii)].
27 28 29 30 31 32 33 34		xii. Compliance with the operating conditions specified in Permit Condition III.10.J.1.c., shall be regarded as compliance with the required performance standards identified in Permit Conditions III.10.J.1.b.i. through x. However, if it is determined that during the effective period of this Permit that compliance with the operating conditions in Permit Condition III.10.J.1.c. is not sufficient to ensure compliance with the performance standards specified in Permit Conditions III.10.J.1.b.i. through x., the Permit may be modified, revoked, or reissued pursuant to Permit Conditions III.10.C.2.e. and III.10.C.2.f., or III.10.C.2.g.
35	III.10.J.1.c.	Operating Conditions [WAC-303-670(6), in accordance with WAC 173-303-680(2) and (3)].
36 37 38 39 40 41		The Permittees shall operate the HLW Vitrification System in accordance with Attachment 51, Chapter 4.0 of this Permit, as updated pursuant to Permit Condition III.10.J.5.e.vi., and Attachment 51, Appendix 10.18 of this Permit, as approved pursuant to Permit Condition III.10.J.5.e., and Attachment 51, Appendix 10.15 of this Permit, as approved pursuant to Permit Condition III.10.J.5.f., except as modified pursuant to Permit Conditions III.10.J.1.b.xii., III.10.J.2., III.10.J.3., III.10.J.4., and in accordance with the following:

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 163 of 210

i The Permittees shall operate the HLW Vitrification System in order to maintain the systems and process parameters listed in Permit Tables III.10.J.C and III.10.J.F, as approved/modified pursuant to Permit Condition III.10.J.5., within the set-points specified in Permit Table III.10.J.F.

- ii. The Permittees shall operate the AWFCO systems, specified in Permit Table III.10.J.F, as approved/modified pursuant to Permit Condition III.10.J.5., to automatically cut-off and/or lock-out the dangerous and mixed waste feed to the HLW Vitrification System when the monitored operating conditions deviate from the set-points specified in Permit Table III.10.J.F.
- iii. The Permittees shall operate the AWFCO systems, specified in Permit Table III.10.J.F, as approved/modified pursuant to Permit Condition III.10.J.5., to automatically cut-off and/or lock-out the dangerous and mixed waste feed to the HLW Vitrification System when all instruments specified on Permit Table III.10.H.F for measuring the monitored parameters fails or exceeds its span value
- iv. The Permittees shall operate the AWFCO systems, specified in Permit Table III.10.J.F, as approved/modified pursuant to Permit Condition III.10.J.5., to automatically cut-off and/or lock out the dangerous and/or mixed waste feed to the HLW Vitrification System when any portion of the HLW Vitrification System is bypassed. The terms "bypassed" and "bypass event" as used in Permit Sections III.10.J and III.10.K shall mean if any portion of the HLW Vitrification System is bypassed so that gases are not treated as during the Demonstration Test.
- v. In the event of a malfunction of the AWFCO systems listed in Permit Table III.10.J.F, as approved/modified pursuant to Permit Condition III.10.J.5., the Permittees shall immediately, manually cut-off the dangerous and mixed waste feed to the HLW Vitrification System. The Permittees shall not restart the dangerous and/or mixed waste feed until the problem causing the malfunction has been identified and corrected.
- vi. The Permittees shall manually cut-off the dangerous and mixed waste feed to the HLW Vitrification System when the operating conditions deviate from the limits specified in Permit Condition III.10.J.1.c.i., unless the deviation automatically activates the waste feed cut-off sequence specified in Permit Conditions III.10.J.1.c.ii., III.10.J.1.c.iii., and/or III.10.J.1.c.iv.
- vii. If greater than thirty (30) dangerous and mixed waste feed cut-off, combined, to the HLW Vitrification System occur due to deviations from Permit Table III.10 J.F., as approved/modified pursuant to Permit Condition III.10 J.5., within a sixty (60) day period, the Permittees shall submit a written report to Ecology within five (5) calendar days of the thirty-first exceedance including the information specified below. These dangerous and mixed waste feed cut-offs to the HLW Vitrification System, whether automatically or manually activated, are counted if the specified set-points are deviated from while dangerous waste, mixed waste, and waste residues continue to be processed in the HLW Vitrification System. A cascade event is counted at a frequency of one (1) towards the first waste feed cut-off parameter, specified on Permit Table III.10 J.F, from which the set-point is deviated:

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 164 of 210

1		A. The parameter(s) that deviated from the set-point(s) in Permit Table III.10.J.F;
2_		B. The magnitude, dates, and duration of the deviations;
3		C. Results of the investigation of the cause of the deviations; and,
4		D. Corrective measures taken to minimize future occurrences of the deviations.
5 6 7 8 9		viii. If any portion of the HLW Vitrification System is bypassed while treating dangerous and/or mixed waste, it shall be regarded as non-compliance with the operating conditions specified in Permit Condition III.10.J.1.c. and the performance standards specified in Permit Condition III.10.J.1.b. After such a bypass event, the Permittees shall perform the following actions:
10		A. Investigate the cause of the bypass event;
11		B. Take appropriate corrective measures to minimize future bypasses;
12 13		C. Record the investigation findings and corrective measures in the operating record and
14 15		D. Submit a written report to Ecology within five (5) days of the bypass event documenting the result of the investigation and corrective measures.
16 17	. i	x. The Permittees shall control fugitive emissions from the HLW Vitrification System by maintaining the melter under negative pressure.
18 19 20 21 22 23	X	Compliance with the operating conditions specified in Permit Condition III.10.J.1.c. shall be regarded as compliance with the required performance standards identified in Permit Condition III.10.J.1.b. However, evidence that compliance with these operating conditions is insufficient to ensure compliance with the performance standards, shall justify modification, revocation, or re-issuance of this Permit, in accordance with Permit Conditions III.10.C.2.e. and III.10.C.2.f., or III.10.C.2.g.
24	III.10.J.1.d. I	nspection Requirements [WAC 173-303-680(3)].
25 26 27		The Permittees shall inspect the HLW Vitrification System in accordance with the Inspection Schedules in Attachment 51, Chapter 6.0 of this Permit, as modified in accordance with Permit Condition III.10.C.5.c.
28 29 30	#2.	The inspection data for HLW Vitrification System shall be recorded, and the records shall be placed in the WTP Unit operating record for the HLW Vitrification System, i accordance with Permit Condition III.10.C.4.
31 32 33 34	i	ii. The Permittees shall comply with the inspection requirements specified in Attachmen 51, Appendix 10.15 of this Permit, as approved pursuant to Permit Condition III.10.J.5.f., and as modified by Permit Conditions III.10.J.1.b.xii., III.10.J.2., III.10.J.3., and III.10.J.4.
35 36		Monitoring Requirements [WAC 173-303-670(5), WAC 173-303-670(6), WAC -173-303-670(7), and WAC 173-303-807(2), in accordance with WAC 173-303-680(3)]
37 38	i.	Upon receipt of a written request from Ecology, the Permittees shall perform sampling and analysis of the dangerous and mixed waste and exhaust emissions to verify that the

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 165 of 210

2		operating requirements established in the Permit achieve the performance standards delineated in this Permit.
3 4 5 6	ii.	The Permittees shall comply with the monitoring requirements specified in Attachment 51, Appendices 10.2, 10.3, 10.7, 10.13, 10.15, and 10.18 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.c., III.10.J.5.d., III.10.J.5.e., and III.10.J.5.f., as modified by Permit Conditions III.10.J.1.b.xii., III.10.J.2., III.10.J.3., and III.10.J.4.
7 8 9 10 11 12 13	iii.	The Permittees shall operate, calibrate, and maintain the carbon monoxide and hydrocarbon continuous emission monitors (CEM) specified in this Permit in accordance with Performance Specification 4B and 8A of 40 CFR Part 60, Appendix B, in accordance with Appendix to Subpart EEE of 40 CFR Part 63, and Attachment 51 Appendix 10.15 of this Permit, as approved pursuant to Permit Condition III.10.J.5.f., and as modified by Permit Conditions III.10.J.1.b.xii., III.10.J.2., III.10.J.3., and III.10.J.4.
14 15 16 17 18	iv.	The Permittees shall operate, calibrate, and maintain the instruments specified on Permit Tables III.10.J.C and F, as approved/modified pursuant to Permit Condition III.10.J.5., in accordance with Attachment 51, Appendix 10.15 of this Permit, as approved pursuant to Permit Condition III.10.J.5.f., and as modified by Permit Conditions III.10.J.1.b.xii., III.10.J.2., III.10.J.3., and III.10.J.4.
19	III.10.J.1.f. Rec	cordkeeping Requirements [WAC 173-303-380 and WAC 173-303-680(3)]
20 21 22 23 24	i.	The Permittees shall record and maintain in the WTP Unit operating record for the HLW Vitrification System, all monitoring, calibration, maintenance, test data, and inspection data compiled under the conditions of this Permit, in accordance with Permit Conditions III.10.C.4. and III.10.C.5., as modified by Permit Conditions III.10.J.1.b.xii., III.10.J.2., III.10.J.3., and III.10.J.4.
25 26 27 28 29	ii.	The Permittees shall record in the WTP Unit operating record the date, time, and duration of all automatic waste feed cut-offs and/or lockouts, including the triggering parameters, reason for the deviation, and recurrence of the incident. The Permittees shall also record all incidents of AWFCO system function failures, including the corrective measures taken to correct the condition that caused the failure.
30 31 32	iii.	The Permittees shall submit to Ecology a report semi-annually the first calendar year, and annually thereafter each calendar year within ninety (90) days following the end of the year. The report will include the following information:
33 34		A. Total dangerous and mixed waste feed processing time for the HLW Vitrification System;
35		B. Date/Time of all HLW Vitrification System startups and shutdowns;
36 37 38		 C. Date/Time/Duration/Cause/Corrective Action taken for all HLW Vitrification System shutdowns caused by malfunction of either process or control equipment; and
	•	

Permit Number: WA7890008967
Modification to Revision 7
Expiration Date: September 27, 2004
Page 166 of 210

1 2 3		D. Date/Time/Duration/Cause/Corrective Action taken for all instances of dangerous and/or mixed waste feed cut-off due to deviations from Permit Table III.10.J.F, as approved/modified pursuant to Permit Condition III.10.J.5.
4 5 6 7	i	v. The Permittees shall submit an annual report to Ecology each calendar year within ninety (90) days following the end of the year of all quarterly CEM Calibration Error and Annual CEM Performance Specification Tests conducted in accordance with Permit Condition III.10.J.1.e.iii.
8 9 10	Ш.10.Ј.1.g.	Closure The Permittees shall close the HLW Vitrification System in accordance with Attachment 51, Chapter 11.0 of this Permit, as approved pursuant to Permit Condition III.10.C.8.
11 12	III.10.J.2.	Shakedown Period [WAC 173-303-670(5), WAC 173-303-670(6), WAC -173-303-670(7), and WAC 173-303-807(2), in accordance with WAC 173-303-680(2) and (3)].
13 14 15 16	III.10.J.2.a.	The shakedown period for the HLW Vitrification System shall be conducted in accordance with Permit Condition III.10.J.1., Attachment 51, Appendix 10.15 of this Permit, as approved pursuant to Permit Condition III.10.J.5.f., and as modified in accordance with Permit Conditions III.10.J.1.b.xii., III.10.J.2., and III.10.J.3.
17	III.10.J.2.b.	Duration of the Shakedown Period
18 19 20		 The shakedown period for the HLW Vitrification System shall begin with the initial introduction of dangerous waste in the HLW Vitrification System following construction and shall end with the start of the demonstration test.
21 22 23 24 25		ii. The shakedown period shall not exceed the following limits, as defined by hours of operation of the HLW Vitrification System with dangerous waste. The Permittees may petition Ecology for one (1) extension of each shakedown phase for seven hundred and twenty (720) additional operating hours in accordance with permit modification procedures specified in Permit Conditions III.10.C.2.e. and III.10.C.2.f.
26	e Section 1	Shakedown Phase 1: 720 hours
27		Shakedown Phase 2: 720 hours
28 29 30 31		iii. Shakedown Phase 2 shall not be commenced until documentation has been submitted to Ecology verifying that the HLW Vitrification System has operated at a minimum of 75% of the shakedown Phase 1 feed-rate limit for two (2) separate eight (8) consecutive hour periods with no AWFCOs:
32	III.10.J.2.c.	Allowable Waste Feed During the Shakedown Period
33 34 35 36 37		i. The Permittees may feed the dangerous waste specified for the HLW Vitrification System on the Part A Forms (Attachment 51, Chapter 1.0 of this Permit), except for those waste outside the waste acceptance criteria specified in the WAP, Attachment 51, Chapter 3.0 of this Permit, as approved pursuant to Permit Condition III.10.C.3., except Permit Conditions III.10.J.2.c.ii. through v. also apply.
38 39		ii. The Permittees shall not feed the following waste to the HLW Vitrification System during Shakedown Phase 1:

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 167 of 210

1 Acutely toxic dangerous waste listed in WAC 173-303-081(a)(2)(a)(i). Mixed waste 3 The Permittees shall not feed the following waste to the HLW Vitrification System 4 during Shakedown Phase 2: A. Mixed waste 5 The feed-rates to the HLW Vitrification System shall not exceed the limits in Permit 6 Tables III.10.J.D and III.10.J.F, as approved/modified pursuant to Permit Condition 7 III.10.J.5. The Permittees shall conduct sufficient analysis of the dangerous waste treated in the HLW Vitrification System to verify that the waste feed is within the physical and 10 chemical composition limits specified in this Permit. 11 III.10.J.3. Demonstration Test Period [WAC 173-303-670(5), WAC 173-303-670(6), WAC 173-303-12 670(7), and WAC 173-303-807(2), in accordance with WAC 173-303-680(2) and (3)] 13 III.10.J.3.a. Demonstration Test Period 14 The Permittees shall operate, monitor, and maintain the HLW Vitrification System as 15 specified in Permit Condition III.10.J.1., and Attachment 51, Appendix 10.15 of this 16 17 Permit, as approved pursuant to Permit Condition III.10.J.5.f., except as modified in accordance with Permit Conditions III.10.J.1.b.xii. and III.10.J.3. 18 19 Attachment 51, Appendix 10.15 of this Permit, as approved pursuant to Permit Condition III.10.J.5.f., shall be re-submitted to Ecology for approval by the Permittees 20 21 as a permit modification pursuant to Permit Conditions III.10.C.2.e. and III.10.C.2.f. at 22 least one hundred and eighty (180) days prior to the start date of the demonstration test. 23 The revised Demonstration Test Plan shall include applicable EPA promulgated test 24 methods and procedures in effect at the time of the re-submittal and projected .25 commencement and completion dates for the Demonstration Test. 26 The Permittees shall not commence the demonstration test period until documentation 27 has been submitted to Ecology verifying that the HLW Vitrification System has 28 operated at a minimum of 90% of the demonstration test period feed-rate limit for a minimum of an eight (8) consecutive hours period on two (2) consecutive days. 29 30 III.10.J.3.b. Performance Standards The Permittees shall demonstrate compliance with the performance standards specified in 31 32 Permit Condition III.10.J.1.b. during the Demonstration Test Period. 33 III.10.J.3.c. Allowable Waste Feed During the Demonstration Test Period 34 The Permittees may feed the dangerous waste specified for the HLW Vitrification 35 System in Part A Forms (Attachment 51, Chapter 1.0 of this Permit), except for those 36 waste outside the waste acceptance criteria specified in the WAP, Attachment 51, 37 Chapter 3.0 of this Permit, as approved pursuant to Permit Condition III.10.C.3., except Permit Conditions III.10.J.3.c.ii. through iv. also apply. 38

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 168 of 210

İ	11.	The Permittees shall not feed mixed waste to the HLW Vitilication System.
2 3 4	iv.	The dangerous waste feed-rates to the HLW Vitrification System shall not exceed the limits in Permit Tables III.10.J.D and F, as approved/modified pursuant to Permit Condition III.10.J.5.
5 6 7	y.	The Permittees shall conduct sufficient analysis of the dangerous waste treated in the HLW Vitrification System to verify that the dangerous waste is within the physical and chemical composition limits specified in this Permit.
8	III.10.J.3.d. De	monstration Data Submissions and Certifications
9 10 11 12 13 14	i.	The Permittees shall submit a summary of data collected as required during the Demonstration Test to Ecology upon completion of the Demonstration Test. The Permittees shall submit to Ecology a complete demonstration test report within one hundred and twenty (120) calendar days of completion of the Demonstration Test including all data collected during the Demonstration Test and updated Permit Tables III.10.K.D, III.10.K.E, and III.10.K.F.
15 16 17 18	ii.	The Permittees must submit to Ecology a certification that the Demonstration Test has been carried out in accordance with the approved Demonstration Test Plan and approved modifications within thirty (30) days of the completion of the Demonstration Test [WAC 173-303-807(8)].
19 20 21 22 23 24	iii.	After successful completion of the Demonstration Test, the Permittees shall be authorized to commence feed of dangerous waste and mixed waste to the HLW Vitrification System - up to 50% of the maximum feed-rates for the post-demonstration test period indicated in Permit Tables III.10.J.D and F, as approved/modified pursuant to Permit Condition III.10.J.5., in compliance with the operating requirements specified in Permit Condition III.10.J.1.c.
25 26 27 28 29 30 31 32 33	iv.	After successful completion of the Demonstration Test, Permittees submittal of the following to Ecology, and the Permittees receipt of Ecology approval of the following in writing, the Permittees shall be authorized to commence dangerous waste and mixed waste to the HLW Vitrification System up to 75% of the maximum feed-rates for the post-demonstration test period indicated in Permit Tables III.10.J.D and F, as approved/modified pursuant to Permit Condition III.10.J.5., in compliance with the operating requirements specified in Permit Condition III.10.J.1.c.: A. Calculations and analytical data showing compliance with the performance standard specified in Permit Condition III.10.J.1.b.i.
34 35 36 37	v.	After successful completion of the Demonstration Test, Permittees submittal of the following to Ecology, and Permittees receipt of Ecology approval of the following in writing, the Permittees shall be authorized to feed dangerous waste and mixed waste to the HLW Vitrification System pursuant to Permit Section III.10.K.
38 39 40		A. A complete Demonstration Test Report for the HLW Vitrification System and updated Permit Tables III.10.K.D, III.10.K.E, and III.10.K.F, as approved/modified pursuant to Permit Conditions III.10.J.5 and III.10.C.11.c. or

Permit Number: WA7890008967
Modification to Revision 7
Expiration Date: September 27, 2004
Page 169 of 210

1 2		III.10.C.11.d., the test report shall be certified in accordance with WAC 173-303-807(8), in accordance with WAC 173-303-680(2) and (3).
3 4		B. A Final Risk Assessment Report completed pursuant to Permit Conditions III.10.C.11.c. or III.10.C.11.d.
5 6 7 8	vi.	If any calculations or testing results show that one or more of the performance standards listed in Permit Condition III.10.J.1.b., with the exception of Permit Condition III.10.J.1.b.x., for the HLW Vitrification System were not met during the Demonstration Test, the Permittees shall perform the following actions:
9 10 11		A. Immediately stop dangerous and mixed waste feed to the HLW Vitrification System under the mode of operation that resulted in not meeting the performance standard(s).
12 13		B. Verbally notify Ecology within twenty-four (24) hours of discovery of not meeting the performance standard(s) as specified in Permit Condition I.E.21.
14 15 16		C. Investigate the cause of the failure and submit a report of the investigation findings to Ecology within fifteen (15) days of discovery of not meeting the performance standard(s).
17 18 19 20 21		D. Submit to Ecology within fifteen (15) days of discovery of not meeting the performance standard(s), documentation supporting a mode of operation where all performance standards listed in Permit Condition III.10.J.1.b., with the exception of Permit Condition III.10.J.1.b.x., for the HLW Vitrification System were met during the demonstration test, if any such mode was demonstrated.
22 23 24 25 26 27 28		E. Based on the information provided to Ecology by the Permittees, pursuant to Permit Conditions III.10.J.3.d.vi.A through D above, and any additional information, Ecology may submit, in writing, direction to the Permittees to stop dangerous and/or mixed waste feed to the LAW Vitrification System and/or amend the mode of operation the Permittees are allowed to continue operations prior to Ecology approval of a compliance schedule and/or revised Demonstration Test Plan, pursuant to Permit Conditions III.10.J.3.d.vi.F and G.
29 30 31 32 33 34 35 36 37		F. If the performance standard listed in Permit Condition III.10.J.1.b.i. was not met during the Demonstration Test, the Permittees shall submit within one hundred and twenty (120) days of discovery of not meeting the performance standard, a revised Demonstration Test Plan (if appropriate) and a compliance schedule for Ecology approval to address this deficiency. If a revised Demonstration Test Plan is submitted, it shall be accompanied by a request for approval to retest as a permit modification pursuant to Permit Conditions II.10.C.2.e. and III.10.C.2.f. The revised Demonstration Test Plan (if submitted) must include substantive changes to prevent failure from reoccurring.
38 39 40 41		G. If any of the performance standards listed in Permit Condition III.10.J.1.b., with the exception of Permit Conditions III.10.J.1.b.i. or III.10.J.1.b.x., were not met during the Demonstration Test, the Permittees shall submit to Ecology within one hundred and twenty (120) days of discovery of not meeting the performance

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 170 of 210

1 · 2		standard(s), a revised Demonstration Test Plan requesting approval to retest as a permit modification pursuant to Permit Conditions II.10.C.2.e. and III.10.C.2.f.
3	-	The revised Demonstration Test Plan must include substantive changes to prevent
4	:	failure from reoccurring.
5		vii. If any calculations or testing results show that any emission rate for any constituent
6		listed in Permit Table III.10.J.E, as approved pursuant to Permit Condition
7		III.10.C.11.b., is exceeded for HLW Vitrification System during the Demonstration
8		Test, the Permittees shall perform the following actions:
9 10		A. Verbally notify Ecology within twenty-four (24) hours of the discovery of exceeding the emission rate(s) as specified in Permit Condition I.E.21.
. 11		B. Submit to Ecology additional risk information to indicate that the increased
12		emissions impact is offset by decreased emission impact from one or more
13		constituents expected to be emitted at the same time, and/or investigate the cause
14		and impact of the exceedance of the emission rate(s) and submit a report of the
15	· · · · · · · · · · · · · · · · · · ·	investigation findings to Ecology within fifteen (15) days of the discovery of
16		exceeding the emission rate(s); and,
17		C. Based on the notification and any additional information, Ecology may submit, in
18	,	writing, direction to the Permittees to stop dangerous and/or mixed waste feed to
19		the HLW Vitrification System and/or to submit a revised Demonstration Test Plan
20		as a permit modification pursuant to Permit Conditions III.10.C.2.e. and
21		III.10.C.2.f., or III.10.C.2.g. The revised Demonstration Test Plan must include
22		substantive changes to prevent failure from reoccurring.
23	III.10.J.4.	Post-Demonstration Test Period [WAC 173-303-670(5), WAC 173-303-670(6), and WAC
24		173-303-807(2), in accordance with WAC 173-303-680(2) and (3)].
25	III.10.J.4.a.	The Permittees shall operate, monitor, and maintain the HLW Vitrification System as
26		specified in Permit Condition III.10.J.1. and Attachment 51, Appendix 10.15 of this Permit,
27		as approved pursuant to Permit Condition III.10.J.5., except as modified in accordance with
28		Permit Conditions III.10.J.1.b.xii., III.10.J.3., and III.10.J.4.
29	III.10.J.4.b.	Allowable Waste Feed During the Post-Demonstration Test Period
30		i. The Permittees may feed the dangerous and/or mixed waste specified for the HLW
31		Vitrification System on the Part A Forms (Attachment 51, Chapter 1.0 of this Permit),
32		except for those waste outside the waste acceptance criteria specified in the WAP,
33		Attachment 51, Chapter 3.0 of this Permit, as approved pursuant to Permit Condition
34	-	III.10.C.3., and except Permit Conditions III.10.J.4.b.ii. and III.10.J.4.b.iii. also apply.
35		ii. The dangerous waste and mixed waste feed rates to the HLW Vitrification System shall
36		not exceed the limits in Permit Tables III.10.J.D and F, as approved/modified pursuant
37		to Permit Condition III.10.J.5., or in Permit Condition III.10.J.3.
38		iii. The Permittees shall conduct sufficient analysis of the dangerous waste and mixed
39	and the first of the second	waste treated in HLW Vitrification System to verify that the waste feed is within the
40		physical and chemical composition limits specified in this Permit.

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 171 of 210

III.16).J.5.	Compliance	Schedules

- 2 III.10.J.5.a. All information identified for submittal to Ecology in a. through f. of this compliance 3 schedule must be signed and certified in accordance with requirements in WAC 173-303-4 810(12), as modified in accordance with Permit Condition III.10.J.1.a.iii. [WAC 173-303-806(4)].
- III.10.J.5.b. The Permittees shall submit to Ecology, pursuant to Permit Condition III.10.C.9.f., prior to construction of each secondary containment and leak detection system for the HLW Vitrification System (per level) as identified in Permit Tables III.10.J.A and III.10.J.B, engineering information as specified below, for incorporation into Attachment 51, Appendices 10.2, 10.4, 10.5, 10.7, 10.8, 10.9, 10.11, and 10.12 of this Permit. At a minimum, engineering information specified below will show the following as described in WAC 173-303-640, in accordance with WAC 173-303-680 (the information specified below will include dimensioned engineering drawings and information on sumps and floor drains):
 - i. IQRPE Reports (specific to foundation, secondary containment, and leak detection system) shall include review of design drawings, calculations, and other information on which the certification report is based and shall include, but not limited to, review of such information described below. Information (drawings, specifications, etc.) already included in Attachment 51, Appendix 10.0 of this Permit, may be included in the report by reference and should include drawing and document numbers. IQRPE Reports shall be consistent with the information separately provided in ii. through ix. below [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)];
 - ii. Design drawings (General Arrangement Drawings, plan and cross sections) and specifications for the foundation, secondary containment including liner installation details, and leak detection methodology. These items should show the dimensions, volume calculations, and location of the secondary containment system, and should include items such as floor/pipe slopes to sumps, tanks, floor drains [WAC 173-303-640(4)(b) through (f) and WAC 173-303-640(3)(a), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)];
 - iii. The Permittees shall provide the design criteria (references to codes and standards, load definitions, and load combinations, materials of construction, and analysis/design methodology) and typical design details for the support of the secondary containment system. This information shall demonstrate the foundation will be capable of providing support to the secondary containment system, resistance to pressure gradients above and below the system, and capable of preventing failure due to settlement, compression, or uplift [WAC 173-303-640(4)(c)(ii), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(B)];
 - iv. A description of materials and equipment used to provide corrosion protection for external metal components in contact with soil, including factors affecting the potential for corrosion [WAC 173-303-640(3)(a)(iii)(B), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(A) through (B)];

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 172 of 210

1 2		v.	Secondary containment/foundation, and leak detection system, materials selection documentation (including, but not limited to, concrete coatings and water stops, and
3		- 1400 575	liner materials), as applicable [WAC 173-303-806(4)(i)(i)(A) through (B)];
4 5 6		vi	Detailed description of how the secondary containment for the HLW Vitrification System will be installed in compliance with WAC 173-303-640(3)(c), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(A) through (B);
7 8 9 10 11 12		vii. viii.	Submit Permit Tables III.10.J.B and III.10.K.B completed to provide for all secondary containment sumps and floor drains the information, as specified in each column heading consistent with information to be provided in i. through vi., above; Documentation that secondary containment and leak detection systems will not accumulate hydrogen gas levels above the lower explosive limit for incorporation into the Administrative Record [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A), and WAC 173-303-806(4)(i)(v)];
14 15 16		ix.	A detailed description of how HLW Vitrification System design provides access for conducting future HLW Vitrification System integrity assessments [WAC 173-303-640(3)(b) and WAC 173-303-806(4)(i)(i)(B)].
17 18 19 20 21 22 23	III.10.J.5.c.	insta infor throu belowith	Permittees shall submit to Ecology pursuant to Permit Condition III.10.C.9.f., prior to allation of each sub-system as identified in Permit Table III.10.J.A, engineering relation as specified below, for incorporation into Attachment 51, Appendices 10.1 and 10.17 of this Permit. At a minimum, engineering information specified will show the following, as required pursuant to WAC 173-303-640, in accordance WAC 173-303-680 (the information specified below will include dimensioned neering drawings):
24 25 26 27 28 29 30 31 32		i.	IQRPE Reports (specific to sub-system) shall include review of design drawings, calculations, and other information on which the certification report is based and shall include as applicable, but not limited to, review of such information described below. Information (drawings, specifications, etc.) already included in Attachment 51, Appendix 10.0 of this Permit, may be included in the report by reference and should include drawing and document numbers. The IQRPE Reports shall be consistent with the information separately provided in ii. through xii. below and the IQRPE Report specified in Permit Condition III.10.J.5.b. [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)];
33 34 35 36 37 38			Design drawings [General Arrangement Drawings in plan and cross section, Process Flow Diagrams, Piping and Instrumentation Diagrams, (including pressure control systems), Mechanical Drawings, and specifications, and other information specific to subsystems (to show location and physical attributes of each subsystem specific to miscellaneous units)] [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)];
39 40 41			Sub-system design criteria (references to codes and, standards, load definitions, and load combinations, materials of construction, and analysis/design methodology) and typical design details to support the sub-systems. Structural support calculations

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 173 of 210

1 2		specific to off-specification, non-standard, and field-fabricated subsystems shall be submitted for incorporation into the Administrative Record. Documentation shall
3 4 5 6 7 8		include, but not be limited to, supporting specifications (test data, treatment effectiveness report, etc.), supporting projected operational capability (e.g., WESP projected removal efficiency for individual metals, halogens, particulates, etc.), and compliance with performance standards specified in Permit Condition III.10.J.1.b [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(B)];
9 10 11 12	îv	A description of materials and equipment used to provide corrosion protection for external metal components in contact with water, including factors affecting the potential for corrosion [WAC 173-303-640(3)(a)(iii)(B), in accordance with WAC 173 303-680(2) and WAC 173-303-806(4)(i)(i)(A) through (B)];
13 14 15	V.	Sub-system materials selection documentation (e.g., physical and chemical tolerances) [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(A)];
16 17 18 19 20	vi.	Sub-system vendor information (including, but not limited to, required performance warranties, as available), consistent with information submitted under ii. above, shall be submitted for incorporation into the Administrative Record [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(v)];
21 22 23	vii.	System descriptions (process) related to sub-system units shall be submitted for incorporation into the Administrative Record [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(v)];
24 25 26 27 28	viii.	Mass and energy balance for normal projected operating conditions used in developing the Piping and Instrumentation Diagrams and Process Flow Diagrams, including assumptions and formulas used to complete the mass and energy balance, so that they can be independently verified for incorporation into the Administrative Record [WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-806(4)(i)(v)];
29	ix.	Detailed description of all potential HLW Vitrification System bypass events including
30 31 32		A. A report which includes an analysis of credible potential bypass events and recommendations for prevention/minimization of the potential, impact, and frequency of the bypass event to include at a minimum:
33		1. Operating procedures
34		2. Maintenance procedures
35		3. Redundant equipment
36		4. Redundant instrumentation
37		5. Alternate equipment
38		6. Alternate materials of construction

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 174 of 210

1 2		x. A detailed description of how the sub-systems will be installed in compliance with WAC 173-303-640(3)(b), (c), (d), and (e), in accordance with WAC 173-303-680 and
3		WAC 173-303-806(4)(i)(i)(B);
4 5 6 7		xi. Sub-system design to prevent escape of vapors and emissions of acutely or chronically toxic (upon inhalation) EHW, for incorporation into the Administrative Record [WAC 173-303-640(5)(e), in accordance with WAC 173-303-680, (2), and WAC 173-303-806(4)(i)(i)(B)];
8 9 10 11		xii. Documentation that sub-systems are designed to prevent the accumulation of hydrogen gases levels above the lower explosive limit for incorporation into the Administrative Record [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A), and WAC 173-303-806(4)(i)(v)];
12 13 14 15 16 17 18	III.10.J.5.d.	installation of equipment for each sub-system as identified in Permit Tables III.10.J.A and III.10.J.B, not addressed in Permit Conditions III.10.J.5.b. or III.10.J.5.c., engineering information as specified below, for incorporation into Attachment 51, Appendices 10.1 through 10.14 of this Permit. At a minimum, engineering information specified below will show the following as required pursuant to in WAC 173-303-640, in accordance with WAC 173-303-680 (the information specified below will include dimensioned engineering drawings):
20 21 22 23 24 25 26 27 28 29		i. IQRPE Reports (specific to sub-system equipment) shall include a review of design drawings, calculations, and other information as applicable on which the certification report is based. The reports shall include, but not be limited to, review of such information described below. Information (drawings, specifications, etc.) already included in Attachment 51, Appendix 10.0 of this Permit, may be included in the report by reference and should include drawing and document numbers. The IQRPE Reports shall be consistent with the information provided separately in ii. through xiii. below and the IQRPE Reports specified in Permit Conditions III.10.J.5.b. and III.10.J.5.c. [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(I)(I)(A) through (B)];
30 31 32 33 34		ii. Design drawings [Process Flow Diagrams, Piping and Instrumentation Diagrams (including pressure control systems), and specifications, and other information specific to equipment (these drawings should include all equipment such as pipes, valves, fittings, pumps, instruments, etc.)] [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(A) through (B)];
35 36 37 38 39		iii. Sub-system equipment design criteria (references to codes and standards, load definitions and load combinations, materials of construction, and analysis/design methodology) and typical design details for the support of the sub-system equipment. [WAC 173-303-640(3)(a) and WAC 173-303-640(3)(f), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(B)];
40 41		iv. A description of materials and equipment used to provide corrosion protection for

Expiration Date: September 27, 2004 Page 175 of 210

	1 2	·	the potential for corrosion [WAC 173-303-640(3)(a)(iii)(B), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(A)];
2	3 4 5	v.	Materials selection documentation for equipment for each sub-system (e.g., physical and chemical tolerances) [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2) and WAC 173-303-806(4)(i)(i)(A)];
)	vi.	Vendor information (including, but not limited to, required performance warranties, as available), consistent with information submitted under ii. above, for sub-system equipment shall for equipment shall be submitted for incorporation into the Administrative Record [WAC 173-303-640(3)(a), in accordance with WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(iv)];
11 12 13 14	2 s 3	vii.	Sub-system, sub-system equipment, and leak detection system instrument control logic narrative description (e.g., software functional specifications, descriptions of fail-safe conditions, etc.) [WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-806(4)(i)(v)];
15 16 17 18	5 !	viii.	System description (process) related to sub-system equipment, and system descriptions related to leak detection systems, (including instrument control logic and narrative descriptions), for incorporation into the Administrative Record [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(v)];
19 20 21).	ix.	A detailed description of how the sub-system equipment will be installed and tested [WAC 173-303-640(3)(c) through (e) and WAC 173-303-640(4)(b) and (c), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(B)];
22 23 24 25 26 27		X.	For process monitoring, control, and leak detection system instrumentation for the HLW Vitrification System as identified in Permit Tables III.10.J.C. and III.10.J. F., a detailed description of how the process monitoring, control, and leak detection system instrumentation will be installed and tested [WAC 173-303-640(3)(c) through (e), WAC 173-303-640(4)(b) and (c), WAC 173-303-806(4)(c)(vi), and WAC 173-303-806(4)(i)(i)(B)];
28 29 30 31 32		xi.	Mass and energy balance for projected normal operating conditions used in developing the Piping and Instrumentation Diagrams and Process Flow Diagrams, including assumptions and formulas used to complete the mass and energy balance, so that they can be independently verified, for incorporation into the Administrative Record [WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-806(4)(i)(v)];
33 34 35 36		xii.	Documentation that sub-systems equipment are designed to prevent the accumulation of hydrogen gas levels above the lower explosive limit into the Administrative Record [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A), and WAC 173-303-806(4)(i)(v)] [WAC 173-303-815(2)(b)(ii)];
37 38 39 40		xiii.	Leak Detection system documentation (e.g. vendor information etc.) consistent with information submitted under Permit Condition III.10.J.5.c.ii. and Permit Conditions III.10.J.5.d.ii., vii., viii., and x. above, shall be submitted for incorporation into the Administrative Record.

Expiration Date: September 27, 2004

Page 176 of 210

	· ·	
1	III.10.J.5.e.	Prior to initial receipt of dangerous and/or mixed waste in the WTP Unit, the Permittees
2	•	shall submit to Ecology, pursuant to Permit Condition III.10.C.9.f., the following as
3		specified below for incorporation into Attachment 51, Appendix 10.18 of this Permit, except
4	1.5	Permit Condition III.10.J.5.e.i., which will be incorporated into Attachment 51, Chapter 6.0
5		of this Permit. All information provided under this permit condition must be consistent with
6		information provided pursuant to Permit Conditions III.10.J.5.b., c., d., e., and f.,
7		III.10.C.3.e.v., and III.10.C.11.b., as approved by Ecology:
8	4	i. Integrity assessment program and schedule for the HLW Vitrification System shall
9		address the conducting of periodic integrity assessments on the HLW Vitrification
10	100	System over the life of the system, as specified in Permit Condition III.10 J.5.b.ix. and

- i. Integrity assessment program and schedule for the HLW Vitrification System shall address the conducting of periodic integrity assessments on the HLW Vitrification System over the life of the system, as specified in Permit Condition III.10 J.5.b.ix. and as specified in WAC 173-303-640(3)(b), in accordance with WAC 173-303-680, and descriptions of procedures for addressing problems detected during integrity assessments. The schedule must be based on past integrity assessments, age of the system, materials of construction, characteristics of the waste, and any other relevant factors [WAC 173-303-640(3)(b), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(B)];
- ii. Detailed plans and descriptions, demonstrating the leak detection system is operated so that it will detect the failure of either the primary or secondary containment structure or the presence of any release of dangerous and/or mixed waste or accumulated liquid in the secondary containment system within twenty-four (24) hours [WAC 173-303-640(4)(c)(iii)]. Detection of a leak of at least 0.1 gallons per hour within twenty-four (24) hours is defined as being able to detect a leak within twenty-four (24) hours. Any exceptions to this criteria must be approved by Ecology in accordance with WAC 173-303-680, WAC 173-303-640(4)(c)(iii), and WAC 173-303-806(4)(i)(i)(b);
- iii. Detailed operational plans and descriptions, demonstrating that spilled or leaked waste and accumulated precipitation liquids can be removed from the secondary containment system within twenty-four (24) hours [WAC 173-303-806(4)(i)(i)(B)];
- iv. Descriptions of operational procedures demonstrating appropriate controls and practices are in place to prevent spills and overflows from the HLW Vitrification System or containment systems in compliance with WAC 173-303-640(5)(b)(i) through (iii), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(B);
- v. Description of procedures for investigation and repair of the HLW Vitrification System [WAC 173-303-640(6) and WAC 173-303-640(7)(e) and (f), in accordance with WAC 173-303-680, WAC 173-303-320, WAC 173-303-806(4)(ia)(iv), and WAC 173-303-806(4)(a)(ii)(B)];
- vi. Updated Chapter 4.0, Narrative Description, Tables and Figures as identified in Permit Tables III.10.J.A and III.10.J.B, as modified pursuant to Permit Condition III.10.H.5.e.x. and updated to identify routinely non-accessible LAW Vitrification subsystems.

Expiration Date: September 27, 2004

Page 177 of 210

1 2	vii.	Description of procedures for management of ignitable and reactive, and incompatible dangerous and/or mixed waste as specified in accordance with WAC 173-303-640(9)
3		and (10), in accordance with WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(B).
4 5	viii.	A description of the tracking system used to track dangerous and/or mixed waste generated throughout the HLW Vitrification System, pursuant to WAC 173-303-380.
6 7 8 9 10 11 12 13 14 15 16	ix.	Permit Table III.10.J.C and III.10.K.C shall be completed for HLW Vitrification. System process and leak detection system monitors and instruments (to include, but no be limited to: instruments and monitors measuring and/or controlling flow, pressure, temperature, density, pH, level, humidity, and emissions) to provide the information as specified in each column heading. Process and leak detection system monitors and instruments for critical systems, as specified in Attachment 51, Appendix 2.0 and as updated pursuant to Permit Condition III.10.C.9.b.and for operating parameters as required to comply with Permit Condition III.10.C.3.e.iii., shall be addressed. Process monitors and instruments for non-waste management operations (e.g., utilities, raw chemical storage, non-contact cooling waters, etc.) are excluded from this permit condition [WAC 173-303-680, WAC 173-303-806(4)(i)(i)(A) through (B), and WAC 173-303-806(4)(i)(v)];
18 19	х.	Permit Tables III.10.J.A and III.10.K.A amended as follows [WAC 173-303-680 and WAC 173-303-806(4)(i)(i)(A) through (B)]:
20 21 22		A. Under column 1, update and complete list of dangerous and mixed waste HLW Vitrification System sub-systems, including plant items that comprise each system (listed by item number).
23		B. Under column 2, update and complete system designations.
24 25 26		C. Under column 3, replace the 'Reserved' with Attachment 51, Appendix 10.0 subsections (e.g., 10.1, 10.2, etc.) designated in Permit Conditions III.10.J.5.b., c., and d. specific to HLW Vitrification System sub-system, as listed in column 1.
27 28		D. Under column 4, update and complete list of narrative description, tables, and figures.
29 30 31 32 33 34 35 36	in the incomposition for the part the I Appe	hundred and eighty (180) days prior to initial receipt of dangerous and/or mixed waste e WTP Unit, the Permittees shall submit for review and receive approval for reporation into Attachment 51, Appendix 10.15 of this Permit, a Demonstration Test Plante HLW Vitrification System to demonstrate that the HLW Vitrification Systems meets performance standards specified in Permit Condition III.10.J.1.b. In order to incorporate Demonstration Test Plan for the HLW Vitrification System into Attachment 51, endix 10.15, Permit Condition III.10.C.2.g. process will be followed. The constration Test Plan shall include, but not be limited to, the following information. The
37 38 39	Dem Pern	constration Test Plan shall also be consistent with the information provided pursuant to nit Conditions III.10.J.5.b., c., d. and e., III.10.C.3.e.v. and III.10.C.11.b., as approved cology and consistent with the schedule described in Attachment 51, Appendix 1.0 of

this Permit. The documentation required pursuant to Permit Condition III.10.J.5.f.xvi., in

Permit Number: WA7890008967
Modification to Revision 7
Expiration Date: September 27, 2004
Page 178 of 210

1 2	addition to being incorporated into Attachment 51, Appendix 10.15, shareference in Attachment 51, Chapter 6.0 of this Permit.	all be incorporated by
3 4 5 6 7 8	Notes: (1) The following should be consulted to prepare this Demonstration "Guidance on Setting Permit Conditions and Reporting Trial Burn Res Hazardous Waste Incineration Guidance Series", and EPA/625/6-89/0. Guidance For Hazardous Waste Combustion Facilities", EPA-R-01-00 173-303-807(2), WAC 173-303-670(5), WAC-173-303-670(6), 40 CFR CFR §63.1209 and Appendix to 40 CFR Part 63 EEE.	ults Volume II of the 19 and Risk Burn 1, July 2001, WAC
9 10 11	(2) Cross-referencing to the information provided pursuant to permit C c., d., e. and III.10.C.3.e.v., as approved by Ecology, that are redundan Demonstration Test Plan for the HLW Vitrification System is acceptabl	t to elements of the
12 13 14 15	 i. Analysis of each feed-stream to be fed during the demonstration to dangerous waste, glass formers and reductants, process streams (e. process air, steam, sparge bubbler air, air in-leakage from melter c HLW Vitrification Vessel Ventilation System, process water, etc.) 	g., control air, ave, and gases from
16 17	 A. Levels of ash, levels of metals, total chlorine (organic and inchalogens and radionuclide surrogates. 	organic), other
18	B. Description of the physical form of the feed-streams;	
19 20	 C. An identification and quantification of organics that are prese including constituents proposed for DRE demonstration; 	nt in the feed-stream
21 22 23 24 25 26	A comparison of the proposed demonstration test feed streams to t envelopes to be processed in the melter must be provided that doct proposed demonstration test feed streams will serve as worst case organic destruction, formation of products of incomplete oxidation chlorine (organic and inorganic), other halogens, particulate forma radionuclides;	ments that the surrogates for , and metals, total
27 28 29 30 31 32	 ii. Specification of trial principal organic dangerous constituents (PO destruction and removal efficiencies are proposed to be calculated demonstration test and for inclusion in Permit Conditions III.10.J.1 III.10.K.1.b.i. These trial PODCs shall be specified based on destruction or mass in the waste and the dangerous waste constitution in WAC 173-303-9905; 	during the l.b.i. and uctibility,
33 34	iii. A description of the blending procedures, prior to introducing the melter, including analysis of the materials prior to blending, and bl	
35 36 37 38	iv. A description of how the surrogate feeds are to be introduced for the This description should clearly identify the differences and justify differences would impact the surrogate feed introduction as representated waste feeds will be introduced;	how any of
39 -	v. A detailed engineering description of the HLW Vitrification System	m, including:
40	A. Manufacturer's name and model number for each sub-system	• •

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 179 of 210

1 2	В.	calculations, manufacturer/vendor specifications, operating data, etc.) supporting
3 4 5		projected operational efficiencies (e.g., WESP projected removal efficiency for individual metals, halogens, particulates, etc.) and compliance with performance standards specified in Permit Condition III.10.J.1.b.;
6 7 8	c.	Detailed scaled engineering drawings, including Process Flow Diagrams, Piping and Instrumentation Diagrams, Vessel Drawings (plan, and elevation with cross sections) and General Arrangement Drawings;
9	D.	Process Engineering Descriptions;
10 11 12 13	E .	Mass and energy balances for each projected operating condition and each demonstration test condition, including assumptions and formulas used to complete mass and energy balances so that they can be independently verified for incorporation into the Administrative Record;
14 15 16	F.	Engineering Specifications/data sheets (materials of construction, physical and chemical tolerances of equipment, equipment performance warranties, and fan curves);
17 18 19	G.	Detailed Description of Automatic Waste Feed Cut-off System addressing critical operating parameters for all performance standards specified in Permit Condition III.10.J.1.b.
20 21 22	н.	Documentation to support compliance with performance standards specified in Permit Condition III.10.J.1.b., including engineering calculations, test data, and manufacturer/vendor's warranties, etc.
23 24	I.	Detailed description of the design, operation and maintenance practices for air pollution control system.
25 26		Detailed description of the design, operation, and maintenance practices of any stack gas monitoring and pollution control monitoring system.
27 28 29 30 31	K.	Documentation based on current WTP Unit design either confirming the Permittees' demonstration that it is not technically appropriate to correct standard listed in Permit Conditions III.J.1.b.ii. through III.J.1.b.ix. to seven percent (7%) oxygen, or a request, pursuant to Permit Conditions III.10.C.9.e. and II.10.C.9.f., to update Permit Conditions III.J.1.b.ii. through III.J.1.b.ix., III.K.b.ii. through
32 33 34		III.K.b.ix., III.K.e.iii., and III.J.1.e.iii., Permit Tables III.10.J.C, III.10.J.F, III.10.K.C., III.10.K.F. and Attachment 51, Appendix 10.0 to reflect the addition o an oxygen monitor and the correction of the standards to seven percent (7%)

vi. Detailed description of sampling and monitoring procedures including sampling and monitoring locations in the system, the equipment to be used, sampling and monitoring frequency, and planned analytical procedures for sample analysis including, but not limited to:

35

36 37

38 39 oxygen.

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 180 of 210

A. A short summary narrative description of each stack sample method should be included within the main body of the demonstration test plan, which references an appendix to the plan that would include for each sampling train: (1) detailed sample method procedures, (2) sampling train configuration schematic, (3) sampling recovery flow sheet, (4) detailed analytical method procedures, and (5) sampling preparation and analysis flow sheet. The detailed procedures should clearly flag where the method has provided decision points (e.g., choices of equipment materials of construction, choices of clean-up procedures or whether additional clean-up procedures will be incorporated, whether pretest surveys or laboratory validation work will be performed, enhancements to train to accommodate high moisture content in stack gas, etc.) and what is being proposed along with the basis for the decision.

- B. A short summary narrative description of the feed and residue sampling methods should be included within the main body of the demonstration test plan, which references an appendix that would include for each sample type: (1) detailed sample method procedures, (2) sampling recovery/compositing procedures, and (3) detailed analytical method procedures. The detailed procedures should clearly flag where the method has provided decision points (e.g., choices of equipment materials of construction, choices of clean-up procedures or whether additional clean-up procedures will be incorporated, whether pretest surveys or laboratory validation work will be performed, etc.) and what is being proposed along with the basis for the decision.
- vii. A detailed test schedule for each condition for which the demonstration test is planned, including projected date(s), duration, quantity of dangerous waste to be fed, and other relevant factors;
- viii. A detailed test protocol including, for each test condition, the ranges of feed-rate for each feed system, and all other relevant parameters that may affect the ability of the HLW Vitrification System to meet performance standards specified in Permit Condition III.10.J.1.b.;
- ix. A detailed description of planned operating conditions for each demonstration test condition, including operating conditions for shakedown, demonstration test, post-demonstration test and normal operations. This information shall also include submittal of Permit Tables III.10.J.D, III.10.J.F, III.10.K.D, and III.10.K.F completed with the information as specified in each column heading for each HLW Vitrification System waste feed cut-off parameter and submittal of supporting documentation for Permit Tables III.10.J.D, III.10.J.F, III.10.K.D, and III.10.K.F set-point values.
- x. The test conditions proposed must demonstrate meeting the performance standards specified in Permit Condition III.10.J.1.b. with the simultaneous operation of the melter at capacity and input from the HLW Vitrification Vessel Ventilation System at capacity to simulate maximum loading to the HLW Vitrification System off-gas treatment system and to establish the corresponding operating parameter ranges.

Expiration Date: September 27, 2004 Page 181 of 210

1 · 2 · 3		xi.	A detailed description of procedures for start-up and shutdown of waste feed and controlling emissions in the event of an equipment malfunction, including off-normal and emergency shutdown procedures;
_			
. 4		X11.	A calculation of waste residence time;
5 6		xiii.	Any request to extrapolate metal feed-rate limits from Demonstration Test levels must include:
7 8 9		•	A. A description of the extrapolation methodology and rationale for how the approach ensures compliance with the performance standards, as specified in Permit Condition III.10.J.1.b.
10 11	e e e e e e e e e e e e e e e e e e e		B. Documentation of the historical range of normal metal feed-rates for each feedstream.
12 13 14 15			C. Documentation that the level of spiking recommended during the demonstration test will mask sampling and analysis imprecision and inaccuracy to the extent that extrapolation of feed-rates and emission rates from the Demonstration Test data will be as accurate and precise as if full spiking were used.
16 17 18 19		xiv.	Documentation of the expected levels of constituents in HLW Vitrification System input streams, including, but not limited to, waste feed, glass former and reactants, control air, process air, steam, sparge bubbler air, air in-leakage from melter cave, gases from HLW Vitrification Vessel Ventilation System, and process water.
20 21 22		XV.	Documentation justifying the duration of the conditioning required to ensure the HLW Vitrification System had achieved steady-state operations under Demonstration Test operating conditions.
23 24 25		xvi.	Documentation of HLW Vitrification System process and leak detection system instruments and monitors as listed on Permit Tables III.10.J.C, III.10.J.F, III.10.K.C, and III.10.K.F to include:
26			A. Procurement specifications
27			B. Location used
28			C. Range, precision, and accuracy
29 30			D. Calibration/functionality test procedures (either method number ASTM) or provide a copy of manufacturer's recommended calibration procedures
31 32 33 34 35 36			E. Calibration/functionality test, inspection, and routine maintenance schedules and checklists, including justification for calibration, inspection and maintenance frequencies, criteria for identifying instruments found to be significantly out of calibration, and corrective action to be taken for instruments found to be significantly out of calibration (e.g., increasing frequency of calibration, instrument replacement, etc.).
37 38 39		-	F. Equipment instrument control logic narrative description (e.g., software functional specifications, descriptions of fail safe conditions, etc.) [WAC 173-303-680(2), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-806(4)(i)(v)]

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 182 of 210

xvii. Outline of demonstration test report.

1

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 183 of 210

Table III.10.J.A - HLW Vitrification System Description

		<u> </u>	
Sub-system Description	Sub-system Designation	Engineering Description (Drawing Nos., Specification Nos., etc.)	Narrative Description, Tables, and Figures
Melter Feed ^a System – Melter 1	HFP HCP	***	Section 4.2.4.1; Table 4-5 & 4-11, Figures 4A-1, 4A-4, 4A-26
HLW Melter 1	НМР		Section 4.2.4.2; Figures 4A-1, 4A-4, 4A-27
HLW Glass Product System-Melter 1	НМР		Section 4.2.4.2; Figures 4A-1, 4A-4, 4A-27
Film Cooler - Melter 1	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-27
Submerged Bed Scrubber /Condensate Collection Vessels ^a -Melter 1	НОР		Section 4.2.4.3; Table 4-5 & 4-11, Figures 4A-1, 4A-4, 4A-28
Wet Electrostatic Precipitator-Melter 1	НОР		Section 4,2.4.3; Figures 4A-1, 4A-4, 4A-28
High Efficiency Particulate Air Filters	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-29
High Efficiency Mist Eliminator	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-28
Thermal Catalytical Oxidation Unit	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-29
Selective Catalytical Reduction Unit	НОР	24590-HLW	Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-29

Sub-system Description	Sub-system Designation	Engineering	Narrative Description, Tables, and
		Description (Drawing	<u>Figures</u>
		Nos., Specification Nos., etc.)	
Silver Mordenite Column Melter 1 Silver Mordenite	НОР	<u>-M6-HOP-P0008</u>	Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-
Column HLW-MV-HOP-ABS-00002, Melter 2		-M6-HOP-P20008	29
Silver Mordenite Column HLW-MV-HOP-ABS-	,	-MKD-HOP-P0014	
<u>00003</u>		-MKD-HOP-P0017	
		<u>-3PS-MBTO-TP001</u>	
Electric Heaters	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A
			29
Heat Exchangers	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-
			29
Pumps	HOP		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A+
			27, 4A-28, 4A-29
Booster Fans	НОР	-	Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-29
FILW Stack	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-29

a. Requirements pertaining to the tanks in HLW Vitrification System Melter Feed System, Submerged Bed Scrubber/Condensate Vessels are specified in Permit Section III.10.E.

Permit Number: WA7890008967

Modification to Revision 7
Expiration Date: September 27, 2004
Page 185 of 210

Table III.10.J.B. - HLW Vitrification Systems Secondary Containment Systems Including Sumps and Floor Drains

Sump/Floor Drain I.D.# & Room Location	Maximum Sump Capacity (gallons)	Sump Dimensions (feet) & Materials of Construction	Maximum Allowable Liquid Height (inches)	Secondary Containment Volume (gallons)	Engineering Description (Drawing Nos., Specification
					Nos., etc.)
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

Table III.10.J.C. - . HLW Vitrification System Process and Leak Detection System Instruments and Parameters

Sub-system Locator and	Control Parameter	Type of Measuring or	Location of Measuring	Instrument Range	Expected Range	Fail States	Instrument Accuracy	Instrument Calibration
Name (including) 	Leak Detection	Instrument (Tag No.)	36.2 T				Method No. and Range
P&ID)		Instrument						
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 186 of 210

Table III.10.J.D. - Maximum Feed-rates to HLW Vitrification System (RESERVED)

Description of Waste	Shakedown 1 and Post Demonstration Test	Shakedown 2 and Demonstration Test		
Dangerous and Mixed Waste Feed Rate				
Ash Feed Rate				
Total Chlorine/Chloride Feed Rate				
Total Metal Feedrates				

3

Table III.10.J.E. - HLW Vitrification System Estimated Emission Rates (RESERVED)

Chemicals	CAS Number	Emission Rates	
		(grams /second)	

7

Table III.10.J.F. - HLW Vitrification System Waste Feed Cut-off Parameters* (RESERVED)

Subsystem Designation	Instrument Tag Number	Parameter Description	Setpoints During Shakedown 1 and Post Demonstration Test	Setpoints During Shakedown 2 and Demonstration Test
	l a e e e e e e	·		·

^{*}A continuous monitoring system shall be used as defined in Permit Section III.10.C.1.

Maximum Feed-rate shall be set based on not exceeding any of the constituent (e.g., metals, ash, and
 chlorine/chloride) feed limits specified on Table III.10.J.D. of this Permit

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004
Page 187 of 210

1	III.10.K	HLW VITILICATION System – Long 1 erm Miscellaneous 1 nermal 1 reatment Unit
2 3 4 5 6		For purposes of Permit Section III.10.K, where reference is made to WAC 173-303-640, the following substitutions apply: substitute the terms "HLW Vitrification System" for "tank system(s)," "sub-system(s)" for "tank(s)," "sub-system equipment" for "ancillary equipment," and "sub-system(s) or sub-system equipment of a HLW Vitrification System" for "component(s)," in accordance with WAC 173-303-680.
7	III.10.K.1	Requirements For HLW Vitrification System Beginning Normal Operation
8 9 10 11 12 13 14 15 16 17		Prior to commencing normal operations provided in Permit Section III.10.K, all requirements in Permit Section III.10.J shall have been met by the Permittees and approved by Ecology, including the following: The HLW Vitrification System Demonstration Test results and the revised Final Risk Assessment provided for in Permit Conditions III.10.C.11.c. or d. and Permit Section III.10.J, shall have been evaluated and approved by Ecology, Permit Tables III.10.K.D and F, as approved/modified pursuant to Permit Condition III.10.J.5, shall have been completed, submitted and approved pursuant to Permit Condition III.10.J.3.d.v. and Permit Table III.10.K.E, as approved/modified pursuant to Permit Condition III.10.J.5, shall have been completed, submitted and approved pursuant to Permit Conditions III.10.J.5, shall have been completed, submitted and approved pursuant to Permit Conditions III.10.C.11.c. or d.
18 19	III.10.K.1.a.	Construction and Maintenance [WAC 173-303-640, in accordance with WAC 173-303-680(2) and (3), and WAC 173-303-340]
20 21 22 23		i. The Permittees shall maintain the design and construction of the HLW Vitrification System as specified in Permit Condition III.10.K.1, Attachment 51, Chapter 4.0 of this Permit, and Attachment 51, Appendices 10.1 through 10.17 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.a. through d. and III.10.J.5.f.
24 25 26 27		ii. The Permittees shall maintain the design and construction of all containment systems for the HLW Vitrification System as specified in Attachment 51, Chapter 4.0 of this Permit, and Attachment 51, Appendices 10.2 and 10.4 through 10.14 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.a. through d.
28 29 30		iii. Modifications to approved design, plans, and specifications in Attachment 51, of this Permit, for the HLW Vitrification System shall be allowed only in accordance with Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g., III.10.C.9.d., e., and h.
31 32 33 34 35		iv. The Permittees shall ensure all certifications required by specialists (e.g., independent, qualified, registered professional engineer; registered, professional engineer; independent corrosion expert; independent, qualified installation inspector; installation inspector; etc.) use the following statement or equivalent pursuant to Permit Condition III.10.C.10:
36 37 38 39 40		"I, (Insert Name) have (choose one or more of the following: overseen, supervised, reviewed, and/or certified) a portion of the design or installation of a new HLW Vitrification system or component located at (address), and owned/operated by (name(s)). My duties were: (e.g., installation inspector, testing for tightness, etc.), for the following HLW Vitrification system components (e.g., the venting piping, etc.), as

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 188 of 210

required by the Dangerous Waste Regulations, namely, WAC 173-303-640(3) (applicable paragraphs [i.e., (a) through (g)]), in accordance with WAC 173-303-680.

"I certify under penalty of law that I have personally examined and am familiar with the information submitted in this document and all attachments and that, based on my inquiry of those individuals immediately responsible for obtaining the information, I believe that the information is true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment."

- v. The Permittees shall ensure periodic integrity assessments are conducted on the HLW Vitrification System listed in Permit Table III.10.I.A, as approved/modified pursuant to Permit Condition III.10.J.5, over the term of this Permit, in accordance with WAC 173-303-680(2) and (3), as specified in WAC 173-303-640(3)(b) following the description of the integrity assessment program and schedule in Attachment 51, Chapter 6.0 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.e.i. and III.10.C.5.c. Results of the integrity assessments shall be included in the WTP Unit operating record until ten (10) years after post-closure, or corrective action is complete and certified, whichever is later.
- vi. The Permittees shall address problems detected during the HLW Vitrification System integrity assessments specified in Permit Condition III.10.K.1.a.v. following the description of the integrity assessment program in Attachment 51, Chapter 6.0 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.e.i. and III.10.C.5.c.
- vii. All process monitors/instruments as specified in Permit Table III.10.K.F, as approved/modified pursuant to Permit Condition III.10.J.5 and III.10.J.3.d.v., shall be equipped with operational alarms to warn of deviation, or imminent deviation from the limits specified in Permit Table III.10.K.F.
- viii. The Permittees shall install and test all process and leak detection system monitors/instruments, as specified in Permit Tables III.10.K.C and III.10.K.F, as approved/modified pursuant to Permit Conditions III.10.J.5 and III.10.J.3.d.v., in accordance with Attachment 51, Appendices 10.1, 10.2, and 10.14 of this Permit, as approved pursuant to Permit Conditions III.10.J.5.d.x. and III.10.J.5.f.xvi.
- ix. No dangerous and/or mixed waste shall be treated in the HLW Vitrification System unless the operating conditions, specified under Permit Condition III.10.K.1.c. are complied with.
- x. The Permittees shall not place dangerous and/or mixed waste, treatment reagents, or other materials in the HLW Vitrification System if these substances could cause the sub-system, sub-system equipment, or the containment system to rupture, leak, corrode, or otherwise fail [WAC 173-303-640(5)(a), in accordance with WAC 173-303-680(2)]. This condition is not applicable to corrosion of HLW Vitrification System sub-system or sub-system equipment that are expected to be replaced as part of normal operations (e.g., melter).

Expiration Date: September 27, 2004

Page 189 of 210

xi. The Permittees shall operate the HLW Vitrification System to prevent spills and overflows using the description of controls and practices as required under WAC 173-303-640(5)(b), described in Permit Condition III.10.C.5, and Attachment 51, Appendix 10.18 of this Permit, as approved pursuant to Permit Condition III.10.J.5.e. [WAC 173-303-640(5)(b), in accordance with WAC 173-303-680(2) and (3), WAC-173-303-806(4)(c)(ix)].

1 2

.27

- xii. For routinely non-accessible HLW Vitrification System sub-systems, as specified in Attachment 51, Chapter 4.0 of this Permit, as updated pursuant to Permit Condition III.10.J.5.e.vi., the Permittees shall mark all routinely non-accessible HLW Vitrification System sub-systems access points with labels or signs to identify the waste contained in each HLW Vitrification System sub-system. The label, or sign, must be legible at a distance of at least fifty (50) feet, and must bear a legend which identifies the waste in a manner which adequately warns employees, emergency response personnel, and the public of the major risk(s) associated with the waste being stored or treated in the HLW Vitrification System sub-systems. For the purposes of this permit condition, "routinely non-accessible" means personnel are unable to enter these areas while waste is being managed in them [WAC 173-303-640(5)(d), in accordance with WAC 173-303-680(2)].
- xiii. For all the HLW Vitrification System sub-systems not addressed in Permit Condition III.10.K.1.a.xii., the Permittees shall mark all these HLW Vitrification System sub-systems holding dangerous and/or mixed waste with labels or signs to identify the waste contained in the HLW Vitrification System sub-systems. The labels, or signs, must be legible at a distance of at least fifty (50) feet, and must bear a legend which identifies the waste in a manner which adequately warns employees, emergency response personnel, and the public of the major risk(s) associated with the waste being stored or treated in the HLW Vitrification System sub-systems [WAC 173-303-640(5)(d), in accordance with WAC 173-303-680(2)].
- xiv. The Permittees shall ensure that the secondary containment systems for the HLW Vitrification System sub-systems listed in Permit Tables III.10.K.A and III.10.K.B, as approved/modified pursuant to Permit Condition III.10.J.5, are free of cracks or gaps to prevent any migration of dangerous and/or mixed waste or accumulated liquid out of the system to the soil, groundwater, or surface water at any time during the use of the HLW Vitrification System sub-systems. Any indication that a crack or gap may exist in the containment systems shall be investigated and repaired in accordance with Attachment 51, Appendix 10.18 of this Permit, as approved pursuant to Permit Condition III.10.J.5.e.v. [WAC 173-303-640(4)(b)(i), WAC 173-303-640(4)(e)(i)(C), and WAC 173-303-640(6), in accordance with WAC 173-303-680(2) and (3), WAC 173-303-806(4)(i)(i)(B), and WAC 173-303-320].
- xv. The Permittees must immediately and safely remove from service any HLW Vitrification System or secondary containment system which through an integrity assessment is found to be "unfit for use" as defined in WAC 173-303-040, following Permit Condition III.10.K.1.a.xvii.A through D, and F. The affected HLW Vitrification System or secondary containment system must be either repaired or closed

Expiration Date: September 27, 2004

Page 190 of 210

1 2			in accordance with Permit Condition III.10.K.1.a.xvii.E [WAC 173-303-640(7)(e) and (f) and WAC 173-303-640(8), in accordance with WAC 173-303-680(3)].
3 4		xvi.	An impermeable coating, as specified in Attachment 51, Appendices 10.4, 10.5, 10.7, 10.9, 10.11, and 10.12 of this Permit, as approved pursuant to Permit Condition
5			III.10.J.5.b.v., shall be maintained for all concrete containment systems and concrete
6			portions of containment systems for the HLW Vitrification System sub-systems listed
7 8			in Permit Tables III.10. K.A and III.10.K.B, as approved/modified pursuant to Permit Condition III.10.J.5 (concrete containment systems that do not have a liner, pursuant to
9			WAC 173-303-640(4)(e)(i), in accordance with WAC 173-303-680(2), and have
10			construction joints, shall meet the requirements of WAC 173-303-640(4)(e)(ii)(C), in
11	and the second		accordance with WAC 173-303-680(2). The coating shall prevent migration of any
12			dangerous and/or mixed waste into the concrete. All coatings shall meet the following
13			performance standards:
14 15	en en en en en en en en en en en en en e		A. The coating must seal the containment surface such that no cracks, seams, or other avenues through which liquid could migrate are present;
	**	.74	
16			B. The coating must be of adequate thickness and strength to withstand the normal operation of equipment and personnel within the given area such that degradation
17 18			or physical damage to the coating or lining can be identified and remedied before
19			dangerous and/or mixed waste could migrate from the system; and
20 21 22 23			C. The coating must be compatible with the dangerous and/or mixed waste, treatment reagents, or other materials managed in the containment system [WAC 173-303-640(4)(e)(ii)(D), in accordance with WAC 173-303-680(2) and (3), and WAC 173-303-806(4)(i)(i)(A)].
24		xvii	The Permittees shall inspect all secondary containment systems for the HLW
25		25 (22)	Vitrification System sub-systems listed in Permit Tables III.10.K.A and III.10.K.B, as
26			approved/modified pursuant to Permit Condition III.10.J.5., in accordance with the
27	er en er er er er er er er er er er er er er	4.4.1	Inspection Schedule specified in Attachment 51, Chapter 6.0 of this Permit, as
28			approved pursuant to Permit Conditions III.10.J.5.e.i. and III.10.C.5.c., and take the
29 30			following actions if a leak or spill of dangerous and/or mixed waste is detected in these containment systems [WAC 173-303-640(5)(c), WAC 173-303-640(6) in accordance
31			with WAC 173-303-680(2) and (3), WAC 173-303-320, and WAC 173-303-
32			806(4)(i)(i)(B)]:
33 34			A. Immediately, and safely, stop the flow of dangerous and/or mixed waste into the HLW Vitrification System sub-systems or secondary containment system.
35			
36			C. Remove the dangerous and/or mixed waste from the containment area in
37			accordance with WAC 173-303-680(2) and (3), as specified in WAC 173-303-640(7)(b). The dangerous and/or mixed waste removed from containment areas of
· 38			the HI W Vitrification System shall be, at a minimum, managed as mixed waste.

D. If the cause of the release was a spill that has not damaged the integrity of the HLW Vitrification System sub-system, the Permittees may return the HLW

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 191 of 210

		Page 191 of 210	
1 2 3 4		Vitrification System sub-system to service in accordance with WAC 173-303-680(2) and (3), as specified in WAC 173-303-640(7)(e)(ii). In such case, the Permittees shall take action to ensure the incident that caused the dangerous and/or mixed waste to enter the containment system will not reoccur.	
5 6 7 8		E. If the source of the dangerous and/or mixed waste is determined to be a leak in from the primary HLW Vitrification System into the secondary containment system, or the system is unfit for use as determined through an integrity assessment or other inspection, the Permittees shall comply with the requirement of WAC 173-303-640(7) and take the following actions:	ts
10 11 12 13		 Close the HLW Vitrification System sub-system following procedures in WAC 173-303-640(7)(e)(i), in accordance with WAC 173-303-680, and Attachment 51, Chapter 11.0 of this Permit, as approved pursuant to Permit Condition III.10.C.8; or 	
14 15 16 17 18 19 20		 Repair and re-certify (in accordance with WAC 173-303-810(13)(a), as modified pursuant to Permit Condition III.10.K.1.a.iii.) the HLW Vitrification System, in accordance with Attachment 51, Appendix 10.18 of this Permit, as approved pursuant to Permit Condition III.10.J.5.e.v., before the HLW Vitrification System is placed back into service [WAC 173-303-640(7)(e)(iii) and WAC 173-303-640(7)(f), in accordance with WAC 173-303-680]. 	
21 22 23		The Permittees shall document in the operating record actions/procedures taken to comply with A through E above, as specified in WAC 173-303-640(6)(d), in accordance with WAC 173-303-680(2) and (3).	to
24 25 26		6. In accordance with WAC 173-303-680(2) and (3), the Permittees shall notify and report releases to the environment to Ecology as specified in WAC 173-303-640(7)(d).	đ
27 28 29 30 31 32 33 34	xviii	If liquids (e.g., dangerous and/or mixed waste, leaks and spills, precipitation, fire vater, liquids from damaged or broken pipes) cannot be removed from the secondary ontainment system within twenty-four (24) hours, Ecology will be verbally notified within twenty-four (24) hours of discovery. The notification shall provide the information in A, B, and C, listed below. The Permittees shall provide Ecology with a written demonstration within seven (7) business days, identifying at a minimum [WA673-303-640(4)(c)(iv) and WAC 173-303-640(7)(b)(ii), in accordance with WAC 173-303-680(3) and WAC 173-303-806(4)(i)(i)(B)]:	a C
35		. Reasons for delayed removal;	
36 · 37		Measures implemented to ensure continued protection of human health and the environment;	,
38		Current actions being taken to remove liquids from secondary containment.	
39 40 41	xix.	all air pollution control devices and capture systems in the HLW Vitrification System hall be maintained and operated at all times in a manner so as to minimize the missions of air contaminants and to minimize process upsets. Procedures for ensuring	

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 192 of 210

1 2		that the air pollution control devices and capture systems in the HLW Vitrification System are properly operated and maintained so as to minimize the emission of air
3		contaminants and process upsets shall be established.
4 5	XX. :	In all future narrative permit submittals, the Permittees shall include HLW Vitrification sub-system names with the sub-system designation.
6 7 8 9	xxi.	For any portion of the HLW Vitrification System which has the potential for formation and accumulation of hydrogen gases, the Permittees shall operate the portion to maintain hydrogen levels below the lower explosive limit [WAC 173-303-815(2)(b)(ii)].
10 11 12 13	xxii	For each HLW Vitrification System sub-system holding dangerous waste which are acutely or chronically toxic by inhalation, the Permittees shall operate the system to prevent escape of vapors, fumes, or other emissions into the air [WAC 173-303-806(4)(i)(i)(B) and WAC 173-303-640(5)(e), in accordance with WAC 173-303-680].
14	III.10.K.1.b. Perf	ormance Standards
15 16 17 18	i	The HLW Vitrification System must achieve a destruction and removal efficiency (DRE) of 99.99% for the principal organic dangerous constituents (PODCs) listed below [40 CFR §63.1203(c)(1) and 40 CFR §63.1203(c)(2), in accordance with WAC 173-303-680(2)]:
19		RESERVED
20 21		DRE in this Permit Condition shall be calculated in accordance with the formula given below:
22		$DRE=[1-(W_{out}/W_{in})] \times 100\%$
23		Where:
24 25		W _{in} =mass feed-rate of one principal organic dangerous constituent (PODC) in a waste feedstream; and
26 27		W _{out} =mass emission rate of the same PODC present in exhaust emissions prior to release to the atmosphere.
28 29 30	ii.	Particulate matter emissions from the HLW Vitrification System shall not exceed 34 mg/dscm (0.015 grains/dscf) [40 CFR §63.1203(b)(7), in accordance with WAC 173-303-680(2)];
31 32 33	iii.	Hydrochloric acid and chlorine gas emissions from the HLW Vitrification System shall not exceed 21 ppmv, combined [40 CFR §63.1203(b)(6), in accordance with WAC 173-303-680(2)];
34 35 36	iv.	Dioxin and Furan TEQ emissions from the HLW Vitrification System shall not exceed 0.2 nanograms (ng)/dscm [40 CFR §63.1203(b)(1), in accordance with WAC 173-303-680(2)];
37 38	v.	Mercury emissions from the HLW Vitrification System shall not exceed 45 $\mu g/dscm$ [40 CFR §63.1203(b)(2), in accordance with WAC 173-303-680(2)];

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 193 of 210

1 Lead and cadmium emissions from the HLW Vitrification System shall not exceed 120 2 μg/dscm, combined [40 CFR §63.1203(b)(3), in accordance with WAC 173-303-3 680(2)]; 4 vii. Arsenic, beryllium, and chromium emissions from the HLW Vitrification System shall not exceed 97 µg/dscm, combined [40 CFR §63.1203(b)(4), in accordance with WAC 5 173-303-680(2)]; 6 viii. Carbon monoxide (CO) emission from the HLW Vitrification System shall not exceed 8 100 parts per million (ppm) by volume, over an hourly rolling average (as measured 9 and recorded by the continuous monitoring system), dry basis [40 CFR 10 §63.1203(b)(5)(i), in accordance with WAC 173-303-680(2) and (3)]: 11 Hydrocarbon emission from the HLW Vitrification System shall not exceed 10 parts 12 per million (ppm) by volume, over an hourly rolling average (as measured and recorded 13 by the continuous monitoring system during demonstration testing required by this 14 Permit), dry basis and reported as propane [40 CFR §63.1203(b)(5)(ii), in accordance 15 with WAC 173-303-680(2) and (3)]: If the emissions from the HLW Vitrification System exceed the emission rates listed in 16 Permit Table III.10.K.E, as approved pursuant to Permit Condition III.10.C.11.c. or d., 17 the Permittees shall perform the following actions [WAC 173-303-680(2) and (3), and 18 19 WAC 173-303-815(2)(b)(ii)]: 20 Verbally notify Ecology within twenty-four (24) hours of the discovery of 21 exceeding the emission rate(s) as specified in Permit Condition I.E.21: 22 Submit to Ecology additional risk information to indicate that the increased В. 23 emissions impact is off-set by decreased emission impact from one or more 24 constituents expected to be emitted at the same time, and/or investigate the cause 25 and impact of the exceedance of the emission rate(s) and submit a report of the 26 investigation findings to Ecology within fifteen (15) days of the discovery of 27 exceeding the emission rate(s); and 28 Based on the notification and any additional information, Ecology may submit, in writing, direction to the Permittees to stop dangerous and/or mixed waste feed to .29 30 the HLW Vitrification System and/or to submit a revised Demonstration Test Plan 31 as a permit modification pursuant to Permit Conditions III.10.C.2.e. and f., or 32 III.10.C.2.g. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring. 33 34 The emission limits specified in Permit Conditions III.10.K.1.b.i. through x. above, 35 shall be met for the HLW Vitrification System by limiting feed rates as specified in 36

shall be met for the HLW Vitrification System by limiting feed rates as specified in Permit Tables III.10.K.D and III.10.K.F, as approved/modified pursuant to Permit Condition III.10.J.5 and III.10.J.3.d.v., compliance with operating conditions specified in Permit Condition III.10.K.1.c. (except as specified in Permit Condition III.10.K.1.b.xii.), and compliance with Permit Condition III.10.K.1.b.xii.

xi. Treatment effectiveness, feed-rates, and operating rates for dangerous and/or mixed waste management units contained in the HLW Building, but not included in Permit

37

38

39

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 194 of 210

Table III.10.K.A, as approved/modified pursuant to Permit Condition III.10.J.5, shall 1 be as specified in Permit Sections III.10.D, III.10.E, III.10.F and consistent with the 2 assumptions and basis which are reflected in Attachment 51, Appendix 6.3.1 of this 4 Permit, as approved pursuant to Permit Condition III.10.C.11.b. For the purposes of this permit condition, Attachment 51, Appendix 6.3.1 shall be superceded by Appendix 5 6.4.1 upon its approval pursuant to either Permit Conditions III.10.C.11.c. or d. [WAC 6 173-303-680(2) and (3), and WAC 173-303-815(2)(b)(ii)]. 7 8 xii. Compliance with the operating conditions specified in Permit Condition III.10.K.1.c., shall be regarded as compliance with the required performance standards identified in 9 Permit Conditions III.10.K.1.b.i. through x. However, if it is determined that during 10 the effective period of this Permit that compliance with the operating conditions in 11 Permit Condition III.10.K.1.c. is not sufficient to ensure compliance with the 12 performance standards specified in Permit Conditions III.10.K.1.b.i. through x., the 13 Permit may be modified, revoked, or reissued pursuant to Permit Conditions 14 15 III.10.C.2.e. and f., or III.10.C.2.g. III.10.K.1.c. Operating Conditions [WAC-303-670(6), in accordance with WAC 173-303-680(2) and (3)] 16 The Permittees shall operate the HLW Vitrification System in accordance with Attachment 17 18 51, Chapter 4.0 of this Permit, as updated pursuant to Permit Condition III.10.J.5.e.vi., Attachment 51, Appendix 10.18 of this Permit, as approved pursuant to Permit Conditions 19 III.10.J.5.e. and f., and Attachment 51, Appendix 10.15 of this Permit, as approved pursuant 20 to Permit Condition III.10.J.5.f., except as modified pursuant to Permit Conditions III.10.J.3, 21 III.10.K.1.b.x., III.10.K.1.b.xii., III.10.K.1.h., and in accordance with and the following: 22 23 The Permittees shall operate the HLW Vitrification System in order to maintain the systems and process parameters listed in Permit Tables III.10.K.C and III.10.K.F, as 24 approved/modified pursuant to Permit Conditions III.10.J.5 and III.J.3.d.v., within the 25 26 set-points specified in Permit Table III.10.K.F. The Permittees shall operate the AWFCO systems, specified in Permit Table 27 III.10.K.F, as approved/modified pursuant to Permit Conditions III.10.J.5 and 28 III.J.3.d.v., to automatically cut-off and/or lock-out the dangerous and/or mixed waste 29 feed to HLW Vitrification System when the monitored operating conditions deviate 30 31 from the set-points specified in Permit Table III.10.K.F. The Permittees shall operate the AWFCO systems, specified in Permit Table 32 III.10.K.F, as approved/modified pursuant to Permit Conditions III.10.J.5 and 33 III.J.3.d.v., to automatically cut-off and/or lock-out the dangerous and/or mixed waste 34 35 feed to HLW Vitrification System when all instruments specified on Permit Table III.10.I.F for measuring the monitored parameters fails or exceeds its span value. 36 The Permittees shall operate the AWFCO systems, specified in Permit Table 37 III.10.K.F, as approved/modified pursuant to Permit Conditions III.10.J.5 and 38 III.J.3.d.v., to automatically cut-off and/or lock out the dangerous and/or mixed waste 39 feed to the HLW Vitrification System when any portion of the HLW Vitrification 40

System is bypassed. The terms "bypassed" and "bypass event" as used in Permit

Expiration Date: September 27, 2004

Page 195 of 210

Sections III.10.J and K shall mean if any portion of the HLW Vitrification System is bypassed so that gases are not treated as during the Demonstration Test.

- v. In the event of a malfunction of the AWFCO systems listed in Permit Table III.10.K.F, as approved/modified pursuant to Permit Conditions III.10.J.5 and III.J.3.d.v., the Permittees shall immediately, manually, cut-off the dangerous and/or mixed waste feed to the HLW Vitrification System. The Permittees shall not restart the dangerous and/or mixed waste feed until the problem causing the malfunction has been identified and corrected.
- vi. The Permittees shall manually cut-off the dangerous and/or mixed waste feed to the HLW Vitrification System when the operating conditions deviate from the limits specified in Permit Condition III.10.K.1.c.i., unless the deviation automatically activates the waste feed cut-off sequence specified in Permit Conditions III.10.K.1.c.ii., iii., and/or iv.
- vii. If greater than thirty (30) dangerous and/or mixed waste feed cut-off, combined, to the HLW Vitrification System occur due to deviations from Permit Table III.10.K.F, as approved/modified pursuant to Permit Conditions III.10.J.5 and III.J.3.d.v., within a sixty (60) day period, the Permittees shall submit a written report to Ecology within five (5) calendar days of the thirty-first (31) exceedance including the information specified below. These dangerous and/or mixed waste feed cut-offs to the HLW Vitrification System, whether automatically or manually activated, are counted if the specified set-points are deviated from while dangerous and/or mixed waste and waste residues continue to be processed in the HLW Vitrification System. A cascade event is counted at a frequency of one (1) towards the first waste feed cut-off parameter, specified on Permit Table III.10.K.F, from which the set-point is deviated:
 - A. The parameter(s) that deviated from the set-point(s) in Permit Table III.10.K.F;
 - B. The magnitude, dates, and duration of the deviations;
 - C. Results of the investigation of the cause of the deviations; and
 - D. Corrective measures taken to minimize future occurrences of the deviations.
- viii. If greater than thirty (30) dangerous and/or mixed waste feed cut-off, combined, to the HLW Vitrification System occur due to deviations from Permit Table III.10.K.F, as approved/modified pursuant to Permit Conditions III.10.J.5 and III.J.3.d.v., within a thirty (30) day period, the Permittees shall submit the written report required to be submitted pursuant to Permit Condition III.10.K.1.c.vii. to Ecology, on the first business day following the thirty-first exceedance. These dangerous and/or mixed waste feed cut-offs to the HLW Vitrification System, whether automatically or manually activated, are counted if the specified set-points are deviated from while dangerous and/or mixed waste and waste residues continue to be processed in the HLW Vitrification System. A cascade event is counted at a frequency of one (1) towards the first waste feed cut-off parameter, specified on Permit Table III.10.K.F, from which the set-point is deviated:

Permit Number: WA7890008967
Modification to Revision 7
Expiration Date: September 27, 2004
Page 196 of 210

1		In accordance with WAC 173-303-680(2) and (3), the Permittees may not resume
2		dangerous and/or mixed waste feed to the HLW Vitrification System until this written
3		report has been submitted; and
4 5		A. Ecology has authorized the Permittees, in writing, to resume dangerous and/or mixed waste feed, or
6		B. Ecology has not, within seven (7) days, notified the Permittees in writing of the following:
8 9		The Permittees written report does not document that the corrective measure taken will minimize future exceedances; and
10 11		The Permittees must take further corrective measures and document that these further corrective measures will minimize future exceedances.
12 13 14 15 16	ix.	If any portion of the HLW Vitrification System is bypassed while treating dangerous and/or mixed waste, it shall be regarded as non-compliance with the operating conditions specified in Permit Condition III.10.K.1.c. and the performance standards specified in Permit Condition III.10.K.1.b. After such a bypass event, the Permittees shall perform the following actions:
17	i de la companya de la companya de la companya de la companya de la companya de la companya de la companya de La companya de la co	A. Investigate the cause of the bypass event;
18		B. Take appropriate corrective measures to minimize future bypasses;
19 20		C. Record the investigation findings and corrective measures in the operating record and
21 22	en general de la companya de la comp	D. Submit a written report to Ecology within five (5) days of the bypass event documenting the result of the investigation and corrective measures.
23 24	x.	The Permittees shall control fugitive emissions from the HLW Vitrification System by maintaining the melter under negative pressure.
25 26 27 28 29 30	XI.	Compliance with the operating conditions specified in Permit Condition III.10.K.1.c. shall be regarded as compliance with the required performance standards identified in Permit Condition III.10.K.1.b. However, evidence that compliance with these operating conditions is insufficient to ensure compliance with the performance standards, shall justify modification, revocation, or re-issuance of this Permit, in accordance with Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g.
31	III.10.K.1.d. Insp	ection Requirements [WAC 173-303-680(3)]
32 33 34	i,	The Permittees shall inspect the HLW Vitrification System in accordance with the Inspection Schedules in Attachment 51, Chapter 6.0 of this Permit, as modified in accordance with Permit Condition III.10.C.5.c.
35 36 37	ii.	The inspection data for HLW Vitrification System shall be recorded, and the records shall be placed in the WTP Unit operating record for HLW Vitrification System, in accordance with Permit Condition III.10.C.4.

Modification to Revision 7

Expiration Date: September 27, 2004

Page 197 of 210

The Permittees shall comply with the inspection requirements specified in Attachment

2 51, Appendix 10.15 of this Permit, as approved pursuant to Permit Condition 3 III.10.J.5.f., and as modified by Permit Conditions III.10.J.3, III.10.K.1.b.x., III.10.K.1.b.xii., and III.10.K.1.h. 4 5 III.10.K.1.e. Monitoring Requirements [WAC 173-303-670(5), WAC 173-303-670(6), WAC 173-303-6 670(7), and WAC 173-303-807(2), in accordance with WAC 173-303-680(3)] 7 Upon receipt of a written request from Ecology, the Permittees shall perform sampling 8 and analysis of the dangerous and/or mixed waste and exhaust emissions to verify that 9 the operating requirements established in the permit achieve the performance standards delineated in this Permit. 10 The Permittees shall comply with the monitoring requirements specified in the 11 12 Attachment 51, Appendices 10.2, 10.3, 10.7, 10.13, 10.15, and 10.18 of this Permit, as approved pursuant to Permit Condition III.10.J.5, and as modified by Permit 13 14 Conditions III.10.J.3, III.10.K.1.h., and III.10.K.1.b.x. and xii. 15 The Permittees shall operate, calibrate, and maintain the carbon monoxide and hydrocarbon continuous emission monitors (CEM) specified in this Permit in 16 accordance with Performance Specifications 4B and 8A of 40 CFR Part 60, Appendix 17 B, in accordance with Appendix to Subpart EEE of 40 CFR Part 63, and Attachment 51 18 19 Appendix 10.15 of this Permit, as approved pursuant to Permit Condition III.10.J.5.f., 20 and as modified by Permit Conditions III.10.H.3, III.10.K.1.h., and III.10.K.1.b.x. and xii. 21 22 The Permittees shall operate, calibrate, and maintain the instruments specified on 23 Permit Tables III.10.K.C and F, as approved/modified pursuant to Permit Conditions 24 III.10.J.5 and III.J.3.d.v., in accordance with Attachment 51, Appendix 10.15 of this Permit, as approved pursuant to Permit Condition III.10.J.5.f., and as modified by 25 Permit Conditions III.10.J.3, III.10.K.1.h., and III.10.K.1.b.x. and xii. 26 III.10.K.1.f. Recordkeeping Requirements [WAC 173-303-380 and WAC 173-303-680(3)] 27 28 The Permittees shall record and maintain in the WTP Unit operating record for the HLW Vitrification System, all monitoring, calibration, maintenance, test data, and 29 inspection data compiled under the conditions of this Permit, in accordance with Permit 30 Conditions III.10.C.4 and 5 as modified by Permit Conditions III.10.J.3, III.10.K.1.h., 31 and III.10.K.1.b.x. and xii. 32 33 The Permittees shall record in the WTP Unit operating record the date, time, and 34 duration of all automatic waste feed cut-offs and/or lockouts, including the triggering 35 parameters, reason for the deviation, and recurrence of the incident. The Permittees shall also record all incidents of AWFCO system function failures, including the 36 corrective measures taken to correct the condition that caused the failure. 37 38 The Permittees shall submit to Ecology an annual report each calendar year within 39 ninety (90) days following the end of the year. The report will include the following 40 information:

1.

Expiration Date: September 27, 2004

Page 198 of 210

1 2		A. Total dangerous and/or mixed waste feed processing time for the HLW Vitrification System;
3		B. Date/Time of all HLW Vitrification System startups and shutdowns;
4 5 6		 C. Date/Time/Duration/Cause/Corrective Action taken for all HLW Vitrification System shutdowns caused by malfunction of either process or control equipment; and
7 8 9		D. Date/Time/Duration/Cause/Corrective Action taken for all instances of dangerous and/or mixed waste feed cut-off due to deviations from Permit Table III.10.K.F, as approved/modified pursuant to Permit Conditions III.10.J.5 and III.10J.3.d.v.
10 11 12 13		iv. The Permittees shall submit an annual report to Ecology each calendar year within ninety (90) days following the end of the year of all quarterly CEM Calibration Error and Annual CEM Performance Specification Tests conducted in accordance with Permit Condition III.10.K.1.e.iii.
14	III.10.K.1.g.	Closure
15 16		The Permittees shall close the HLW Vitrification System in accordance with Attachment 51, Chapter 11.0 of this Permit, as approved pursuant to Permit Condition III.10.C.8.
17 18	III.10.K.1.h.	Periodic Emission Re-testing Requirements [WAC 173-303-670(5), WAC 173-303-670(7), and WAC 173-303-807(2), in accordance with WAC 173-303-680(2) and (3)]
19		i. Dioxin and Furan Emission Testing
20 21 22 23 24 25 26 27		A. Within eighteen (18) months of commencing operation pursuant to Permit Section III.10.K, the Permittees shall submit to Ecology for approval, a Dioxin and Furan Emission Test Plan (DFETP) for the performance of emission testing of the HLW Vitrification System gases for dioxin and furans during "Normal Operating Conditions" as a permit modification in accordance with Permit Conditions III.10.C.2.e. and f. The DFETP shall include all elements applicable to dioxin and furan emission testing included in the "Previously Approved Demonstration Test Plan," applicable EPA promulgated test methods and procedures in effect at the
28 29 30		time of the submittal, and projected commencement and completion dates for dioxin and furan emission test. "Normal Operating Conditions" shall be defined for the purposes of this permit condition as follows:
31 32 33 34		1. Carbon monoxide emissions, dangerous and/or mixed waste feed-rate, and automatic waste feed cut-off parameters specified on Permit Table III.10.K.F (as approved/modified pursuant to Permit Conditions III.10.J.5 and III.10.J.3.d.v), that were established to maintain compliance with Permit

35

36

37

38 39

40

41

Condition III.10.K.1.b.iv., as specified in Attachment 51, Appendix 10.15 of

range of the average value over the previous twelve (12) months and the set-

this Permit (as approved pursuant to Permit Condition III.10.J.3.d. and in

accordance with III.10.K.1.b.xii. and III.10.K.1.c.xi.), are held within the

point value specified on Permit Table III.10.K.F. The average value is defined as the sum of the rolling average values recorded over the previous

twelve (12) months divided by the number of rolling averages recorded

Expiration Date: September 27, 2004

Page 199 of 210

during that time. The average value shall not include calibration data, malfunction data, and data obtained when not processing dangerous and/or mixed waste; and

1 2

2. Feed-rate of metals, ash, and chlorine/chloride are held within the range of the average value over the previous twelve (12) months and the set-point value specified on Permit Table III.10.K.D (as approved/modified pursuant to Permit Conditions III.10.J.5 and III.10.J.3.d.v). Feed-rate of organics as measured by TOC are held within the range of the average value over the previous twelve (12) months. The average value is defined as the sum of the rolling average values recorded over the previous twelve (12) months divided by the number of rolling averages recorded during that time. The average value shall not include data obtained when not processing dangerous and/or mixed waste.

For purposes of this permit Condition, the "Previously Approved Demonstration Test Plan" is defined to include the Demonstration Test Plan approved pursuant to Permit Condition III.10.J.5.f.

- B. Within sixty (60) days of Ecology's approval of the DFETP, or within thirty-one (31) months of commencing operation pursuant to Permit Section III.10.K, whichever is later, the Permittees shall implement the DFETP approved, pursuant to Permit Condition III.10.K,1.h.i.A.
- C. The Permittees shall resubmit the DFETP, approved pursuant to Permit Condition III.10.K.1.h.i.A, revised to include applicable EPA promulgated test methods and procedures in effect at the time of the submittal, and projected commencement and completion dates for dioxin and furan emission test as a permit modification in accordance with Permit Conditions III.10.C.2.e. and f. at twenty-four (24) months from the implementation date of the testing required pursuant to Permit Condition III.10.K.1.h.i.A and at reoccurring eighteen (18) month intervals from the implementation date of the previously approved DFETP. The Permittees shall implement these newly approved revised DFETPs every thirty-one (31) months from the previous approved DFETP implementation date or within sixty (60) days of the newly Ecology approved revised DFETP, whichever is later, for the duration of this Permit.
- D. The Permittees shall submit a summary of operating data collected pursuant to the DFETPs in accordance with Permit Conditions III.10.K.1.h.i.A and C to Ecology upon completion of the tests. The Permittees shall submit to Ecology the complete test report within ninety (90) calendar days of completion of the testing. The test reports shall be certified as specified in WAC 173-303-807(8), in accordance with WAC 173-303-680(2) and (3).
- E. If any calculations or testing results collected pursuant to the DFETPs in accordance with Permit Conditions III.10.K.1.h.i.A and C show that one or more of the performance standards listed in Permit Condition III.10.K.1.b., with the exception of Permit Condition III.10.K.1.b.x., for the HLW Vitrification System

Modification to Revision 7

Expiration Date: September 27, 2004

Page 200 of 210

were not met during the emission test, the Permittees shall perform the following 1. 2 actions: Immediately stop dangerous and/or mixed waste feed to the HLW 3 1. Vitrification System under the mode of operation that resulted in not meeting 4 the performance standard(s). 5 6 Verbally notify Ecology within twenty-four (24) hours of discovery of not meeting the performance standard(s) as specified in Permit Condition I.E.21. 7 8 3. Investigate the cause of the failure and submit a report of the investigation findings to Ecology within fifteen (15) days of discovery of not meeting the 9 performance standard(s). 10 Submit to Ecology within fifteen (15) days of discovery of not meeting the 11 performance standard(s) documentation supporting a mode of operation 12 where all performance standards listed in Permit Condition III.K.1.b., with 13 the exception of Permit Condition III.10.K.1.b.x., for the HLW Vitrification 14 System were met during the demonstration test, if any such mode was 15 16 demonstrated. Based on the information provided to Ecology by the Permittees, pursuant to 17 Permit Conditions III.10.K.1.h.i.E.1 through 4 above, and any additional 18 information, Ecology may submit, in writing, direction to the Permittees to 19 stop dangerous and/or mixed waste feed to the HLW Vitrification System 20 and/or amend the mode of operation the Permittees are allowed to continue 21 22 operations prior to Ecology approval of the revised Demonstration Test Plan 23 pursuant to Permit Condition III.10. K.1.h.i.E.6. Submit to Ecology within one hundred and twenty (120) days of discovery of 24 25 not meeting the performance standard(s) a revised Demonstration Test Plan requesting approval to retest as a permit modification pursuant to Permit 26 Conditions III. 10.C.2.e. and f. The revised Demonstration Test Plan must 27 28 include substantive changes to prevent failure from reoccurring reflecting performance under operating conditions representative of the extreme range 29 of normal conditions, and include revisions to Permit Tables III.10 K.D and 30 31 If any calculations or testing results collected pursuant to the DFETPs in 32 33 accordance with Permit Conditions III. 10.K. 1.h. i.A and C show that any emission rate for any constituent listed in Permit Table III.10.K.E, as approved/modified 34 pursuant to Permit Conditions III.10.C.11.c. or d., is exceeded for HLW 35 Vitrification System during the emission test, the Permittees shall perform the 36 following actions: 37 Verbally notify Ecology within twenty-four (24) hours of the discovery of 38 exceeding the emission rate(s) as specified in Permit Condition I.E.21; 39 Submit to Ecology additional risk information to indicate that the increased 40

41

emissions impact is off-set by decreased emission impact from one or more

Modification to Revision 7

Expiration Date: September 27, 2004

Page 201 of 210

constituents expected to be emitted at the same time, and/or investigate the cause and impact of the exceedance and submit a report of the investigation findings to Ecology within fifteen (15) days of this discovery of exceeding the emission rate(s); and

3. Based on the notification and any additional information, Ecology may submit, in writing, direction to the Permittees to stop dangerous and/or mixed waste feed to the HLW Vitrification System and/or to submit a revised Demonstration Test Plan as a permit modification pursuant to Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring reflecting performance under operating conditions representative of the extreme range of normal conditions, and include revisions to Permit Tables III.10.K.D and F.

ii. Non-organic Emission Testing

- A. Within forty-eight (48) months of commencing operation pursuant to Permit Section III.10.K, the Permittees shall resubmit to Ecology for approval the "Previously Approved Demonstration Test Plan" revised as a permit modification in accordance with Permit Conditions III.10.C.2.e. and f. The revised Demonstration Test Plan (RDTP) shall include applicable EPA promulgated test methods and procedures in effect at the time of the submittal, projected commencement and completion dates for emission testing to demonstrate performance standards specified in Permit Conditions III.10.K.1.b.ii., iii., v., vi., and vii., and non-organic emissions as specified in Permit Table III.10.K.E, as approved/modified pursuant to Permit Conditions III.10.J.3.d. and III.10.C.11.c. or d., under "Normal Operating Conditions." "Normal Operating Conditions" shall be defined for the purposes of this permit condition as follows:
 - 1. Carbon monoxide emissions, dangerous and/or mixed waste feed-rate, and automatic waste feed cut-off parameters specified in Permit Table III.10.K.F, as approved/modified pursuant to Permit Conditions III.10.J.3.d. and III.10.C.11.c. or d., that were established to maintain compliance with Permit Conditions III.10.K.1.b.ii., iii., v., vi., and vii., and non-organic emissions, as specified in Permit Table III.10.K.E, as specified in Attachment 51, Appendix 10.15 of this Permit (as approved pursuant to Permit Conditions III.10.J.3.d. and III.10.C.11.c. or d.), are held within the range of the average value over the previous twelve (12) months and the set-point value specified on Permit Table III.10.K.F. The average value is defined as the sum of the rolling average values recorded over the previous twelve (12) months divided by the number of rolling averages recorded during that time. The average value shall not include calibration data, malfunction data, and data obtained when not processing dangerous and/or mixed waste; and
 - 2. Feed-rate of metals, ash, and chlorine/chloride are held within the range of the average value over the previous twelve (12) months and the set-point value specified on Permit Table III.10.K.D, as approved/modified pursuant to

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 202 of 210

Permit Conditions III.10.J.3.d. and III.10.C.11.c. or d. The average value is defined as the sum of all rolling average values recorded over the previous twelve (12) months divided by the number of rolling averages recorded during that time. The average value shall not include data obtained when not processing dangerous and/or mixed waste.

For purposes of this permit Condition, the "Previously Approved Demonstration Test Plan" is defined to include the Demonstration Test Plan approved pursuant to Permit Condition III.10.J.5.f.

B. Within sixty (60) days of Ecology's approval of the RDTP, or within sixty (60) months of commencing operation pursuant to Permit Section III.10.K, whichever is later, the Permittees shall implement the RDTP approved pursuant to Permit Condition III.10.K.1.h.ii.A.

-32

- C. The Permittees shall resubmit the RDTP, approved pursuant to Permit Condition III.10.K.1.h.ii.A, revised to include applicable EPA promulgated test methods and procedures in effect at the time of the submittal, and projected commencement and completion dates for emission test as a permit modification in accordance with Permit Conditions III.10.C.2.e. and f. at forty-eight (48) months from the implementation date of the testing required pursuant to Permit Condition III.10.K.1.h.ii.A and at reoccurring forty-eight (48) month intervals from the implementation date of the previously approved RDTP. The Permittees shall implement these newly approved revised RDTP, every sixty (60) months from the previous approved RDTP implementation date or within sixty (60) days of the newly Ecology approved revised RDTP, whichever is later, for the duration of this Permit.
- D. The Permittees shall submit a summary of operating data collected pursuant to the RDTPs in accordance with Permit Conditions III.10.K.1.h.ii.A and C to Ecology upon completion of the tests. The Permittees shall submit to Ecology the complete test report within ninety (90) calendar days of completion of the testing. The test reports shall be certified pursuant to WAC 173-303-807(8), in accordance with WAC 173-303-680(2) and (3).
- E. If any calculations or testing results collected pursuant to the DFETPs in accordance with Permit Conditions III.10.K.1.h.ii.A and C show that any emission rate for any constituent listed in Permit Table III.10.K.E, as approved/modified pursuant to Permit Conditions III.10.J.3.d. and III.10.C.11.c. or d., is exceeded for HLW Vitrification System during the emission test, the Permittees shall perform the following actions:
 - 1. Verbally notify Ecology within twenty-four (24) hours of the discovery of exceeding the emission rate(s) as specified in Permit Condition I.E.21;
 - Submit to Ecology additional risk information to indicate that the increased emissions impact is off-set by decreased emission impact from one or more constituents expected to be emitted at the same time, and/or investigate the cause and impact of the exceedance and submit a report of the investigation

Expiration Date: September 27, 2004 Page 203 of 210

1 2	findings to Ecology within fifteen (15) days of this discovery of exceeding the emission rate(s); and
3 4 5 6 7 8 9	3. Based on the notification and any additional information, Ecology may submit, in writing, direction to the Permittees to stop dangerous and/or mixed waste feed to the HLW Vitrification System and/or to submit a revised Demonstration Test Plan as a permit modification pursuant to Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring reflecting performance under operating conditions representative of the extreme range of normal conditions, and include revisions to Permit Tables III.10.K.D and III.10.K.F.
12 13 14 15 16 17	F. If any calculations or testing results collected pursuant to the DFETPs in accordance with Permit Conditions III.10.K.1.h.ii.A and C show that one or more of the performance standards listed in Permit Condition III.10.K.1.b., with the exception of Permit Condition III.10.K.1.b.x., for the HLW Vitrification System were not met during the emission test, the Permittees shall perform the following actions:
18 19 20	 Immediately stop dangerous and/or mixed waste feed to the HLW Vitrification System under the mode of operation that resulted in not meeting the performance standard(s).
21 22	2. Verbally notify Ecology within twenty-four (24) hours of discovery of not meeting the performance standard(s), as specified in Permit Condition I.E.21.
23 24 25	3. Investigate the cause of the failure and submit a report of the investigation findings to Ecology within fifteen (15) days of discovery of not meeting the performance standard(s).
26 27 28 29 30 31	4. Submit to Ecology within fifteen (15) days of discovery of not meeting the performance standard(s) documentation supporting a mode of operation where all performance standards listed in Permit Condition III K.1.b., with the exception of Permit Condition III.10.K.1.b.x., for the HLW Vitrification System were met during the demonstration test, if any such mode was demonstrated.
32 33 34 35 36 37 38	5. Based on the information provided to Ecology by the Permittees pursuant to Permit Conditions III.10.K.1.h.ii.F.1 through 4 above, and any additional information, Ecology may submit, in writing, direction to the Permittees to stop dangerous and/or mixed waste feed to the HLW Vitrification System and/or amend the mode of operation the Permittees are allowed to continue operations prior to Ecology approval of the revised Demonstration Test Plan pursuant to Permit Condition III.10.K.1.h.ii.F.6.
39 40 41	6. Submit to Ecology within one hundred and twenty (120) days of discovery of not meeting the performance standard(s) a revised Demonstration Test Plan requesting approval to retest as a permit modification pursuant to Permit

Permit Number: WA7890008967 Modification to Revision 7 Expiration Date: September 27, 2004 Page 204 of 210

Conditions III.10.C.2.e. and f. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring reflecting performance under operating conditions representative of the extreme range of normal conditions, and include revisions to Permit Tables III.10.K.D and F.

iii. Other Emission Testing

- A. Within seventy-eight (78) months of commencing operation pursuant to Permit Section III.10.K, the Permittees shall resubmit to Ecology for approval the "Previously Approved Demonstration Test Plan" revised as a permit modification in accordance with Permit Conditions III.10.C.2.e. and f. The revised Demonstration Test Plan (RDTP) shall include applicable EPA promulgated test methods and procedures in effect at the time of the submittal, projected commencement and completion dates for emission testing to demonstrate performance standards as specified in Permit Conditions III.10.K.1.b.viii. and ix., and emissions as specified on Permit Table III.10.K.E, as approved/modified pursuant to Permit Conditions III.10.J.3.d. and III.10.C.11.c. or d., not addressed under Permit Conditions III.10.K.1.h.i. or ii. under "Normal Operating Conditions." "Normal Operating Conditions" shall be defined for the purposes of this permit Condition as follows:
 - Carbon monoxide emissions, dangerous and/or mixed waste feed-rate, and automatic waste feed cut-off parameters specified on Permit Table III.10.K.F. as approved/modified pursuant to Permit Condition III.10.J.3.d. and III.10.C.11.c. or d., that were established to maintain compliance with Permit Conditions III.10.K.1.b.viii. and ix., and emissions as specified on Permit Table III.10.K.E, not addressed under Permit Conditions III.10.K.1.h.i. or ii. as specified in Attachment 51, Appendix 10.15 of this Permit, as approved pursuant to Permit Condition III.10.J.3.d., and in accordance with Permit Conditions III.10.K.1.b.xii. and III.10.K.1.c.xi. are held within the range of the average value over the previous twelve (12) months and the set-point value specified on Permit Table III.10.K.F. The average value is defined as the sum of all rolling average values recorded over the previous twelve (12) months divided by the number of rolling averages recorded during that time. The average value shall not include calibration data, malfunction data, and data obtained when not processing dangerous and/or mixed waste; and
 - 2. Feed-rate of metals, ash, and chlorine/chloride are held within the range of the average value over the previous twelve (12) months and the set-point value specified on Permit Table III.10.K.D, as approved/modified pursuant to Permit Conditions III.10.J.3.d. and III.10.C.11.c. or d. Feed-rate of organics as measured by TOC are held within the range of the average value over the previous twelve (12) months. The average value is defined as the sum of the rolling average values recorded over the previous twelve (12) months divided by the number of rolling averages recorded during that time. The average

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 205 of 210

value shall not include data obtained when not processing dangerous and/or 1 2 mixed waste. 3 For purposes of this permit Condition, the "Previously Approved Demonstration 4 Test Plan" is defined to include the Demonstration Test Plan approved pursuant to 5 Permit Condition III.10.J.5.f. Within sixty (60) days of Ecology's approval of the RDTP, or within ninety-one 6 7 (91) months of commencing operation pursuant to Permit Section III.10.K. 8 whichever is later, the Permittees shall implement the RDTP approved pursuant to Permit Condition III.10 K. 1.h.iii.A. 10 The Permittees shall submit a summary of operating data collected pursuant to the 11 RDTPs in accordance with Permit Condition III.10.K.1.h.iii.A to Ecology upon completion of the tests. The Permittees shall submit to Ecology the complete test 12 report within ninety (90) calendar days of completion of the testing. The test 13 reports shall be certified as specified in WAC 173-303-807(8), in accordance with 14 Permit Condition WAC 173-303-680(2) and (3). 15 If any calculations or testing results show that one or more of the performance 16 17 standards listed in Permit Condition III.10.K.1.b., with the exception of Permit Condition III.10.K.1.b.x., for the HLW Vitrification System were not met during 18 19 the emission test, the Permittees shall perform the following actions: 20 Immediately stop dangerous and/or mixed waste feed to the HLW 21 Vitrification System under the mode of operation that resulted in not meeting 22 the performance standard(s). 23 Verbally notify Ecology within twenty-four (24) hours of discovery of not 24 meeting the performance standard(s), as specified Permit Condition I.E.21. 25 Investigate the cause of the failure and submit a report of the investigation 26 findings to Ecology within fifteen (15) days of discovery of not meeting the 27 performance standard(s). 28 Submit to Ecology within fifteen (15) days of discovery of not meeting the 29 performance standard(s) documentation supporting a mode of operation 30 where all performance standards listed in Permit Condition III.10.K.1.b., 31 with the exception of Permit Condition III.10.K.1.b.x., for the HLW 32 Vitrification System were met during the demonstration test, if any such 33 mode was demonstrated. 34 Based on the information provided to Ecology by the Permittees pursuant to 35 Permit Conditions III.10.K.1.h.iii.D.1 through 4 above, and any additional 36 information, Ecology may submit, in writing, direction to the Permittees to 37 stop dangerous and/or mixed waste feed to the HLW Vitrification System 38 and/or amend the mode of operation the Permittees are allowed to continue 39 operations prior to Ecology approval of the revised Demonstration Test Plan, 40 pursuant to Permit Condition III.10.K.1.h.iii.D.6.

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004

Page 206 of 210

	1	
	2	
	3	
	4	
	5	
	6	
	7	
	8	
	9	
1	n	٠,

- 6. Submit to Ecology within one hundred and twenty (120) days of discovery of not meeting the performance standard(s) a revised Demonstration Test Plan requesting approval to retest as a permit modification pursuant to Permit Conditions II.10.C.2.e. and f. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring reflecting performance under operating conditions representative of the extreme range of normal conditions, and include revisions to Permit Tables III.10.K.D and F.
- E. If any calculations or testing results show that any emission rate for any constituent listed in Permit Table III.10.K.E, as approved/modified pursuant to Permit Condition III.10.C.11.c. or d., is exceeded for HLW Vitrification System during the emission test, the Permittees shall perform the following actions:
 - 1. Verbally notify Ecology within twenty-four (24) hours of the discovery of exceeding the emission rate(s) as specified in Permit Condition I.E.21;
 - 2. Submit to Ecology additional risk information to indicate that the increased emissions impact is off-set by decreased emission impact from one or more constituents expected to be emitted at the same time, and/or investigate the cause and impact of the exceedance of the emission rate(s) and submit a report of the investigation findings to Ecology within fifteen (15) days of the discovery of the exceedance of the emission rate(s); and
 - 3. Based on the notification and any additional information, Ecology may submit, in writing, direction to the Permittees to stop dangerous and/or mixed waste feed to the HLW Vitrification System and/or to submit a revised Demonstration Test Plan as a permit modification pursuant to Permit Conditions III.10.C.2.e. and f., or III.10.C.2.g. The revised Demonstration Test Plan must include substantive changes to prevent failure from reoccurring reflecting performance under operating conditions representative of the extreme range of normal conditions, and include revisions to Permit Tables III.10.K.D and F.

Expiration Date: September 27, 2004

Page 207 of 210

1

Table III.10.K.A - HLW Vitrification System Description

Sub-system Description	Subsystem	Engineering Description	Narrative Description, Tables
	Designation	(Drawing Nos., Specification Nos., etc.)	and Figures
Melter Feed ^a System – Melter 1	HFP		Section 4.2.4.1; Table 4-5 & 4-11,
	НСР		Figures 4A-1, 4A-4, 4A-26
HLW Melter I	HMP		Section 4.2.4.2; Figures 4A-1,
			4A-4, 4A-27
HLW Glass Product System-Melter 1	HMP		Section 4.2.4.2; Figures 4A-1, 4A-4, 4A-27
Film Cooler - Melter 1	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-27
Submerged Bed Scrubber /Condensate Collection Vessels ^a -Melter 1	HOP		Section 4.2.4.3; Table 4-5 & 4-11, Figures 4A-1, 4A-4, 4A-28
Wet Electrostatic Precipitator-Melter	HOP		Section 4.2.4.3; Figures 4A-1,
1			4A-4, 4A-28
High Efficiency Particulate Air Filters	HOP		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-29
High Efficiency Mist Eliminator	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-28
Thermal Catalytical Oxidation Unit	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-29
Selective Catalytical Reduction Unit	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-29
Silver Mordenite Column Melter 1 Silver Mordenite Column HLW-MV-	НОР	24590-HLW -M6-HOP-P0008	Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-29
HOP-ABS-00002, Melter 2 Silver Mordenite Column HLW-MV-HOP-		<u>-M6-HOP-P20008</u>	
ABS-00003		<u>-MKD-HOP-P0014</u>	
		<u>-MKD-HOP-P0017</u> -3PS-MBTO-TP001	
	TIOD	<u>-3FS-WB1O-4R001</u>	
Electric Heaters	HOP		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-29
Heat Exchangers	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-29
Pumps	НОР		Section 4.2.4.3; Figures 4A-1,
Booster Fans	НОР		4A-4, 4A-27, 4A-28, 4A-29 Section 4.2.4.3; Figures 4A-1,
·			4A-4, 4A-29
HLW Stack	НОР		Section 4.2.4.3; Figures 4A-1, 4A-4, 4A-29

a. Requirements pertaining to the tanks in HLW Vitrification System Melter Feed System, Submerged Bed

⁵ Scrubber/Condensate Vessels are specified in Permit Section III.10.E.

Permit Number: WA7890008967

Modification to Revision 7

Expiration Date: September 27, 2004
Page 208 of 210

Modification to Revision 7

Expiration Date: September 27, 2004 Page 209 of 210

Table III.10.K.B - HLW Vitrification System Secondary Containment Systems Including Sumps and Floor Drains

Sump/Floor Drain I.D.# & Room Location	Maximum Sump Capacity (gallons)	Sump Dimensions (feet) & Materials of Construction	Engineering Description (Drawing Nos., Specification Nos., etc.)
RESERVED	RESERVED	RESERVED	RESERVED

Table III.10.K.C - HLW Vitrification System Process and Leak Detection System Instruments and Parameters

Sub-system Locator and Name (including P&ID)	Control Parameter	Type of Measuring or Leak Detection Instrument	Location of Measuring Instrument (Tag No.)	Instrument Range	Failure State	Expected Range	Instrument Accuracy	Instrument Calibration Method No. and Range
RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED	RESERVED

Modification to Revision 7

Expiration Date: September 27, 2004

Page 210 of 210

Table III.10.K.D - Maximum Feed-rates to HLW Vitrification System (RESERVED)

	Normal Operation			
Description of Waste				
Dangerous and/or mixed waste Feed Rate				
Ash Feed Rate				
Total Chlorine/Chloride Feed Rate				
Total Metal Feed-rates				

2

Table III.10.K.E- HLW Vitrification System Estimated Emission Rates (RESERVED)

1.				
Chemicals	CAS Number		Emission Rates	
			(grams /second)	
<u> </u>	. 2	*	and the second	
•			1	

6

TABLE III.10.K.F - HLW Vitrification System Waste Feed Cut-off Parameters* (RESERVED)

Sub-system Designation	Instrument Tag Number	Parameter Description	Set-points During Normal Operation	

^{*}A continuous monitoring system shall be used as defined in Permit Section III.10.C.1.

11

10

8

¹Maximum Feed-rate shall be set based on not exceeding any of the constituent (e.g., metals, ash, and chlorine/chloride) feed limits specified on Table III.10.K.D. of this Permit